



SCALES:
 1" = 20' HOR
 1" = 5' VER

- ① PAVEMENT REMOVAL
 LT. & RT. STA. 91+91.93 TO STA. 92+50.00
 LT. STA. 92+50.00 TO STA. 93+12.22
 - ④ COMBINATION CURB AND GUTTER REMOVAL
 STA. 90+12.59, 31.52 RT TO STA. 90+14.11, 38.32 LT
 LT. STA. 91+91.93 TO LT. STA. 93+12.22
 RT. STA. 91+91.93 TO RT. STA. 94+16.94
 - ⑧ PIPE CULVERT REMOVAL
 STA. 90+24.69, 25.13 RT. TO STA. 90+14.69, 24.94 RT.
 - ⑪ TREE REMOVAL
 STA. 91+19.30, 9.70' RT.
- SPLIT RAIL FENCE TO BE REMOVED AND RE-ERECTED
 STA. 92+27.99, 12.96' RT. TO STA. 92+59.34, 13.68 RT.

LEGEND

- ① [Hatched Box] PAVEMENT REMOVAL
- ② [Dotted Box] SIDEWALK REMOVAL
- ③ [Diagonal Lines Box] DRIVEWAY PAVEMENT REMOVAL
- ④ [X-X-X-X Box] COMBINATION CURB AND GUTTER REMOVAL
- ⑥ [Circle with X] REMOVE EXISTING MANHOLE
- ⑧ [Circle with X] PIPE CULVERT REMOVAL
- ⑨ [Circle with X] RETAINING WALL REMOVAL
- ⑩ [Circle with X] STORM SEWER REMOVAL
- ⑪ [Circle with X] TREE REMOVAL
- ⑫ [Circle with X] REMOVE EXISTING INLET

L:\BARTONVILLE\WORK\BARTONVILLE\BARTONVILLE.DWG