ROUTE NO.	SECTION NO.	TOTAL SHEET	SHEET NO.
FAU 6578 FAU 6679	03-00019-1-FP	98	4

FED. ROAD DIST. NO.	COUNTY	PROJECT
	PEORIA	M-5093 (10
	ILLINOIS	

CONTRACT NO. 89369

SUMMARY OF QUANTITIES

CONSTRUCTION CODE Y031-IF

		UNIT	QUANT.
70 106500*	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	1
80500205*	SERVICE INSTALLATION,TYPE B (MODIFIED)	EACH	1
8 1400400*	CONCRETE HANDHOLE	EACH	9
8 1400600*	CONCRETE DOUBLE HANDHOLE	EACH	1
82 102400*	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 400 WATT	EACH	4
82500605*	LIGHTING CONTROLLER, PHOTOCELL RELAY	EACH	1
85700205*	FULL ACTUATED CONTROLLER AND TYPE IV CABINET, SPECIAL	EACH	1
85900 100*	TRANSCEIVER	EACH	1
87900200*	DRILL EXISTING HANDHOLE	EACH	1
882003 10*	TRAFFIC SIGNAL BACKPLATE, LOUVERED, PLASTIC	EACH	8
88800 100*	PEDESTRIAN PUSH-BUTTON	EACH	8
M8 100260*	CONDUIT IN TRENCH, 50 MM, PVC	METER	809
M8 100280*	CONDUIT IN TRENCH, 75 MM, PVC	METER	27
M8 100290*	CONDUIT IN TRENCH, 90 MM, PVC	METER	89
M8 10 1450*	CONDUIT PUSHED, 50 MM DIA., PVC	METER	34
M8 150200*	TRENCH AND BACKFILL FOR ELECTRICAL WORK	METER	896
M8 170040*	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE), 1/C NO.6	METER	370
M873 1240*	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	METER	18 1
M873 1250*	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	METER	637
M873 16 10*	ELECTRIC CABLE IN CONDUIT, COMMUNICATION., NO. 16, 6 PAIR	METER	800
M8750450*	TRAFFIC SIGNAL POST, GALVANIZED 3.0 METER	EACH	3
M8770740*	STEEL COMBINATION MAST ARM ASSEMBLY & POLE, 9.14 M	EACH	1
M8770750*	STEEL COMBINATION MAST ARM ASSEMBLY & POLE, 10.36 M	EACH	1
M8770770*	STEEL COMBINATION MAST ARM ASSEMBLY & POLE, 12.80M	EACH	1
M8770780*	STEEL COMBINATION MAST ARM ASSEMBLY & POLE, 15.24 M	EACH	1
M8780 100*	CONCRETE FOUNDATION, TYPE A	METER	2.7
M8780200*	CONCRETE FOUNDATION , TYPE D	METER	1. 1
MX032922*	ELECTRIC CABLE IN CONDUIT, GROUNDING, NO. 6 1C	METER	237
MX878030*	CONCRETE FOUNDATION, TYPE E, 900 MM DIA.	METER	15.4
X032348 1*	VIDEO VEHICLE DETECTION, 4 CAMERA	EACH	1
X8800020*	SIGNAL HEAD, LED, 1-FACE 3-SECTION MAST ARM MOUNTED	EACH	4
X8800036*	SIGNAL HEAD, LED, 1-FACE 4-SECTION WITH ONE DUAL INDICATION SECTION, MAST ARM MOUNTED	EACH	4
X8800040*	SIGNAL HEAD,LED,1-FACE 5-SECTION BRACKET MOUNTED	EACH	5
X88 10620*	PEDESTRIAN SIGNAL HEAD, LED, 2-FACE, BRACKET MOUNTED	EACH	4

* THESE ITEMS ARE CONSIDERED SPECIALITY ITEMS

SUMMARY OF QUANTITIES

		UNIT	QUANT.