

SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
01-00088-00-WR	CHAMPAIGN	21	6
STA. TO STA.		F.H.W.A. REG. ILLINOIS PROJECT	

# SCHEDULES OF QUANTITIES

PAVEMENT REMOVAL	
LOCATION	SQ YD
LT EOP	222.0
RT EOP	167.0
GATES INTERSECTION	440.0
<b>TOTAL</b>	<b>829.0</b>

CURB REMOVAL INCLUDED IN WORK EFFORT AND PRICE OF PAVEMENT REMOVAL

REMOVING MANHOLES		
STATION		EACH
16.5' LT	10+74	1.0
9.7' LT	11+69	1.0
17.2' LT	13+49	1.0
<b>TOTAL</b>		<b>3.0</b>

CLASS D PATCHES 6"				
PATCH NO.	DIMENSIONS	TYPE II	TYPE III	TYPE IV
		>5-<15	>15-<25	>25
		SQ YD	SQ YD	SQ YD
1	5' x 8'	5.0		
2	10' x 16'		18.0	
3	90' x 8'			80.0
4	24' x 3'	8.0		
5	9' x 5'	5.0		
6	20' x 5'	11.0		
7	13' x 5'	7.2		
8	14' x 5'	7.8		
9	13' x 11'		16.0	
10	13' x 11'		16.0	
11	13' x 10'	14.5		
12	13' x 10'	14.5		
13	12' x 5'	6.7		
14	12' x 5'	6.7		
15	9' x 25'			25.0
16	16' x 5'	8.9		
17	13' x 5'	7.2		
18	14' x 5'	7.8		
19	12' x 5'	6.7		
20	36' x 8'			32.0
21	34' x 8'			30.0
<b>TOTALS</b>		<b>117.0</b>	<b>50.0</b>	<b>167.0</b>

DRIVEWAY PAVEMENT REMOVAL	
STATION	SQ YD
RT 10+21	20.4
RT 10+40	31.3
LT 10+93	52.6
RT 12+34	23.4
RT 13+09	49.9
RT 15+50	52.5
RT 16+60	24.2
RT 100+50	41.8
RT 100+87	25.8
<b>TOTAL</b>	<b>322.0</b>

REMOVING INLETS		
STATION		EACH
15.7' RT	11+40	1.0
13.9' RT	13+48	1.0
17.1' RT	14+52	1.0
15.8' RT	15+98	1.0
12.6' LT	16+00	1.0
<b>TOTAL</b>		<b>5.0</b>

STORM SEWER REMOVAL 10 INCH			TRENCH BACKFILL
STATION	FOOT	CU YD	
AR 11+57	37.0	10.0	
<b>TOTAL</b>	<b>37.0</b>	<b>10.0</b>	

SIDEWALK REMOVAL		
STATION	TO STATION	SQ FT
LT 17+57	LT 17+62	134.5
RT 17+56	RT 17+69	176.2
<b>TOTAL</b>		<b>310.7</b>

STORM SEWER REMOVAL 12 INCH			TRENCH BACKFILL
STATION	FOOT	CU YD	
AR 13+48	28.0	5.0	
<b>TOTAL</b>	<b>28.0</b>	<b>5.0</b>	

TREE REMOVAL, 6-15"		
STATION	UNIT	
30.5' RT	11+48	13.0
35' RT	11+56	9.0
25' LT	11+90	12.0
<b>TOTAL</b>		<b>34.0</b>

COMBINATION CURB & GUTTER REMOVAL	
LOCATION	FOOT
LON AT 136 SW	36.0
LON AT 136 SE	36.0
CAROLINA N.	75.0
CAROLINA S.	90.0
<b>TOTAL</b>	<b>239.0</b>

REMOVING & RESETTING STREET SIGNS	
LOCATION	EACH
LON / GATES	1.0
LON / GROVE	1.0
<b>TOTAL</b>	<b>2.0</b>

MANHOLES TO BE ADJUSTED		
STATION	EACH	
16.0' RT	11+60	1.0
9.5' RT	12+42	1.0
7.3' RT	14+06	1.0
34.3' RT	17+67	1.0
<b>TOTAL</b>	<b>4.0</b>	

BITUMINOUS SURFACE REMOVAL - BUTT JOINT				TEMPORARY RAMP
STATION	LOCATION	SQ YD	SQ YD	
200+67 TO 200+90	CAROLINA	65.7	15.0	
9+42 TO 9+62	W. GATES	56.8	15.0	
101+00 TO 101+10	E. GATES	28.6	6.0	
17+09 TO 17+69	N. LON	246.9	34.0	
<b>TOTAL</b>		<b>398.0</b>	<b>70.0</b>	

INLETS TO BE ADJUSTED WITH NEW TYPE 1 FRAME, OPEN LID		
STATION	EACH	
33.0' RT	13+73	1.0
<b>TOTAL</b>		<b>1.0</b>