

SUMMARY OF QUANTITIES



CITY OF URBANA
PUBLIC WORKS
ENGINEERING DIVISION

DATED: 2/06
DESIGNED BY: CES
DRAWN BY: PLS
CHECKED BY: GLJ
CITY SECTION
95-00305-01-PV

Philo Road Improvements
Summary of Quantities

SHEET NO.
3
OF
62

SUMMARY OF QUANTITIES		SAFETY CODE		2A
		CONSTRUCTION CODE		1000
ITEM NO.	DESCRIPTION	UNIT	TOTAL QUANTITY	ROADWAY 50% FEDERAL 50% CITY
20200100	EARTH EXCAVATION	CU YD	1190	1190
* 20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	575	575
* 20800250	TRENCH BACKFILL, SPECIAL	CU YD	600	600
* 21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	9393	9393
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	177	177
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	177	177
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	177	177
* 25000900	SEEDING, CLASS 1 (SPECIAL)	ACRE	1.9	1.9
25200110	SODDING, SALT TOLERANT	SQ YD	341	341
* 25200200	SUPPLEMENTAL WATERING	UNIT	145	145
* 28000255	TEMPORARY EROSION CONTROL SEEDING	ACRE	1.9	1.9
28000400	PERIMETER EROSION BARRIER	FOOT	1445	1445
28000500	INLET AND PIPE PROTECTION	EACH	27	27
* 28000510	INLET FILTERS	EACH	78	78
31101000	SUB-BASE GRANULAR MATERIAL, TYPE B	TON	2193	2193
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	3069	3069
40600300	AGGREGATE (PRIME COAT)	TON	61	61
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	2	2
40600990	TEMPORARY RAMP	SQ YD	400	400
42000200	PORTLAND CEMENT CONCRETE PAVEMENT 7"	SQ YD	348	348
42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	SQ YD	519	519
42300300	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 7 INCH	SQ YD	624	624
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	13654	13654
* 42400800	DETECTABLE WARNINGS	SQ FT	350	350
* 44000004	BITUMINOUS SURFACE REMOVAL 1"	SQ YD	6546	6546
* 44000006	BITUMINOUS SURFACE REMOVAL 1 1/2"	SQ YD	1306	1306

* SEE SPECIAL PROVISIONS

SUMMARY OF QUANTITIES		SAFETY CODE		2A
		CONSTRUCTION CODE		1000
ITEM NO.	DESCRIPTION	UNIT	TOTAL QUANTITY	ROADWAY 50% FEDERAL 50% CITY
44000100	PAVEMENT REMOVAL	SQ YD	846	846
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	1576	1576
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	1179	1179
44000600	SIDEWALK REMOVAL	SQ FT	7599	7599
* 44004400	PAVEMENT REMOVAL (SPECIAL)	SQ YD	507	507
* 44201329	CLASS C PATCHES, TYPE II, 8 INCH	SQ YD	136	136
* 44201335	CLASS C PATCHES, TYPE IV, 8 INCH	SQ YD	68	68
44300100	AREA REFLECTIVE CRACK CONTROL TREATMENT	SQ YD	409	409
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	5465	5465
* 50104400	CONCRETE HEADWALL REMOVAL	EACH	2	2
* 50105210	REMOVE EXISTING CULVERTS	FOOT	265	265
550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	179	179
550A0090	STORM SEWERS, CLASS A, TYPE 1 18"	FOOT	17	17
550A0340	STORM SEWERS, CLASS A, TYPE 2 12"	FOOT	878	878
550A0360	STORM SEWERS, CLASS A, TYPE 2 15"	FOOT	127	127
* 550A0380	STORM SEWERS, CLASS A, TYPE 2 18"	FOOT	74	74
* 60224600	RESTRICTED DEPTH MANHOLES, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	2	2
* 60224700	RESTRICTED DEPTH MANHOLES, 4'-DIAMETER, TYPE 3 FRAME AND GRATE	EACH	7	7
* 60225100	RESTRICTED DEPTH MANHOLES, 4'-DIAMETER, TYPE 8 GRATE	EACH	1	1
* 60225400	RESTRICTED DEPTH MANHOLES, 5'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	13	13
* 60225900	RESTRICTED DEPTH MANHOLES, 5'-DIAMETER, TYPE 8 GRATE	EACH	3	3
60234200	INLETS, TYPE A, TYPE 1 FRAME, OPEN LID	EACH	5	5
60235300	INLETS, TYPE A, TYPE 1 FRAME, CLOSED LID	EACH	1	1
* 60235700	INLETS, TYPE A, TYPE 3 FRAME AND GRATE	EACH	30	30
60236200	INLETS, TYPE A, TYPE 8 GRATE	EACH	13	13
* 60243910	INLETS, SPECIAL, WITH TYPE 3 FRAME AND GRATE	EACH	1	1

* SEE SPECIAL PROVISIONS