

# SCHEDULE OF QUANTITIES



CITY OF URBANA  
PUBLIC WORKS  
ENGINEERING DIVISION

DATED: 2/06  
DESIGNED BY: CES  
DRAWN BY: PLS  
CHECKED BY: GLJ  
CITY SECTION  
95-00305-01-PV

Philo Road Improvements  
Schedule of Quantities

SHEET NO.  
7  
OF  
62

THERMOPLASTIC PAVEMENT MARKING									
LOCATION	4" SKIP-DASH YELLOW (FOOT)	4" SOLID YELLOW (FOOT)	4" DOUBLE YELLOW NARROW (FOOT)	4" SKIP-DASH WHITE (FOOT)	4" SOLID WHITE (FOOT)	4" LANE LINE EXTENSIONS WHITE (FOOT)	6" CROSSWALK WHITE (FOOT)	12" DIAGONAL YELLOW NARROW (FOOT)	24" STOP BAR WHITE (FOOT)
RT 407+20 TO RT 408+80.6			321.2						
LT 407+20 TO LT 408+80.6			322.4						
RT 408+80.6 TO RT 412+92.4	100	411.8							
LT 408+80.6 TO LT 412+92.4	100	411.8							
407+61.6 TO 804+82.6 CL								67.7	
RT 413+53.2 TO RT 417+48.4	90	360.2							
LT 413+53.2 TO LT 417+48.4	90	360.2							
RT 418+53.2 TO RT 419+25.7	20	72.6							
LT 418+53.2 TO LT 419+25.7	20	72.6							
RT 420+25.6 TO RT 429+70.0	240	944.4							
LT 420+25.6 TO LT 429+70.0	240	944.4							
RT 425+11.2 TO RT 427+80.2						90			
RT 427+80.2 TO RT 429+70.0					190				
RT 430+60.7 TO RT 432+57.0	50	196.3							
LT 430+60.7 TO LT 432+57.0	50	196.3							
RT 430+60.7 TO RT 431+33.0						20			
RT 431+33.0 TO RT 432+57.0					124.2				
RT 433+53.6 TO RT 441+12.5	190	758.9							
LT 433+53.6 TO LT 441+12.5	190	758.9							
441+81.9 TO 444+44.2 CL			1031.9						
441+87.9 TO 442+32.7 CL								15.5	
RT 442+74.4 TO RT 444+44.4				50					
LT 442+74.4 TO LT 444+44.4				50					
PHILO RD/COLORADO AV									30
PHILO RD/COLORADO AV							459.8		
TOTALS	1380	5488.4	1675.5	100	314.2	110	460	83	30

THERMOPLASTIC PAVEMENT MARKING LETTERS AND SYMBOLS		
LOCATION	SYMBOLS (SQ. FT.)	COMMENTS
409+22.5 CL	31.2	DOUBLE LEFT ARROW
410+86.5 CL	31.2	DOUBLE LEFT ARROW
412+50.5 CL	31.2	DOUBLE LEFT ARROW
414+30.3 CL	31.2	DOUBLE LEFT ARROW
415+68.4 CL	31.2	DOUBLE LEFT ARROW
417+6.4 CL	31.2	DOUBLE LEFT ARROW
418+98.4 CL	31.2	DOUBLE LEFT ARROW
420+67.6 CL	31.2	DOUBLE LEFT ARROW
422+83.0 CL	31.2	DOUBLE LEFT ARROW
424+99.0 CL	31.2	DOUBLE LEFT ARROW
427+13.0 CL	31.2	DOUBLE LEFT ARROW
429+28.0 CL	31.2	DOUBLE LEFT ARROW
427+80.2 RT	15.6	RIGHT ARROW
428+37.6 RT	15.6	RIGHT ARROW
428+94.9 RT	15.6	RIGHT ARROW
429+52.3 RT	15.6	RIGHT ARROW
431+33.0 RT	15.6	RIGHT ARROW
431+81.6 RT	15.6	RIGHT ARROW
432+30.1 RT	15.6	RIGHT ARROW
431+2.7 CL	31.2	DOUBLE LEFT ARROW
432+5.58 CL	31.2	DOUBLE LEFT ARROW
433+95.6 CL	31.2	DOUBLE LEFT ARROW
436+20.6 CL	31.2	DOUBLE LEFT ARROW
438+45.6 CL	31.2	DOUBLE LEFT ARROW
440+70.5 CL	31.2	DOUBLE LEFT ARROW
TOTALS	671	