

COUNTY	ROUTE	SECTION NO.	SHT. NO.
ADAMS	FAS 1588	05-00189-00-BR	2 OF 38
SUMMARY OF QUANTITIES			

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	QUANTITIES STRUC. NO 001-3027	QUANTITIES STRUC. NO. 001-3028	TOTAL QUANTITY
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	60	80	140
* 42001400	BRIDGE APPROACH PAVEMENT (SPECIAL)	SQ. YD.	160	160	320
* 44000030	BITUMINOUS SURFACE REMOVAL (VARIABLE DEPTH)	SQ. YD.	527	573	1,100
50102400	CONCRETE REMOVAL	CU. YD.	3.1	3.1	6.2
* 50104720	REMOVAL OF EXISTING CONCRETE DECK	EACH	1	1	2
50300120	PREFORMED JOINT SEAL 2 1/2"	FOOT	31.5	32	63.5
50300130	PREFORMED JOINT SEAL 4"	FOOT	31.5	32	63.5
* 50300255	CONCRETE SUPERSTRUCTURE	CU. YD.	116.0	107.2	223.2
50300260	BRIDGE DECK GROOVING	SQ. YD.	458	421	879
50300300	PROTECTIVE COAT	SQ. YD.	512	471	983
* 50300310	ELASTOMERIC BEARING ASSEMBLY TYPE I	EACH	6	6	12
* 50300320	ELASTOMERIC BEARING ASSEMBLY TYPE II	EACH	6	6	12
50500505	STUD SHEAR CONNECTORS	EACH	2,172	2,016	4,188
* 50500715	JACK AND REMOVE EXISTING BEARINGS	EACH	12	12	24
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	26,880	24,940	51,820
* 50901002	STEEL BRIDGE RAIL (SPECIAL)	FOOT	299	276	575
* 51500100	NAME PLATES	EACH	1	1	2
63000000	STEEL PLATE BEAM GUARDRAIL, TYPE A	FOOT	100	100	200
63100075	TRAFFIC BARRIER TERMINAL, TYPE 5A	EACH	4	4	8
* 63200305	STEEL PLATE BEAM GUARD RAIL REMOVAL	FOOT	200	200	400
67100100	MOBILIZATION	L. SUM			1
* 70101800	TRAFFIC CONTROL AND PROTECTION (SPECIAL)	L. SUM			1
* 70300100	SHORT TERM PAVEMENT MARKING	FOOT	20	30	50
* X4066414	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "C", N50	TON	65	95	160
LR631020	TRAFFIC BARRIER TERMINAL, TYPE 1	EACH	4	4	8

* SPECIAL PROVISIONS
CONSTRUCTION TYPE CODE: X071-2A