

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
567	04-00027-01-PV	MASON	79	6
STA.	TO STA.			
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	MASON COUNTY			CITY OF HAVANA	
				I000	J000	SFTY-1A (1)	MFT (2)	LOCAL (3)
42000306	PORTLAND CEMENT CONCRETE PAVEMENT 8 1/4" (JOINTED)	SQ YD	13367		13367			
42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	SQ YD	140					140
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	158					158
42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SQ FT	6031		176	237		5619
42400800	DETECTABLE WARNINGS	SQ FT	99			99		
44000100	PAVEMENT REMOVAL	SQ YD	13367		13367			
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	435					435
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	635		547 ^Δ			88
44000600	SIDEWALK REMOVAL	SQ FT	6000.6		5618.3			382.3
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	500		500			
44201785	CLASS D PATCHES, TYPE I, 12 INCH	SQ YD	8	4				4
44201789	CLASS D PATCHES, TYPE II, 12 INCH	SQ YD	28	28				
44201796	CLASS D PATCHES, TYPE IV, 12 INCH	SQ YD	84	84				
48101200	AGGREGATE SHOULDERS, TYPE B	TON	113	113				
550A2320	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 1 12"	FOOT	65				56	9
550A2520	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 2 12"	FOOT	734				715	19
550A2540	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 2 18"	FOOT	414				387	27
550A2580	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 2 30"	FOOT	776				776	
56100500	WATER MAIN 4"	FOOT	107					107

- NOTES: (1) MASON COUNTY PEDESTRIAN RAMPS ON EXISTING CURBS
 (2) CITY OF HAVANA STORM SEWER
 (3) CITY OF HAVANA WATER MAIN

•SEE SPECIAL PROVISION
 Δ SPECIALTY ITEMS

REVISIONS	
NAME	DATE
Δ RDJ	4/14/06

ILLINOIS DEPARTMENT OF TRANSPORTATION
 PROMENADE STREET (C.H. 20)
 SUMMARY OF QUANTITIES

SCALE: VERT.
 HORIZ.
 DATE 11/18/05

DRAWN BY RDJ
 CHECKED BY RXC

82:20:45 PM 04/13/2006 02:20 PM
 I:\PROJECTS\14552014\14552014.DWG ADMIN\11/18/05-CALCULATIONS\BOM\SQS\SHEETS.DWG
 LAYOUT JLW 9/6/05
 DRAWN RDJ 11/10/05
 REVIEWED RC 2/3/06