

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
567	04-00027-01-PV	MASON	79	9
STA.	TO STA.			
FED. ROAD DIST. NO.	ILLINOIS FED. AID PROJECT			

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	MASON COUNTY			CITY OF HAVANA	
				I000	J000	SFTY-1A (1)	MFT (2)	LOCAL (3)
•XX001135	PAVEMENT PATCHING SPECIAL	SQ YD	824				682	142
•XX002816	TEMPORARY LINE STOPPER, 4 INCH	EACH	1					1
Δ •XX002982	GATE VALVES, 6"	EACH	16					16
Δ •XX004040	DOMESTIC WATER METER TO BE RELOCATED	EACH	1					1
Δ •XX004690	CONNECTION TO EXISTING WATER MAINS "A" (NON PRESSURE)	EACH	1					1
Δ •XX004691	CONNECTION TO EXISTING WATER MAINS "B" (NON PRESSURE)	EACH	1					1
Δ •XX004692	CONNECTION TO EXISTING WATER MAINS "C" (NON PRESSURE)	EACH	1					1
Δ •XX004693	CONNECTION TO EXISTING WATER MAINS "D" (NON PRESSURE)	EACH	1					1
Δ •XX004694	CONNECTION TO EXISTING WATER MAINS "E" (NON PRESSURE)	EACH	1					1
Δ •XX005450	STORM SEWER WATER MAIN QUALITY 12"	FOOT	68					68
Δ •XX005891	WATER SERVICE RECONNECTIONS	EACH	30					30
•Z0000990	AGGREGATE FOR TEMPORARY ACCESS	TON	544		344			200
•Z0013798	CONSTRUCTION LAYOUT	L SUM	1	0.30	0.30		0.20	0.20
•Z0013825	CONTROLLED LOW-STRENGTH MATERIAL	CU YD	32				32	
•Z0014900	CURB STOPS 3/4"	EACH	31					31
•Z0015000	CURB STOPS 1"	EACH	2					2
•Z0057000	SANITARY SEWER 10"	FOOT	21				21	
+ Z0076600	TRAZAEES	HOUR	500	500				
Δ •XX006535	SANITARY SEWERS, WATER MAIN QUALITY 12"	FOOT	26					26
Δ •XX006536	WATER SERVICE LINE 1" (BORED)	FOOT	58					58

NOTES: (1) MASON COUNTY PEDESTRIAN RAMPS ON EXISTING CURBS
 (2) CITY OF HAVANA STORM SEWER
 (3) CITY OF HAVANA WATER MAIN

•SEE SPECIAL PROVISION
 + Y080
 Δ SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 PROMENADE STREET (C.H. 20)
 SUMMARY OF QUANTITIES

SCALE: VERT.
 HORIZ.
 DATE 11/10/18

DRAWN BY RDJ
 CHECKED BY RXC

12:07:18 PM
 02/02/2006, 12:07 PM
 #FILE#
 LAYOUT JUN 9/6/05
 DRAWN ROJ 11/10/18
 REVIEWED RXC 2/3/06