

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
567	04-0002T-01-PV	MASON	79	14
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

PAVING SCHEDULE

LOCATION	SUB-BASE GRANULAR MATERIAL, TYPE B	AGGREGATE SURFACE COURSE, TYPE A	BITUMINOUS MATERIALS (PRIME COAT)	AGGREGATE (PRIME COAT)	PORTLAND CEMENT CONCRETE PAVEMENT 8 1/4" (JOINTED)	POLYMERIZED BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "D", N50	LEVELING BINDER (MACHINE METHOD), SUPERPAVE N50
PROMENADE STREET							
STA 9+26.62 TO STA 9+80.80			0.2			3.3	
STA 10+00.00 TO STA 12+69.10	252.0				1116.0		
STA 10+00.00 TO STA 12+69.10							
STA 11+21.79 TO STA 11+41.65			0.1			2.0	
STA 12+91.00 TO STA 13+60.54						8.7	
STA 13+51.71 TO STA 16+65.27	289.7				1282.0		
STA 13+51.71 TO STA 16+65.27							
STA 16+65.22 TO STA 17+45.71						10.0	
STA 17+46.42 TO STA 20+65.09	296.4						
STA 17+46.42 TO STA 20+65.09					1311.0		
STA 20+65.09 TO STA 21+64.32						12.3	
STA 21+64.32 TO STA 24+92.32	307.1				1358.0		
STA 21+64.32 TO STA 24+92.32							
STA 24+07.48 TO STA 24+23.70		4.5					
STA 24+75.34 TO STA 24+92.32		4.3					
STA 24+92.12 TO STA 25+71.36						9.9	
STA 25+77.00 TO STA 28+87.83	291.1						
STA 25+77.00 TO STA 28+87.83					1288.0		
STA 27+14.87 TO STA 27+27.38		2.9					
STA 28+87.85 TO STA 29+97.48						13.6	
STA 29+97.47 TO STA 36+83.25	642.2						
STA 29+97.47 TO STA 36+83.25					2830.0		
STA 31+73.06 TO STA 31+83.47		2.9					
STA 36+89.07 TO STA 37+61.35						9.0	
STA 37+34.52 TO STA 38+02.60		34.9					
STA 38+08.12 TO STA 38+64.33			0.1	0.4		20.2	
STA 38+64.33 TO STA 55+00.00			1.7	8.7		488.5	
STA 38+96.35 TO STA 54+92.15			5.2			90.1	
STA 47+40.00 TO STA 48+50.00							3.9
STA 47+40.00 TO STA 49+70.00			0.1	0.6			6.7
STA 47+60.00 TO STA 48+35.00							5.9
STA 47+60.00 TO STA 49+70.00			0.1	0.6			4.2
STA 48+35.00 TO STA 48+80.00							6.0
STA 48+50.00 TO STA 49+10.00							
STA 48+80.00 TO STA 49+15.00							
STA 49+03.36 TO STA 49+86.53				2.0			
STA 49+03.36 TO STA 49+86.53				2.0			
STA 49+10.00 TO STA 49+70.00							3.8
STA 49+15.00 TO STA 49+70.00							7.1
STA 55+00.00 TO STA 61+78.13			0.8	4.1		228.7	
SUBTOTAL	2078.4	49.5	8.4	18.4	9185.0	896.4	37.6
PROMENADE STREET (DUE TO WATER MAIN)							
STA 24+07.48 TO STA 24+23.70		1.0					
STA 24+75.34 TO STA 24+92.32		0.7					
SUBTOTAL		1.7					
INTERSECTIONS							
PROMENADE STREET / LAUREL STREET			0.2	0.8		3.7	
PROMENADE STREET / WASHINGTON STREET	141.8		0.3	1.3	622.6	6.1	
PROMENADE STREET / ADAMS STREET	135.6		0.3	1.5	595.2	7.1	
PROMENADE STREET / MARKET STREET	193.2		0.3	1.6	848.0	7.1	
PROMENADE STREET / JEFFERSON STREET	155.8		0.3	1.5	683.6	7.0	
PROMENADE STREET / FRANKLIN STREET	171.9		0.3	1.4	737.5	6.4	
PROMENADE STREET / MAIN STREET	158.2		0.3	1.2	694.7	5.8	
SUBTOTAL	956.5		2.1	9.3	4181.9	43.3	
TOTAL	3035	51	10.4	27.7	13367	940	38

PROPOSED PCC SIDEWALK 4" SCHEDULE

LOCATION	PCC SIDEWALK 4" (SQ FT)
PROMENADE STREET (DUE TO WATER MAIN)	
LT STA 6+74.40 TO LT STA 7+47.04	290.6
LT STA 7+64.09 TO LT STA 8+04.52	161.7
LT STA 8+27.28 TO LT STA 8+82.63	141.4
LT STA 8+82.95 TO LT STA 9+36.43	249.9
LT STA 9+72.27 TO LT STA 10+48.80	306.1
LT STA 10+82.79 TO LT STA 11+14.18	125.6
LT STA 11+39.12 TO LT STA 12+80.17	602.8
LT STA 13+36.77 TO LT STA 15+26.56	820.6
LT STA 15+37.51 TO LT STA 15+65.80	113.2
LT STA 15+74.39 TO LT STA 16+78.64	462.4
LT STA 17+46.21 TO LT STA 18+78.02	515.5
LT STA 18+88.28 TO LT STA 19+48.83	242.2
LT STA 19+57.26 TO LT STA 19+84.14	107.5
LT STA 19+96.24 TO LT STA 20+79.39	332.6
LT STA 21+56.83 TO LT STA 22+36.22	317.6
LT STA 22+50.11 TO LT STA 23+12.20	248.4
LT STA 29+65.54 TO LT STA 30+51.67	319.1
LT STA 30+70.33 TO LT STA 31+25.71	221.5
LT STA 7+06.24 TO LT STA 7+10.10	11.2
LT STA 17+29.88 TO LT STA 17+34.68	11.4
LT STA 18+50.27 TO LT STA 18+56.28	10.3
LT STA 22+86.95 TO LT STA 22+88.94	6.9
SUBTOTAL	5618.3
PROMENADE STREET (DUE TO ROADWAY)	
LT STA 12+80.17 TO LT STA 12+89.36	36.5
LT STA 13+31.83 TO LT STA 13+36.77	18.4
LT STA 16+78.64 TO LT STA 16+85.04	26.9
LT STA 17+33.63 TO LT STA 17+46.21	35.6
LT STA 24+99.64 TO LT STA 25+02.33	29.0
RT STA 25+59.26 TO RT STA 25+63.05	94.0
LT STA 25+60.14 TO LT STA 25+73.41	70.6
RT STA 28+95.59 TO RT STA 29+05.09	30.0
LT STA 29+54.46 TO LT STA 29+65.54	35.1
RT STA 29+55.70 TO RT STA 29+59.10	13.6
LT STA 31+52.28 TO LT STA 31+55.28	22.6
SUBTOTAL	412.3
TOTAL	6031

DRIVEWAY PAVEMENT REMOVAL SCHEDULE

LOCATION	DRIVEWAY PAVEMENT REMOVAL (SQ YD)
PROMENADE STREET	
LT STA 7+55.69	27.9
LT STA 8+15.90	35.6
LT STA 8+72.79	38.2
LT STA 9+54.35	54.6
LT STA 10+67.31	56.5
LT STA 11+26.65	35.0
LT STA 15+32.06	19.7
LT STA 15+76.04	21.3
LT STA 18+83.15	5.3
LT STA 18+83.15	2.2
LT STA 19+53.05	5.2
LT STA 19+53.05	1.9
LT STA 19+90.19	6.2
LT STA 19+90.19	2.9
LT STA 22+42.50	7.4
LT STA 22+42.50	3.1
LT STA 23+20.10	10.0
LT STA 23+20.10	1.9
LT STA 23+36.50	9.0
LT STA 23+36.50	1.8
LT STA 24+08.58	13.1
LT STA 24+08.58	3.0
LT STA 24+81.01	12.6
LT STA 24+81.01	2.1
LT STA 26+20.90	9.9
LT STA 27+21.65	8.5
LT STA 30+61.00	13.0
LT STA 31+73.53	8.4
LT STA 32+09.34	19.2
TOTAL	435.4

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 PROMENADE STREET (C.H. 20)
 SCHEDULE OF QUANTITIES
 SCALE: VERT. DATE 11/7/05
 HORIZ. DATE 11/7/05
 DRAWN BY RDJ
 CHECKED BY RXC

10/26/17 AM
 821/10/2006, 10+20 AM
 8 FILES
 LAYOUT 8/04/05
 RET 8/04/05
 DRAWN 11/17/05
 REVIEWED 11/18/05