

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
567	04-00027-01-PV	MASON	79	79
STA. TO STA.				
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				

PAVEMENT MARKING SCHEDULE

LOCATION							SHORT-TERM PAVEMENT MARKING (FOOT)	TEMPORARY PAVEMENT MARKING LINE 4" (FOOT)	WORK-ZONE PAVEMENT MARKING REMOVAL (SQ FT)	PAINT PAVEMENT MARKING - LINE 4" (FOOT)	PAINT PAVEMENT MARKING - LINE 6" (FOOT)	PAINT PAVEMENT MARKING - LINE 24" (FOOT)	LOCATION												
PROMENADE STREET												PROMENADE STREET (CONTINUED)													
STA	9+90.00	17.00'	LT TO	STA	12+69.10	17.00'	LT		279				STA	24+98.47	19.13'	LT TO	STA	25+04.26	21.56'	RT					6.3
STA	9+90.00	5.00'	LT TO	STA	12+69.10	5.00'	LT		279				STA	25+04.29	20.80'	LT TO	STA	25+10.61	23.72'	RT					7.0
STA	10+00.00	17.00'	RT TO	STA	12+69.10	17.00'	RT		269	93.0			STA	25+04.29	20.80'	LT TO	STA	25+57.64	19.12'	LT					53.4
STA	10+00.00	5.00'	RT TO	STA	12+69.10	5.00'	RT		269	93.0			STA	25+09.61	26.63'	LT TO	STA	25+56.31	25.16'	LT					46.7
STA	9+90.00	0.00'	CL TO	STA	61+78.13	0.00'	CL	1038					STA	25+10.61	23.72'	RT TO	STA	25+59.22	19.57'	RT					48.8
STA	9+90.00	0.00'	CL TO	STA	61+78.13	0.00'	CL				10010		STA	25+11.73	29.65'	RT TO	STA	25+56.35	25.83'	RT					44.8
STA	12+89.60	29.21'	LT TO	STA	13+31.96	28.60'	LT					42.4	STA	25+11.83	30.56'	LT TO	STA	25+33.09	29.89'	LT					21.0
STA	12+91.66	35.18'	LT TO	STA	13+29.46	34.64'	LT					37.8	STA	25+34.05	31.74'	RT TO	STA	25+52.61	31.72'	RT					19.0
STA	12+91.77	38.87'	LT TO	STA	13+10.35	38.91'	LT					19.0	STA	25+57.64	19.12'	LT TO	STA	25+59.22	19.57'	RT					1.6
STA	13+22.67	22.83'	RT TO	STA	13+41.43	22.77'	RT					19.0	STA	25+63.62	19.89'	LT TO	STA	25+65.24	19.80'	RT					1.6
STA	13+52.12	5.00'	LT TO	STA	16+65.27	5.00'	LT						STA	25+69.32	5.00'	LT TO	STA	28+81.31	5.00'	LT		312			
STA	13+52.12	17.00'	LT TO	STA	16+65.27	17.00'	LT						STA	25+69.32	17.00'	LT TO	STA	28+81.31	17.00'	LT		312			
STA	13+52.12	5.00'	RT TO	STA	16+65.27	5.00'	RT						STA	25+69.32	5.00'	RT TO	STA	28+81.31	5.00'	RT		312	104.0		
STA	13+52.12	17.00'	RT TO	STA	16+65.27	17.00'	RT						STA	25+69.32	17.00'	RT TO	STA	28+81.31	17.00'	RT		312	104.0		
STA	16+85.86	32.49'	LT TO	STA	17+35.69	20.96'	LT					51.1	STA	29+03.45	23.76'	RT TO	STA	29+53.88	21.18'	RT					50.5
STA	16+87.22	38.33'	LT TO	STA	17+26.92	29.15'	LT					40.7	STA	29+08.13	29.51'	RT TO	STA	29+52.75	27.24'	RT					44.7
STA	17+06.16	22.24'	RT TO	STA	17+33.77	22.21'	RT					28.0	STA	29+10.30	35.83'	LT TO	STA	29+29.09	35.83'	LT					19.0
STA	17+46.42	5.00'	LT TO	STA	20+65.09	5.00'	LT						STA	29+30.44	32.38'	RT TO	STA	29+49.44	32.38'	RT					19.0
STA	17+46.42	17.00'	LT TO	STA	20+65.09	17.00'	LT						STA	29+57.72	21.33'	LT TO	STA	29+59.93	22.09'	RT					2.3
STA	17+46.42	5.00'	RT TO	STA	20+65.09	5.00'	RT						STA	29+68.21	5.00'	LT TO	STA	38+89.26	5.00'	LT		721			
STA	17+46.42	17.00'	RT TO	STA	20+65.09	17.00'	RT						STA	29+68.21	17.00'	LT TO	STA	38+89.26	17.00'	LT		721			
STA	20+71.27	19.13'	LT TO	STA	20+76.63	20.93'	RT					5.7	STA	29+68.21	5.00'	RT TO	STA	38+89.26	5.00'	RT		721	240.3		
STA	20+77.22	19.92'	LT TO	STA	20+83.03	23.51'	RT					6.8	STA	29+68.21	17.00'	RT TO	STA	38+89.26	17.00'	RT		721	240.3		
STA	20+77.22	19.92'	LT TO	STA	21+59.52	19.46'	LT					82.3	STA	37+02.56	37.69'	LT TO	STA	37+18.47	37.72'	LT					16.0
STA	20+82.90	25.89'	LT TO	STA	21+49.32	25.52'	LT					66.4	STA	37+20.53	35.42'	RT TO	STA	37+39.27	35.43'	RT					19.0
STA	20+83.03	23.51'	RT TO	STA	21+56.33	20.45'	RT					73.4	STA	37+52.08	5.00'	LT TO	STA	38+08.12	5.00'	LT		56			
STA	20+85.83	29.87'	LT TO	STA	21+11.54	29.54'	LT					26.0	STA	37+52.08	17.00'	LT TO	STA	38+08.12	17.00'	LT		56			
STA	20+86.02	29.39'	RT TO	STA	21+48.80	26.77'	RT					62.8	STA	37+52.08	5.00'	RT TO	STA	38+08.12	5.00'	RT		56	18.7		
STA	21+23.02	31.14'	RT TO	STA	21+45.84	31.43'	RT					23.0	STA	37+52.08	17.00'	RT TO	STA	38+08.12	17.00'	RT		56	18.7		
STA	21+56.33	20.45'	RT TO	STA	21+60.78	19.17'	LT					4.6	STA	38+56.25	12.00'	LT TO	STA	61+78.13	12.00'	LT			2322		
STA	21+62.56	18.57'	RT TO	STA	21+66.77	18.75'	LT					4.2	STA	38+64.33	12.00'	RT TO	STA	61+78.13	12.00'	RT			2314		
STA	21+64.32	5.00'	LT TO	STA	24+92.32	5.00'	LT																		
STA	21+64.32	17.00'	LT TO	STA	24+92.32	17.00'	LT																		
STA	21+64.32	5.00'	RT TO	STA	24+92.32	5.00'	RT																		
STA	21+64.32	17.00'	RT TO	STA	24+92.32	17.00'	RT																		
							TOTAL	1038	9292	1552	14646	786	228												

09143111.dwg
 02/06/2005, 09:43 AM
 #FILES
 LAYOUT KET 8/04/05
 DRAWN RDJ 11/18/05
 REVIEWED RXC 11/18/05

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

PROMENADE STREET (C.H. 20)
 SCHEDULE OF QUANTITIES

SCALE: VERT.
 HORIZ.
 DATE 11/18/05

DRAWN BY RDJ
 CHECKED BY RXC