

F.A.E. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	182 & 18Y, RS 282	MARION	222	19A
STA.	TO STA.			
IDOT DIST. NO. 1	ILLINOIS FED. AID PROJECT			
CONTRACT NO. 94700				

US ROUTE 51 ENTRANCE SCHEDULE

STATION	SIDE	TYPE	L1	L2	W1	W2	RADII		PAVEMENT AREA	PAVEMENT AREA 2	AGGREGATE BASE COURSE, TYPE B, 8"	BITUMINOS MATERIALS COMPLETE	PCC PAVEMENT 8" (SE)	PAVEMENT FABRIC	PCC DRIVEWAY PAVEMENT, 6" (PE)	PCC DRIVEWAY PAVEMENT, 8" (CE)	TEMPORARY ACCESS (PRIVATE ENTRANCE)	TEMPORARY ACCESS (COMMERCIAL ENTRANCE)	TRMPORARY ACCESS (ROAD)
							LT	RT											
1339+27.23	LT	PE	25.00		47.00	17.00	15	15	521.57						58.0		1		
1341+28.96	LT	PE	25.00		32.00	12.00	10	10	342.92						38.1		1		
1341+37.50	RT	CE	25.00		48.00	14.00	15	15	474.04							52.7		1	
1342+45.66	RT	CE	25.00		74.00	31.00	20	20	982.73							109.2		1	
1342+71.11	LT	PE	25.00		32.00	12.00	10	10	342.92						38.1		1		
1343+14.35	RT	CE	24.50		58.00	23.00	15	15	687.54							76.4		1	
1343+95.46	RT	SE	34.50	20.00		35.00	30	30	1593.78	736.71	81.9	9.2	177.1	177.1					1
1344+09.38	LT	PE	26.00		48.50	18.00	15	15	564.57						62.7		1		
1345+32.25	LT	PE	25.00		45.00	15.00	15	15	471.57						52.4		1		
1346+05.23	LT	PE	25.00		32.00	12.00	10	10	342.92						38.1		1		
1346+33.79	LT	PE	25.00		28.50	12.00	10	10	342.92						38.1		1		
1347+54.81	RT	PE	25.00		32.00	12.00	10	10	342.92						38.1		1		
1347+62.02	LT	PE	25.00		45.00	15.00	15	15	471.57						52.4		1		
1348+77.87	RT	SE	27.00			26.00	30	30	1088.28		0.0	0.0	120.9	120.9					1
TOTALS											543.3	60.8	1627.4	1627.4	657.5	2602.2	14	33	11

BITUMINOUS MATERIALS AND AGGREGATE (PRIME COAT) FOR ENTRANCES AND PUBLIC ROAD APPROACHES SHALL BE CONSIDERED INCIDENTAL TO THE COST OF BITUMINOUS MIXTURE COMPLETE

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		URBAN ENTRANCE DETAILS & SCHEDULES

SCALE: VERT. _____
HORIZ. _____
DATE _____

DRAWN BY _____
CHECKED BY _____

REVISED 3/28/06