



| | | | |
|--------------------|---------------------------|---------|-----------------|
| F.A.D. RTE. | SECTION | COUNTY | TOTAL SHEET NO. |
| 322 | 18Z & 18Y, RS 28Z | MARION | 222 11 |
| STA. | 2318+60.19 | TO STA. | 2324+09.63 |
| DOT DIST. NO. 7 | ILLINOIS FED. AID PROJECT | | |
| CONTRACT NO. 94700 | | | |



TYPICAL SECTION

FROM STATION 2318+60.12
TO STATION 2322+43.19



TYPICAL SECTION

FROM STATION 2322+43.90
TO STATION 2324+04.83

- ① EXISTING PAVEMENT
- ② EXISTING AGGREGATE SHOULDER-TO BE REMOVED
- ③ ORIGINAL CONCRETE ROADWAY
- ④ EXISTING 2' CONCRETE WIDENING
- ⑤ EXISTING ASPHALT SHOULDER- REMOVE 11' FROM EXISTING CENTERLINE
- ⑥ EXISTING SIDEWALK
- ⑦ BITUMINOUS SURFACE REMOVAL (VARIABLE DEPTH)
- ⑧ BITUMINOUS CONCRETE BINDER COURSE, SUPERPAVE IL-19.0, N70- DEPTH VARIES
- ⑨ LEVELING BINDER (MACHINE METHOD), SUPERPAVE N90, (MINIMUM 1" & VARIES)
- ⑩ BITUMINOUS CONCRETE SURFACE COURSE SUPERPAVE MIXTURE D, N90 1.50"
- ⑪ BITUMINOUS CONCRETE BASE COURSE WIDENING, SUPERPAVE, 12"
- ⑫ BITUMINOUS SHOULDER, 6 1/2"
- ⑬ AGGREGATE SHOULDER, TYPE B, 8"
- ⑭ EARTH FILL
- ⑮ COMBINATION CONCRETE CURB AND GUTTER, TYPE B6.24
- ⑯ EXISTING CONCRETE CURB AND GUTTER
- ⑰ SUB-BASE GRANULAR MATERIAL, TYPE B, 12"
- ⑱ SUB-BASE GRANULAR MATERIAL, TYPE C
- ⑲ BITUMINOUS CONCRETE BASE COURSE SUPERPAVE, 12"

STRUCTURAL DESIGN INFORMATION

STRUCTURAL DESIGN TRAFFIC: YEAR 2015 ADT = 8134
 PV = 85.5% SU = 6.6% MU = 7.8%
 ROAD / STREET CLASSIFICATION: CLASS II
 PERCENT STRUCTURAL DESIGN TRAFFIC IN DESIGN LANE
 PV = 0.5 SU = 0.5 MU = 0.5
 MINIMUM SOIL SUPPORT: IBR = 2
 MINIMUM TRAFFIC FACTOR = 3.81

| REVISIONS | |
|-----------|------|
| NAME | DATE |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |

ILLINOIS DEPARTMENT OF TRANSPORTATION
 TYPICAL SECTIONS
 U.S. ROUTE 51

SCALE: VERT. DRAWN BY ALM
 HORIZ. CHECKED BY MJM
 DATE 6/27/03

REVISED 12/20/05