

US ROUTE 51 ENTRANCE SCHEDULE

F.A.P. NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	18Z & 18Y, RS 28Z	MARION	222	19
STA.	TO STA.			
ILLINOIS DOT DIST. NO. 7	ILLINOIS FED. AID PROJECT			
CONTRACT NO. 94700				

STATION	SIDE	TYPE	L1	L2	W1	W2	RADIUS		PAVEMENT AREA SQ. FT.	PAVEMENT AREA 2 SQ. FT.	DEPRESSED CURB AND GUTTER PAID FOR AS PAVEMENT SQ. FT.	AGGREGATE BASE COURSE, TYPE B, 8" SQ YD	BITUMINOS MATERIALS COMPLETE TON	PCC PAVEMENT 8" (SE) SQ. YD.	PAVEMENT FABRIC SQ. YD.	PCC DRIVEWAY PAVEMENT, 6" (PE) SQ. YD.	PCC DRIVEWAY PAVEMENT, 8" (CE) SQ. YD.	TEMPORARY ACCESS (PRIVATE ENTRANCE) EACH	TEMPORARY ACCESS (COMMERCIAL ENTRANCE) EACH	TRMPORARY ACCESS (ROAD) EACH
							LT	RT												
2309+40.00	RT	CE	17.00		74.00	31.00	20	20	642.05		185.00						91.9		1	
2310+88.96	RT	CE	17.00		69.00	31.00	20	20	609.56		172.50						86.9		1	
2311+43.27	LT	CE	22.50		75.50	30.00	20	20	846.68		188.75						115.0		1	
2311+91.26	RT	CE	17.00		60.00	30.00	15	15	606.57		150.00						84.1		1	
2312+51.50	RT	CE	17.00		60.00	30.00	15	15	606.57		150.00						84.1		1	
2312+54.75	LT	CE	23.00		68.00	24.00	20	20	723.68		170.00						99.3		1	
2313+45.95	RT	CE	17.00		54.00	20.00	15	15	436.57		135.00						63.5		1	
2314+05.00	LT	CE	23.00		68.00	24.00	20	20	723.68		170.00						99.3		1	
2314+90.55	RT	CE	17.00		54.00	20.00	15	15	436.57		135.00						63.5		1	
2316+09.03	LT	CE	23.00		68.00	24.00	20	20	723.68		170.00						99.3		1	
2316+13.64	RT	SE	32.00	22.00		26.00	30	30	1218.28	503.17		55.9	6.3	135.4	135.4					1
2316+85.63	RT	CE	17.00		58.00	24.00	15	15	504.57		145.00						72.2		1	
2317+72.77	RT	CE	17.00		58.00	24.00	15	15	504.57		145.00						72.2		1	
2318+84.63	LT	SE	32.00	38.00		28.00	30	30	1282.28	866.70		96.3	10.8	142.5	142.5					1
2318+86.35	RT	SE	34.00	25.00		26.00	30	30	1270.28	557.17		61.9	6.9	141.1	141.1					1
2319+62.94	RT	CE	21.50		64.00	26.00	15	15	655.57		160.00						90.6		1	
2319+67.89	LT	CE	23.50		68.50	26.00	20	20	782.68		171.25						106.0		1	
2320+60.22	LT	CE	23.00		71.00	29.00	20	20	838.68		177.50						112.9		1	
2320+64.88	RT	CE	16.00		51.50	21.00	15	15	432.57		128.75						62.4		1	
2321+17.46	RT	CE	31.00		58.00	26.00	15	15	902.57		145.00						116.4		1	
2321+31.61	LT	CE	23.50		73.00	31.00	20	20	900.18		182.50						120.3		1	
2322+38.91	LT	CE	23.50		73.50	37.00	20	20	1041.18		183.75						136.1		1	
2323+18.34	LT	CE	23.50		58.00	24.00	15	15	660.57		145.00						89.5		1	
2323+77.29	RT	CE	20.00		75.00	27.00	20	20	711.68		187.50						99.9		1	
2323+79.31	LT	CE	15.50		55.00	31.00	10	10	523.42		137.50						73.4		1	
2324+57.26	LT	CE	15.50		54.50	31.00	10	10	523.42		136.25						73.3		1	
2325+11.30	LT	CE	15.50		54.50	31.00	10	10	523.42		136.25						73.3		1	
2325+36.06	RT	SE	37.00	10.00		26.00	30	30	1348.28	239.15		26.6	3.0	149.8	149.8					1
2325+74.15	LT	CE	15.50		60.50	31.00	10	15	523.42		151.25						75.0		1	
2326+25.95	RT	CE	20.00		75.50	31.00	20	20	791.68		188.75						108.9		1	
2327+23.34	LT	CE	28.00		65.50	25.00	15	20	796.57		163.75						106.7		1	
2328+24.90	RT	SE	39.00	4.00		26.00	30	30	1400.28	105.42		11.7	1.3	155.6	155.6					1
2328+78.67	LT	SE	38.00	13.00		26.00	30	30	1374.28	318.01		35.3	4.0	152.7	152.7					1
1331+40.92	RT	CE	27.00		75.00	34.00	20	20	1089.68		187.50						141.9		1	
1331+77.47	LT	CE	22.00		75.00	31.00	20	20	853.68		187.50						115.7		1	
1332+64.49	RT	SE	40.00	20.00		26.00	30	30	1426.28	476.24		52.9	5.9	158.5	158.5					1
1333+52.74	RT	SE	39.00	24.00		26.00	30	30	1400.28	545.98		60.7	6.8	155.6	155.6					1
1334+47.96	RT	CE	26.00		45.00	11.00	15	15	382.57		112.50						55.0		1	
1335+21.36	RT	PE	25.00		35.00	15.00	10	10	417.92						46.4			1		
1335+86.32	RT	PE	27.00	27.00		35.00	10	10	447.92	474.19		52.7	5.9		49.8			1		
1336+48.41	RT	PE	25.00		48.00	18.00	15	15	546.57						60.7			1		
1337+29.03	RT	PE	25.00		32.00	12.00	10	10	342.92						38.1			1		
1337+56.21	LT	PE	25.00		35.00	15.00	10	10	417.92						46.4			1		

BITUMINOUS MATERIALS AND AGGREGATE (PRIME COAT) FOR ENTRANCES AND PUBLIC ROAD APPROACHES SHALL BE CONSIDERED INCIDENTAL TO THE COST OF BITUMINOUS MIXTURE COMPLETE

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

URBAN ENTRANCE DETAILS
& SCHEDULES

SCALE: VERT. _____
HORIZ. _____

DATE _____

DRAWN BY _____
CHECKED BY _____

REVISED 12/20/05