

| F.A.P. RTE | SECTION | COUNTY | TOTAL SHEETS | SHEET NO |
|------------|---------|---------|--------------|----------|
| 331 | * | JACKSON | 258 | 5 |

FED. ROAD DIST. NO. - ILLINOIS FED. AID PROJECT

* (12-112N, I-5, TS-3, B-1)

| CODE NO | ITEM | CONSTRUCTION TYPE CODE | | 1000-2A | 1000-2A | X071-2A | Y031-1F | Y031-1F | Y030-1E | Y030-1E | SFTY-1B |
|----------|---|------------------------|------------------|--|---|---|---|--|---|---|---|
| | | UNIT | TOTAL QUANTITIES | ILL 13 ROADWAY 80% FED 20% STATE | EMERALD/SYCAMORE 80% FED 20% CITY | BRIDGE SN (039-0071) 80% FED 20% STATE | TRAFFIC SIGNALS EMERALD/SYCAMORE 80% FED 10% STATE 10% CITY | TRAFFIC SIGNALS GLENVIEW 80% FED 13.33% STATE 6.66% CITY | LIGHTING EMERALD/SYCAMORE 80% FED 20% CITY | LIGHTING GLENVIEW 80% FED 20% CITY | SIDEWALK 100% STATE UP TO \$150,000 REMAINDER 100% CITY |
| 550A0050 | STORM SEWER, CLASS A, TYPE 1, 12" | FOOT | 126 | 115 | 11 | | | | | | |
| 550A0070 | STORM SEWER, CLASS A, TYPE 1, 15" | FOOT | 56 | 56 | | | | | | | |
| 550A0120 | STORM SEWER, CLASS A, TYPE 1, 24" | FOOT | 24 | 24 | | | | | | | |
| 550A0340 | STORM SEWER, CLASS A, TYPE 2, 12" | FOOT | 14 | 14 | | | | | | | |
| 550A0360 | STORM SEWER, CLASS A, TYPE 2, 15" | FOOT | 322 | 322 | | | | | | | |
| 550A0430 | STORM SEWER, CLASS A, TYPE 2, 30" | FOOT | 22 | 22 | | | | | | | |
| 55100500 | STORM SEWER REMOVAL, 12" | FOOT | 250 | 234 | 16 | | | | | | |
| 55100700 | STORM SEWER REMOVAL, 15" | FOOT | 664 | 664 | | | | | | | |
| 55100900 | STORM SEWER REMOVAL, 18" | FOOT | 593 | 593 | | | | | | | |
| 55101100 | STORM SEWER REMOVAL, 21" | FOOT | 6 | 6 | | | | | | | |
| 55101200 | STORM SEWER REMOVAL, 24" | FOOT | 42 | 42 | | | | | | | |
| 55101300 | STORM SEWER REMOVAL, 27" | FOOT | 12 | 12 | | | | | | | |
| 55101400 | STORM SEWER REMOVAL, 30" | FOOT | 6 | 6 | | | | | | | |
| 59100100 | GEOCOMPOSITE WALL DRAIN | SQ YD | 227 | | | 227 | | | | | |
| 60109580 | PIPE UNDERDRAINS FOR STRUCTURES, 4" | FOOT | 360 | | | 360 | | | | | |
| 60242500 | INLETS SPECIAL NO. 1 | EACH | 1 | 1 | | | | | | | |
| 60242600 | INLET SPECIAL NO. 2 | EACH | 1 | 1 | | | | | | | |
| X0325301 | INLETS SPECIAL, TY3, 5' (MODIFIED) | EACH | 4 | | 4 | | | | | | |
| 60243500 | INLET SPECIAL, TYPE 3, 6' | EACH | 17 | 16 | 1 | | | | | | |
| 60500060 | REMOVING INLETS | EACH | 27 | 25 | 2 | | | | | | |
| 60500065 | REMOVING INLETS SPECIAL | EACH | 3 | 1 | 2 | | | | | | |
| 60603800 | COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12 | FOOT | 1719 | 690 | | | | | | | 1029 |
| 60605000 | COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24 | FOOT | 3987 | 3498 | 489 | | | | | | |
| 60608600 | COMBINATION CONCRETE CURB AND GUTTER, TYPE M-6.06 | FOOT | 328 | 328 | | | | | | | |
| 60618300 | CONCRETE MEDIAN SURFACE, 4" | SQ FT | 4665 | 4665 | | | | | | | |
| 63000000 | STEEL PLATE BEAM GUARD RAIL, TYPE A | FOOT | 487.5 | 287.5 | | 200 | | | | | |
| 63100045 | TRAFFIC BARRIER TERMINAL, TYPE 2 | EACH | 1 | 1 | | | | | | | |
| 63100085 | TRAFFIC BARRIER TERMINAL, TYPE 6 | EACH | 2 | | | 2 | | | | | |
| 63100167 | TRAFFIC BARRIER TERMINAL, TYPE 1, SPECIAL (TANGENT) | EACH | 2 | | | 2 | | | | | |
| 63100169 | TRAFFIC BARRIER TERMINAL, TYPE 1, SPECIAL (FLARED) | EACH | 1 | 1 | | | | | | | |
| 63200310 | GUARD RAIL REMOVAL | FOOT | 426 | | | 426 | | | | | |
| 66900450 | SPECIAL WASTE PLANS AND REPORTS | L SUM | 1 | 1 | | | | | | | |
| 66900510 | BETX-PNAS SOIL ANALYSIS | EACH | 2 | 2 | | | | | | | |
| 66900530 | SOIL DISPOSAL ANALYSIS | EACH | 1 | 1 | | | | | | | |
| 66900635 | LEAD TCLP SOIL ANALYSIS | EACH | 2 | 2 | | | | | | | |
| 69900105 | NON-SPECIAL WASTE DISPOSAL | CU YD | 27 | 27 | | | | | | | |
| 67000400 | ENGINEER'S FIELD OFFICE, TYPE A | CAL MO | 14 | 14 | | | | | | | |
| 67100100 | MOBILIZATION | L SUM | 1 | 1 | | | | | | | |
| 70100310 | TRAFFIC CONTROL AND PROTECTION, STANDARD 701421 | L SUM | 1 | 1 | | | | | | | |
| 70100330 | TRAFFIC CONTROL AND PROTECTION, STANDARD 701426 | L SUM | 1 | 1 | | | | | | | |
| 70101835 | TRAFFIC CONTROL AND PROTECTION, STANDARD BLR 22 | L SUM | 1 | 1 | | | | | | | |
| 70102635 | TRAFFIC CONTROL AND PROTECTION, STANDARD 701701 | L SUM | 1 | 1 | | | | | | | |
| 70102640 | TRAFFIC CONTROL AND PROTECTION, STANDARD 701801 | L SUM | 1 | 1 | | | | | | | |
| 70101700 | TRAFFIC CONTROL AND PROTECTION | L SUM | 1 | | | 1 | | | | | |
| 70103815 | TRAFFIC CONTROL SURVEILLANCE | CAL DAILY | 180 | 180 | | | | | | | |
| 70300100 | SHORT-TERM PAVEMENT MARKING | FOOT | 4801 | 4674 | 127 | | | | | | |
| 70300210 | TEMPORARY PAVEMENT MARKING-LETTERS & SYMBOLS | SQ FT | 332.8 | 249.6 | 83.2 | | | | | | |
| 70300220 | TEMPORARY PAVEMENT MARKING-LINE 4" | FOOT | 16214 | 15647 | 567 | | | | | | |
| 70300240 | TEMPORARY PAVEMENT MARKING-LINE 6" | FOOT | 585 | 287 | 298 | | | | | | |
| 70300260 | TEMPORARY PAVEMENT MARKING-LINE 12" | FOOT | 813 | 731 | 82 | | | | | | |
| 70300280 | TEMPORARY PAVEMENT MARKING-LINE 24" | FOOT | 345 | 195 | 150 | | | | | | |
| 70300505 | PAVEMENT MARKING TAPE, TYPE III SPECIAL | FOOT | 29146 | 29146 | | | | | | | |
| 70301000 | WORK ZONE PAVEMENT MARKING REMOVAL | SQ FT | 18050 | 18008 | 42 | | | | | | |
| 70400100 | TEMPORARY CONCRETE BARRIER | FOOT | 760 | | | 760 | | | | | |
| 70400200 | RELOCATE TEMPORARY CONCRETE BARRIER | FOOT | 580 | | | 580 | | | | | |
| 72000200 | SIGN PANEL - TYPE 2 | SQ FT | 60 | | | | 30 | | 30 | | |
| 72400710 | RELOCATE SIGN PANEL - TYPE 1 | SQ FT | 22.5 | | | | 10 | | 12.5 | | |
| 72400720 | RELOCATE SIGN PANEL - TYPE 2 | SQ FT | 20 | | | | 20 | | | | |
| 78000100 | THERMOPLASTIC PAVEMENT MARKING LETTERS AND SYMBOLS | SQ FT | 332.8 | 249.6 | 83.2 | | | | | | |
| 78000200 | THERMOPLASTIC PAVEMENT MARKING LINE 4" | FOOT | 16214 | 15647 | 567 | | | | | | |
| 78000400 | THERMOPLASTIC PAVEMENT MARKING LINE 6" | FOOT | 585 | 287 | 298 | | | | | | |
| 78000600 | THERMOPLASTIC PAVEMENT MARKING LINE 12" | FOOT | 813 | 731 | 82 | | | | | | |
| 78000650 | THERMOPLASTIC PAVEMENT MARKING LINE 24" | FOOT | 345 | 195 | 150 | | | | | | |
| 78200405 | GUARDRAIL MARKERS | EACH | 11 | 5 | | 6 | | | | | |
| 78200500 | BARRIER WALL MARKERS | EACH | 4 | | | 4 | | | | | |
| 78201000 | TERMINAL MARKERS - DIRECT APPLIED | EACH | 5 | 1 | | 4 | | | | | |
| 78300100 | PAVEMENT MARKING REMOVAL | SQ FT | 172 | | 172 | | | | | | |
| 78300200 | RAISED REFLECTIVE PAVEMENT MARKER REMOVAL | EACH | 206 | 206 | | | | | | | |
| 80300100 | LOCATING UNDERGROUND CABLE | FOOT | 105 | | | | 30 | | 75 | | |
| 80500105 | SERVICE INSTALLATION, TYPE A (MODIFIED) | EACH | 1 | | | | 1 | | | | |

2/23/2006
c:\projects\98827\98827.dgn
5/2/2006 7:11 AM

REV.

SUMMARY OF QUANTITIES