

SUMMARY OF QUANTITIES

CODE NUMBER	ITEM DESCRIPTION CONSTRUCTION TYPE CODE	UNIT	FAS 1909
			STP-RURAL-STATE 80% FED / 20% STATE JACKSON COUNTY QUANTITY 1000
X0322729	MATERIAL TRANSFER DEVICE	TON	7,660.0
X4066418	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX C, N90	TON	7,513.0
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	8,423.0
40600300	AGGREGATE (PRIME COAT)	TON	137.0
X4066775	LEVELING BINDER (MACHINE METHOD), SUPERPAVE N90	TON	44.0
40600895	CONSTRUCTING TEST STRIP	EACH	1.0
40600980	BITUMINOUS SURFACE REMOVAL - BUTT JOINT	SQ YD	985.0
40600990	TEMPORARY RAMP	SQ YD	65.0
40800040	INCIDENTAL BITUMINOUS SURFACE	TON	160.0
44201761	CLASS D PATCHES, TYPE I, 10 INCH	SQ YD	15.0
44201765	CLASS D PATCHES, TYPE II, 10 INCH	SQ YD	75.0
44201769	CLASS D PATCHES, TYPE III, 10 INCH	SQ YD	37.0
44201771	CLASS D PATCHES, TYPE IV, 10 INCH	SQ YD	630.0
48101200	AGGREGATE SHOULDERS, TYPE B	TON	1,508.0
48201000	BITUMINOUS SHOULDERS	TON	46.0
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	2.0
67100100	MOBILIZATION	L SUM	1.0
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1.0
70100600	TRAFFIC CONTROL AND PROTECTION, STANDARD 701336	L SUM	1.0
70300100	SHORT- TERM PAVEMENT MARKING	FOOT	6,674.0
70300220	TEMPORARY PAVEMENT MARKING, LINE 4"	FOOT	114,074.0
70300280	TEMPORARY PAVEMENT MARKING, LINE 24"	FOOT	16.0
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	39,848.0
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	114,074.0
* 78001180	PAINT PAVEMENT MARKING - LINE 24"	FOOT	16.0
* 78100100	RAISED REFLECTIVE PAVEMENT MARKERS	EACH	418.0
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	418.0

* SPECIALTY ITEMS

△ Rev. 4-11-06