

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
726	130 RS-2	WILLIAMSON	58	3
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

SUMMARY OF QUANTITIES

CODE NO	ITEM	CONSTRUCTION TYPE CODE	1000-1A	
			URBAN ROADWAY	HES SAFETY
		UNIT	FED STATE	90% 10%
X0300351	CONCRETE STEP REMOVAL	EACH	3	
X4066530	POLYMERIZED BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "D", N105	TONS	1,700	
X7015000	CHANGEABLE MESSAGE SIGN	CAL MO	1	
20200100	EARTH EXCAVATION	CU YD	393	▲
20800150	TRENCH BACKFILL	CU YD	107	
25100630	EROSION CONTROL BLANKET	SQ YD	471	
31100300	SUB-BASE GRANULAR MATERIAL, TYPE A 4"	SQ YD	1288	
35500600	BITUMINOUS BASE COURSE 9"	SQ YD	404	
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	1,899	
40800040	INCIDENTAL BITUMINOUS SURFACING	TON	74	
40600300	AGGREGATE (PRIME COAT)	TON	32	
40600990	TEMPORARY RAMP	SQ YD	72	
42000200	PORTLAND CEMENT CONCRETE PAVEMENT, 7"	SQ YD	542	
42001200	PAVEMENT FABRIC	SQ YD	542	
42001300	PROTECTIVE COAT	SQ YD	806	▲
42300300	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 7 INCH	SQ YD	103	
42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SQ FT	210	
44000006	BITUMINOUS SURFACE REMOVAL 1 1/2"	SQ YD	20,603	
44000030	BITUMINOUS SURFACE REMOVAL (VARIABLE DEPTH)	SQ YD	88	
44000100	PAVEMENT REMOVAL	SQ YD	404	
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	80	
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	684	
44000600	SIDEWALK REMOVAL	SQ FT	562	
44201811	CLASS D PATCHES, TYPE I, 14 INCH	SQ YD	69	
44201815	CLASS D PATCHES, TYPE II, 14 INCH	SQ YD	217	
44201819	CLASS D PATCHES, TYPE III, 14 INCH	SQ YD	33	
44201821	CLASS D PATCHES, TYPE IV, 14 INCH	SQ YD	90	
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	15,650	
50300225	CONCRETE STRUCTURES	CU YD	4	
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	250	
54248510	CONCRETE COLLAR	CU YD	0.32	
550A0050	STORM SEWERS, CLASS A, TYPE 1, 12"	FOOT	340	▲
60243500	INLETS, SPECIAL, TYPE 3, 6'	EACH	4	
60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	1	
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6. 12	FOOT	738	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	3	
67100100	MOBILIZATION	L SUM	1	
70101830	TRAFFIC CONTROL AND PROTECTION, STANDARD BLR 21	L SUM	1	
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DAY	6	
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	2,504	
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	556	
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	9,284	▲
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	186	
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	4,858	▲
78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	556	
78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	9,284	▲
78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	186	

PLOT DATE = 2/16/2006
 FILE NAME = \\s0219851\9819851.dwg
 PLOT SCALE = 50.0000 / IN
 USER NAME = carlsonej

▲ Rev. 4-10-06

SUMMARY OF QUANTITIES