

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
726	130 RS-2	WILLIAMSON	58	8
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

## PAVEMENT MARKING SCHEDULE

LOCATION	THERMOPLASTIC				LETTERS AND SYMBOLS
	4 INCH		24 INCH		
	WHITE	YELLOW	DOUBLE YELLOW	WHITE	
STATION TO STATION	FOOT	FOOT	FOOT	FOOT	SQ FT
<b>IL 148</b>					
STA 232+50 TO STA 243+62.39, 7' LEFT		1112			
STA 232+50 TO STA 243+62.39, 7' RIGHT		1112			
STA 232+50 TO STA 243+62.39, 6' LEFT(SKIP DASH)		278			
STA 232+50 TO STA 243+62.39, 6' RIGHT(SKIP DASH)		278			
STA 232+50 TO STA 245+62.46, 18' LEFT(SKIP DASH)	328				
STA 232+50 TO STA 245+62.46, 18' RIGHT(SKIP DASH)	328				
STA 232+83 (TWLT ARROW)					31.2
STA 235+02 (TWLT ARROW)					31.2
STA 237+02 (TWLT ARROW)					31.2
STA 239+02 (TWLT ARROW)					31.2
STA 241+02 (TWLT ARROW)					31.2
STA 243+02 (TWLT ARROW)					31.2
STA 243+62.39 TO STA 245+62.46, 7' LT(DOUBLE YELLOW)			201		
STA 244+62.39 TO STA 245+62.46, 7' RIGHT	100				
STA 244+73 ("ONLY")					20.8
STA 245+00 (LEFT TURN ARROW)					15.6
STA 245+62.46 (STOP BAR)				36	
STA 246+22.97 (STOP BAR)				36	
STA 246+20.97 TO STA 252+09.30, 18' LEFT(SKIP DASH)	147				
STA 246+20.97 TO STA 252+09.30, 18' RIGHT(SKIP DASH)	147				
STA 246+20.97 TO STA 247+21.01, 7' LEFT	100				
STA 246+81 (LEFT TURN ARROW)					15.6
STA 247+10 ("ONLY")					20.8
STA 246+20.97 TO STA 248+21.01, 7' RIGHT			200		
STA 248+21.01 TO STA 250+09.30, 7' LEFT		188			
STA 248+21.01 TO STA 250+09.30, 7' RIGHT		188			
STA 248+21.01 TO STA 250+09.30, 6' LEFT(SKIP DASH)		47			
STA 248+21.01 TO STA 250+09.30, 6' RIGHT(SKIP DASH)		47			
STA 248+46 (TWLT ARROW)					31.2
STA 249+77 (TWLT ARROW)					31.2
STA 250+09.30 TO STA 252+09.30, 7' LEFT			200		
STA 251+09.30 TO STA 252+09.30, 7' RIGHT	100				
STA 251+19 ("ONLY")					20.8
STA 251+47 LEFT TURN ARROW					15.6
STA 252+09.30 (STOP BAR)				36	
STA 252+71.89 (STOP BAR)				36	
STA 252+71.89 TO STA 263+79.92, 18' LEFT(SKIP DASH)	277				
STA 252+71.89 TO STA 263+79.92, 18' RIGHT(SKIP DASH)	277				
STA 252+71.89 TO STA 253+71.87, 7' LEFT	100				
STA 252+71.89 TO STA 254+71.87, 7' RIGHT			200		
STA 253+33 LEFT TURN ARROW					15.6
STA 253+62 ("ONLY")					20.8
STA 254+71.87 TO STA 261+79.92, 7' RIGHT		707			
STA 254+71.87 TO STA 261+79.92, 7' LEFT		707			
STA 254+71.87 TO STA 261+79.92, 6' RIGHT (SKIP DASH)		177			
STA 254+71.87 TO STA 261+79.92, 6' LEFT (SKIP DASH)		177			
STA 255+02 (TWLT ARROW)					31.2
STA 257+02 (TWLT ARROW)					31.2
STA 259+02 (TWLT ARROW)					31.2
STA 261+02 (TWLT ARROW)					31.2
STA 261+79.92 TO STA 263+79.92, 7' LEFT			200		
STA 262+79.92 TO STA 263+79.92, 7' RIGHT	100				
STA 262+93 ("ONLY")					20.8
STA 263+19 LEFT TURN ARROW					15.6
STA 263+79.92 (STOP BAR)				42	
<b>PARKING SPACES</b>					
STA 253+43 TO STA 254+47 LEFT		50			
STA 254+33 TO STA 255+37 RIGHT		50			
STA 254+91 TO STA 255+53 LEFT		30			
STA 256+28 TO STA 256+92 LEFT		30			
STA 256+28 TO STA 257+78 RIGHT		70			
STA 258+01 TO STA 258+63 RIGHT		30			
<b>SUBTOTAL</b>	2004	5278	2002	186	556
<b>TOTAL</b>		9284		186	556

PLOT DATE = 3/24/2005  
 FILE NAME = c:\projects\98912\98912.dwg  
 PLOT SCALE = 1/8"=1'-0"  
 USER NAME = b1111111