	CONTR	CACT NO.	98366
SECTION	COUNTY	TOTAL	SHEET

RTE.		COUNTY	SHEETS	NO
845	5 **	FRANKLI	N 7	2
STA.	. 198+30	TO STA.	369+50	
FED.	. ROAD DIST. NO.	7 ILLINOIS	FED. AID	PROJECT

^{**} SLOPE STABILIZATION FYO6

SUMMARY OF QUANTITIES

	r	RURAL-FRANKLIN COUNTY		
		80% FEDERAL; 20% STATE		
	CONSTRUCTION TYPE CODE	Y009		
CODE NUMBER	ITEM DESCRIPTION	UNIT	QUANTITY	
28100809	STONE DUMPED RIPRAP, CLASS A5	TON	16, 165	
67100100	MOBILIZATION	L. SUM	1	
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L. SUM	1	
			1	
· · · · · · · · · · · · · · · · · · ·				

GENERAL NOTES

FACTORS USED FOR ESTIMATING PLAN QUANTIES ARE AS FOLLOWS AND SHALL NOT BE USED FOR THE BASIS OF FINAL QUANTITIES. RIPRAP = 1.5 TONS/CU. YDS.

IN ADDITION TO THE REQUIREMENTS OF ARTICLE 107.16 THE CONTRACTOR SHALL PROTECT
THE SURFACE OF ALL BRIDGE DECKS AND BRIDGE APPROACH PAVEMENTS IN A MANNER
SATISFACTORY TO THE ENGINEER BEFORE ANY EQUIPMENT IS ALLOWED TO CROSS THE
STRUCTURE. PROTECTION SHALL BE PROVIDED FOR ALL EQUIPMENT AS DEFINED IN ARTICLE
101.16 REGARDLESS IF TRACK MOUNTED OR WHEELED.

IT IS NOT THE INTENT OF THESE PLANS TO DUMP RIPRAP BELOW THE POOL ELEVATION OF THE LAKE AS DEPICTED IN THE TYPICAL SECTIONS. IF THE CONTRACTOR ELECTS TO WORK IN THE WATERS OF THE LAKE, IT SHALL BE THEIR RESPONSIBILITY TO OBTAIN ALL NECESSARY PERMITS AND/OR APPROVALS FOR THIS TYPE OF WORK.

INDEX OF SHEETS

- COVER SHEET
- 2 SUMMARY OF QUANTITIES; GENERAL NOTES; INDEX OF SHEETS
- 3 SCHEDULES OF QUANTITIES
- 4 TYPICAL SECTION
- 5 PLAN SHEET STA. 195+00 TO STA. 255+00
- 6 PLAN SHEET STA. 255+00 TO STA. 315+00
- 7 PLAN SHEET STA. 315+00 TO STA. 375+00

STANDARDS

000001-04 701001*-01*

701006-02

701011-*0|* 701**3**0**6-0|**

701301-02

702001-06

Prepared By

Examined By:

Examined By:

Examined By:

Examined By:

Examinea BA:

Examined By:

kamined By:

kamined By:

Approved By: May C. Rami

Feb 9 20 Ob