

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
845	**	FRANKLIN	7	3
STA. 198+30		TO STA. 369+50		
FED. ROAD DIST. NO. 7	ILLINOIS	FED. AID PROJECT		

** SLOPE STABILIZATION FY06

SCHEDULE

LOCATION STATION TO STATION	STONE DUMPED RIPRAP CLASS A5
	TONS
SOUTH FACE OF CAUSEWAY	
RT. STA. 198+30 TO 198+90	75
RT. STA. 200+50 TO 201+30	100
RT. STA. 203+00 TO 204+00	125
RT. STA. 204+50 TO 204+80	38
RT. STA. 206+60 TO 208+35	292
RT. STA. 209+50 TO 211+50	250
RT. STA. 213+00 TO 214+00	125
RT. STA. 216+50 TO 220+50	500
RT. STA. 223+80 TO 228+00	525
RT. STA. 230+10 TO 232+25	269
RT. STA. 233+50 TO 234+50	125
RT. STA. 235+50 TO 236+50	125
RT. STA. 237+00 TO 237+50	63
RT. STA. 240+00 TO 241+00	125
RT. STA. 242+00 TO 242+50	63
RT. STA. 246+00 TO 247+50	188
RT. STA. 251+00 TO 251+50	84
RT. STA. 254+00 TO 256+50	313
RT. STA. 257+20 TO 258+20	125
RT. STA. 258+75 TO 260+15	389
RT. STA. 260+15 TO 261+00	189
RT. STA. 261+75 TO 262+50	94
RT. STA. 263+00 TO 263+50	63
RT. STA. 264+20 TO 264+75	153
RT. STA. 265+00 TO 267+50	313

SCHEDULE

LOCATION STATION TO STATION	STONE DUMPED RIPRAP CLASS A5
	TONS
SOUTH FACE OF CAUSEWAY	
S. W. CONE OF SN 028-0051	167
RT. STA. 280+00 TO 282+00	417
RT. STA. 282+00 TO 284+50	556
RT. STA. 285+00 TO 286+00	250
RT. STA. 331+70 TO 334+20	347
RT. STA. 335+00 TO 337+50	139
RT. STA. 344+50 TO 345+00	63
RT. STA. 346+50 TO 347+75	208
RT. STA. 350+00 TO 350+50	63
RT. STA. 354+50 TO 355+50	125
S. W. CONE OF SN 028-0052	125
S. E. CONE OF SN 028-0052	63
RT. STA. 363+50 TO 365+00	188
RT. STA. 367+75 TO 369+50	389
NORTH FACE OF CAUSEWAY	
N. W. CONE OF SN 028-0050	139
N. E. CONE OF SN 028-0050	139
LT. STA. 251+20 TO 266+00	3084
LT. STA. 266+85 TO 267+35	167
LT. STA. 267+65 TO 268+15	167
LT. STA. 268+75 TO 275+00	2084
LT. STA. 279+50 TO 287+22	2574
TOTAL	16165

PLOT DATE = 12/21/2005
 FILE NAME = I:\982305\enddata.e32
 PLOT SCALE = 50.0000 / IN.
 USER NAME = halswood