

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
VAR	*	JACKSON	23	4
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

SUMMARY OF QUANTITIES

CODE NUMBER	ITEM DESCRIPTION CONSTRUCTION TYPE CODE	UNIT	TOTAL QUANTITY	1000			1000		
				LOC #1 JACKSON CO. RURAL 100% STATE	LOC #2 JACKSON CO. RURAL 100% STATE	JACKSON CO. URBAN 100% CITY	LOC #3 JACKSON CO. RURAL 100% STATE	LOC #4 JACKSON CO. RURAL 100% STATE	LOC #5 JACKSON CO. RURAL 100% STATE
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GAL	1,746	1,111			567	68	
40600105	BITUMINOUS MATERIALS (PRIME COAT), SPECIAL	GAL	294		126	24			144
40600300	AGGREGATE (PRIME COAT)	TON	37	19	2	1	10	2	3
40600990	TEMPORARY RAMP	50 YD	329	30	103		48	30	118
44000006	BITUMINOUS SURFACE REMOVAL - 1 1/2"	50 YD	19,657	12,343		266	6,298	750	
44000009	BITUMINOUS SURFACE REMOVAL - 3"	50 YD	2,992		1,396				1,596
44200114	PAVEMENT PATCHING, TYPE IV, 9 INCH	50 YD	161		134				27
44200168	PAVEMENT PATCHING, TYPE II, 14 INCH	50 YD	147	147					
48101200	AGGREGATE SHOULDERS, TYPE B	TON	290	144			144	2	
67100100	MOBILIZATION	L SUM	1	0.2	0.2		0.2	0.2	0.2
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	3	0.6	0.6		0.6	0.6	0.6
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	0.4			0.3	0.3	
70100600	TRAFFIC CONTROL AND PROTECTION, STANDARD 701336	L SUM	1	1					
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1		0.5				0.5
70300100	SHORT TERM PAVEMENT MARKING	FOOT	1,922	1065	89		567	50	151
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	50 FT	98.8		98.8				
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	28,702	20,183	241	28	7,547	563	140
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	346		100				246
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	91		50				41
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	50 FT	10,664	7,083	369		2,705	205	302
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	50 FT	98.8		98.8				
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	972		241	28		563	140
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	346		100				246
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	91		50				41
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	27,730	20,183			7,547		
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	79	67				4	8
* 88600100	DETECTOR LOOP, TYPE I	FOOT	171		60				111
X4066530	POLYMERIZED BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "D", N105	TON	274		118	22			134
X4066418	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "C", N90	TON	1,567	1,037			530		
X4066428	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "D", N90	TON	61					61	
X4066775	LEVELING BINDER (MACHINE METHOD) SUPERPAVE, N90	TON	3					3	
X4066920	POLYMERIZED LEVELING BINDER (MACHINE METHOD), SUPERPAVE N105	TON	252		118				134
X7015000	CHANGEABLE MESSAGE SIGN	CAL MO	1		0.5				0.5

*SPECIALTY ITEMS