AU062

PATH: K:\AuroraAp\0428504\Draw\Sheet
FILE: landscaping-33.dwg
UPDATE BY: johse

XREF DWG:
XREF DWG:
DATE: Mon 2/28/05 5:06pm

TAXIWAY A

RUNWAY 15/33

RUNWAY 18/36

TAXIWAY C

NORTH
0 100 200
SCALE IN FEET

EXISTING STORM SEWER

EXISTING TREE TO BE REMOVED

EXISTING WETLAND TO HAVE VEGETATION CLEARED AND LANDSCAPED 0.5 ACRES VEGETATION CLEARING PAID FOR AS CLEARING (151)(SEE NOTE 1)

EXISTING BARBED WIRE FENCE TO BE REMOVED (INCIDENTAL TO CLEARING)

STA. 551+40.00, 250' RT.
℄ RUNWAY 15/33

NEW GLIDESLOPE ANTENNA AND SHELTER

100'

STA. 848+03.58, 200' RT.
BASELINE A

NEW SILT FENCE (156)(TYPICAL)

5' (TYPICAL)

25'

CONTRACTOR'S ACCESS ROUTE BETWEEN SITES

NEW GRADING/ LANDSCAPING LIMITS (TYPICAL)

5' (TYPICAL)

NEW GRADING/ LANDSCAPING LIMITS (TYPICAL)

STA. 555+02.05
END OF RUNWAY
ELEVATION = 698.55

NEW MALSR LIGHT (TYPICAL)

NEW GLIDE SLOPE CRITICAL AREA

STA. 558+17.96, 250' RT.
℄ RUNWAY 15/33

5' (TYPICAL)

NEW INLET PROTECTION (156)(TYPICAL)

EXISTING FARMED WETLAND TO BE LANDSCAPED (SEE NOTE 1)

STA. 858+17.96, 200' RT.
BASELINE A

BASELINE A

EXISTING FIELD TILE

NEW STABILIZED CONSTRUCTION ENTRANCE

NEW STABILIZED CONSTRUCTION ENTRANCE

U.S. ROUTE 30

OHE

LEGEND

- EXISTING WETLAND
- NEW LIMITS OF SEEDING (901) AND MULCHING (908)
- EXISTING WETLAND TO HAVE VEGETATION CLEARED (151) AND SEEDED (901) AND MULCHED (908)
- EXISTING FARMED WETLAND TO BE SEEDED (901) AND MULCHED (908)
- NEW GRADING AND LANDSCAPING LIMITS
- NEW SILT FENCE (156)
- NEW INLET PROTECTION (156)
- EXISTING TREE TO BE REMOVED W/ TRUNK DIAMETER (30")
- EXISTING FENCE TO BE REMOVED

NOTES

1. NO GRADING IS ALLOWED WITHIN THE WETLAND LIMITS. THE EXISTING VEGETATION IS TO BE REMOVED AT GROUND LEVEL, AND THE AREA IS TO BE LANDSCAPED.
2. NO CONSTRUCTION TRAFFIC SHALL CROSS OR DISTURB EXISTING WETLANDS.

REVISIONS

NUMBER	BY	DATE

0 1 2
THIS BAR IS EQUAL TO 2" AT FULL SCALE (34X22).

AURORA MUNICIPAL AIRPORT
AURORA, ILLINOIS
CONSTRUCT RUNWAY 33 ILS;
RELOCATE RUNWAY 9 LOCALIZER

RUNWAY 33 GLIDE SLOPE STORMWATER PREVENTION PLAN

© Copyright CMT, Inc.

CMT
CRAWFORD, MURPHY & TILLY, INC.
CONSULTING ENGINEERS
License No. 184-000813

DESIGN BY:	CAL/DKP
DRAWN BY:	JRO
CHECKED BY:	CAL
APPROVED BY:	
DATE:	03/03/06
JOB No:	04285-04

ILLINOIS PROJECT: ARR-3468
A.I.P. PROJECT: 3-17-0003-B31
FINAL SUBMITTAL