

SUMMARY OF QUANTITIES				
ITEM NO.	DESCRIPTION	UNIT	AS BID QUANTITY	AS BUILT QUANTITY
AR108000	CABLE TRENCH	LIN. FT.	120	
AR108108	1/C #8 5 KV UG CABLE	LIN. FT.	4,130	
AR108158	1/C #8 5 KV UG CABLE IN UD	LIN. FT.	56,005	
AR109100	CONSTRUCT ELECTRICAL VAULT	L. SUM	1	
AR109200	INSTALL ELECTRICAL EQUIPMENT	L. SUM	1	
AR109311	7.5 KW REGULATOR, STYLE 1	EACH	2	
AR109341	20 KW REGULATOR, STYLE 1	EACH	1	
AR109342	20 KW REGULATOR, STYLE 2	EACH	1	
AR109530	POWER CABLE INSTALLATION	L. SUM	1	
AR109535	ELECTRIC SERVICE ENTRANCE	L. SUM	1	
AR109600	L-821 CONTROL PANEL	EACH	1	
AR109610	L-854 PCAL SYSTEM	L. SUM	1	
AR109902	REMOVE ELECTRICAL EQUIPMENT	L. SUM	1	
AR109903	REMOVE REGULATOR	EACH	6	
AR109909	REMOVE CONTROL PANEL	L. SUM	1	
AR109910	REMOVE ELECTRICAL TRANSCLOSURE	L. SUM	1	
AR110314	4" STEEL DUCT, JACKED	LIN. FT.	146	
AR110710	ELECTRICAL MANHOLE	EACH	1	
AR125410	MITL-STAKE MOUNTED	EACH	287	
AR125415	MITL-BASE MOUNTED	EACH	32	
AR125442	TAXI GUIDANCE SIGN, 2 CHARACTER	EACH	16	
AR125443	TAXI GUIDANCE SIGN, 3 CHARACTER	EACH	5	
AR125444	TAXI GUIDANCE SIGN, 4 CHARACTER	EACH	7	
AR125445	TAXI GUIDANCE SIGN, 5 CHARACTER	EACH	3	
AR125448	TAXI GUIDANCE SIGN, 8 CHARACTER	EACH	1	
AR125449	TAXI GUIDANCE SIGN, 9 CHARACTER	EACH	4	
AR125505	MIRL, STAKE MOUNTED	EACH	26	
AR125510	MIRL, BASE MOUNTED	EACH	8	
AR125515	HIRL, BASE MOUNTED	EACH	62	
AR125540	MI THRESHOLD LIGHT STAKE MTD	EACH	16	
AR125550	HI THRESHOLD LIGHT BASE MTD	EACH	16	
AR125565	SPLICE CAN	EACH	1	
AR125610	REILS	PAIR	1	
AR125901	REMOVE STAKE MOUNTED LIGHT	EACH	305	
AR125902	REMOVE BASE MOUNTED LIGHT	EACH	114	
AR125904	REMOVE TAXI GUIDANCE SIGN	EACH	50	
AR125907	REMOVE REILS	PAIR	1	
AR150530	TRAFFIC MAINTENANCE	L. SUM	1	
AR501605	5" PCC SIDEWALK	SQ. FT.	72	

GALESBURG MUNICIPAL AIRPORT  
GALESBURG, ILLINOIS

SUMMARY OF QUANTITIES

HUTCHISON ENGINEERING, INC.  
JACKSONVILLE, ILLINOIS

DRAWN BY: T.J.D.  
DATE: MARCH, 2006

ILL. PROJ. NO. G96-3433  
AP PROJ. NO. 3-17-0047-B8