

GENERAL NOTES

1. THE STANDARDS INCLUDED IN THE BACK OF THESE PLANS SHALL APPLY TO THIS PROJECT.
2. THESE PLANS HAVE BEEN PREPARED USING STANDARD SYMBOLS AS INDICATED IN THESE PLANS, AND THEY SHALL TAKE PRECEDENCE OVER THOSE SHOWN ON STANDARD 000001-06 IF THERE IS A CONFLICT.
3. EXISTING RAISED REFLECTIVE PAVEMENT MARKERS SHALL BE REMOVED PRIOR TO RESURFACING.
4. THE CONTRACTOR SHALL VERIFY ALL DIMENSIONS AND CONDITIONS IN THE FIELD PRIOR TO CONSTRUCTION AND ORDERING OF MATERIALS.
5. THE CONTRACTOR SHALL PROTECT UTILITY PROPERTY FROM CONSTRUCTION OPERATIONS AS OUTLINED IN ARTICLE 107.31 OF THE STANDARD SPECIFICATIONS. AGENCIES KNOWN TO HAVE FACILITIES WITHIN THE PROJECT AREA ARE AS FOLLOWS:

J.U.L.I.E. 1-800-892-0123

ILLINOIS STATE LAW REQUIRES A 48-HOUR NOTICE BE GIVEN TO ALL UTILITIES BEFORE DIGGING. FIELD MARKING OF FACILITIES MAY BE OBTAINED BY CONTACTING J.U.L.I.E. OR FOR NON-MEMBERS, BY CONTACTING THE UTILITY COMPANY DIRECTLY.

IT IS UNDERSTOOD AND AGREED THAT THE CONTRACTOR HAS TAKEN THE FOREGOING INTO CONSIDERATION IN SUBMITTING HIS BID, AND NO ADDITIONAL COMPENSATION WILL BE ALLOWED FOR ANY DELAYS OR INCONVENIENCES CAUSED BY THE SAME.

THE INFORMATION AND DATA SHOWN OR INDICATED ON THESE IMPROVEMENT PLANS WITH RESPECT TO EXISTING UNDERGROUND FACILITIES AND UTILITIES AT OR CONTIGUOUS TO THE SITE IS BASED ON INFORMATION AND DATA FURNISHED BY THE OWNERS OF SUCH UNDERGROUND FACILITIES AND UTILITIES OR BY OTHERS. FIELD MARKINGS OF FACILITIES IN CRITICAL AREAS MAY BE OBTAINED BY PROVIDING A MINIMUM OF 96 HOURS ADVANCE NOTICE TO THE RESIDENT ENGINEER SO THAT UTILITIES CAN BE GIVEN NOTICE. NO GUARANTEE IS IMPLIED AS TO THE ACCURACY OR COMPLETENESS OF ANY SUCH INFORMATION OR DATA; AND CONTRACTOR SHALL HAVE FULL RESPONSIBILITY FOR (i) REVIEWING AND CHECKING ALL SUCH INFORMATION AND DATA, (ii) VERIFYING IF ANY CONFLICTS EXIST WITH THE PROPOSED WORKED AND UNDERGROUND FACILITIES AND UTILITIES SHOWN OR INDICATED ON THE IMPROVEMENT PLANS; (iii) COORDINATION OF THE WORK WITH THE OWNERS OF SUCH UNDERGROUND FACILITIES AND UTILITIES DURING CONSTRUCTION, AND (iv) THE SAFETY AND PROTECTION OF ALL SUCH UNDERGROUND FACILITIES AND UTILITIES AND REPAIR ANY DAMAGE THERETO RESULTING FROM THE WORK AT HIS EXPENSE.

6. FULL DEPTH SAW CUTTING ON ALL EDGES FOR REMOVAL ITEMS SHALL BE INCLUDED IN THE COST OF THE REMOVAL ITEM AS INDICATED AND IN ACCORDANCE WITH SECTION 440 OF THE STANDARD SPECIFICATIONS.
7. FOR STABILIZATION, ALL TYPE III BARRICADES SHALL REQUIRE A MINIMUM OF FOUR SANDBAGS PER BARRICADE.
8. ALL AREAS DISTURBED BEYOND THE CONSTRUCTION LIMITS FOR ANY REASON SHALL BE SEEDED WITH CLASS 2 SEEDING, AS DIRECTED BY THE ENGINEER. NUTRIENTS SHALL CONFORM TO ARTICLE 250.04. FINAL SEEDING SHALL BE PERFORMED AS SOON AS POSSIBLE. THESE AREAS WILL NOT BE MEASURED FOR PAYMENT.
9. WHERE SECTION OR SUBSECTION MONUMENTS ARE ENCOUNTERED, THE ENGINEER SHALL BE NOTIFIED BEFORE SUCH MONUMENTS ARE REMOVED. THE CONTRACTOR SHALL PROTECT AND CAREFULLY PRESERVE ALL MONUMENTS UNTIL AN AUTHORIZED SURVEYOR OR AGENT HAS WITNESSED OR OTHERWISE REFERENCED THEIR LOCATION. THE CONTRACTOR SHALL BE RESPONSIBLE FOR HAVING AN AUTHORIZED SURVEYOR REESTABLISH ANY SECTION OR SUBSECTION MONUMENTS DESTROYED BY HIS/HER OPERATIONS.
10. THE FOLLOWING RATES OF APPLICATION HAVE BEEN USED TO CALCULATE THE PLAN QUANTITIES:
 GRANULAR MATERIALS 2.05 TONS / CU YD
 BITUMINOUS MATERIALS (PRIME COAT) 0.05 LBS / SQ FT (MILLED/AGED)
 0.025 LBS / SQ FT (FOG COAT BTW LIFTS)
 0.25 LBS / SQ FT (ACC BASE)
 HMA RESURFACING 112 LBS / SQ YD / IN
 SHORT TERM PAVEMENT MARKING 4 FT / 40 FT OF APPLICATION
11. THE CONTRACTOR SHALL NOTIFY THE DISTRICT 6 BUREAU OF OPERATION AT (217) 785-5312 THREE WEEKS PRIOR TO IMPLEMENTING ANY TRAFFIC CONTROL.

INDEX OF SHEETS

- 1 COVER SHEET
- 2 GENERAL NOTES
- 3-4 SUMMARY OF QUANTITIES
- 5 SCHEDULE OF QUANTITIES
- 6 TYPICAL SECTION
- 7-9 PLAN
- 10-13 DETAILS

COMMITMENTS

1. THE RESIDENT ENGINEER SHALL CONTACT STUDIES & PLANS CONCERNING ANY MAJOR PLAN CHANGES.
2. THE PROPOSED PAVEMENT MARKINGS FOR EDGE LINES SHALL BE DONE BY THE DISTRICT 6 OPERATIONS. ON COMPLETION OF THE PROJECT, THE CONTRACTOR SHALL CONTACT DISTRICT 6 OPERATIONS AT (217)785-5312 TWO WEEKS PRIOR TO MAKE ARRANGEMENTS FOR THIS WORK.

DISTRICT SIX	
EXAMINED <u>January 25th</u> 20 <u>17</u>	
<i>John Colman</i> OPERATIONS ENGINEER	
EXAMINED <u>January 17</u> 20 <u>17</u>	
<i>Ron Chamberlain</i> PROJECT IMPLEMENTATION ENGINEER	
EXAMINED <u>January 24</u> 20 <u>17</u>	
<i>John P. Myer</i> PROGRAM DEVELOPMENT ENGINEER	

MIXTURE TABLES

Location(s):	MAINLINE	MAINLINE	SHOULDER	SHOULDER
MIXTURE USE(S):	BINDER	SURFACE	LOWER LIFT	TOP LIFT
PG:	SBS PG 70-28	SBS PG 70-28	PG 64-22	PG 64-22
DESIGN AIR VOIDS:	4.0% @ N70	4.0% @ N70	4.0% @ N50	4.0% @ N50
Mixture Composition:	IL 19.0	IL 9.5	IL 19.0	IL 9.5
FRICTION AGGREGATE:	N/A	MIX "D"	N/A	MIX "C"
Quality Management:	QCP QC/QA	QCP QC/QA	QC/QA	QC/QA
Mixture Sublot Size:	500 TONS N/A	300 TONS N/A	N/A	N/A



10 UAGNUE
 2004/04/16 10:23:25

△ REV. 4-14-17

FILE NAME: p:\IL094EBID\INTEG.illinois.gov\100710	USER NAME: Rohan1M	DESIGNED: -	REVISED: -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	GENERAL NOTES, INDEX OF SHEETS, COMMITMENTS, AND MIXTURE TABLES	F.A.I. RTE. 172	SECTION (1, 2) RS	COUNTY ADAMS	TOTAL SHEETS 13	SHEET NO. 2
PLLOT SCALE = 100.0000 / in.	CHECKED: -	REVISED: -	SCALE:			SHEET OF SHEETS STA. TO STA.	ILLINOIS FED. AID PROJECT	CONTRACT NO. 72J46		
PLLOT DATE = 1/30/2017	DATE: -	REVISED: -								