

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTR. CODE	
				ROADWAY	URBAN
X0327611	REMOVE AND REINSTALL BRICK PAVER	SQ FT	309	0005	309
X4060002	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, STONE MATRIX ASPHALT, 12.5, N80	TON	5972		5972
X4060006	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, STONE MATRIX ASPHALT, 12.5, N80	TON	12182		12182
X5537800	STORM SEWERS TO BE CLEANED 12"	FOOT	3500		3500
X6030310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	80		80
X7030005	TEMPORARY PAVEMENT MARKING REMOVAL	SQ FT	26141		26141
Z0004530	HOT-MIX ASPHALT DRIVEWAY PAVEMENT, 8"	SQ YD	25		25
Z0004538	HOT-MIX ASPHALT DRIVEWAY PAVEMENT, 10"	SQ YD	25		25
Z0004562	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	2270		2270
Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	77		77
Z0030850	TEMPORARY INFORMATION SIGNING	SQ FT	864		864
Z0034105	MATERIAL TRANSFER DEVICE	TON	20483		20483
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	LSUM	1		1
Z0076600	TRAINEES	Hour	500		500
Z0076604	TRAINEES - TRAINING PROGRAM GRADUATE	Hour	500		500

Ø 004Z
 NON-PARTICIPATING

* - DENOTES SPECIALTY ITEM

F:\60616R003\07-F1B177-004-W07-IL-50-Resurfacing-62A08\02C\11\08Support\F1B177-004-W07-IL-50-62A08-INT-5005.dgn

FILE NAME :	USER NAME : amhammad	DESIGNED - ZJT	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	IL ROUTE 50 (CICERO AVE) SUMMARY OF QUANTITIES		F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
MODEL NAME :	PLOT SCALE * 100.0000' / 1" =	DRAWN - ZJT	REVISED -				350	461R5-2	COOK	71	8	
	PLOT DATE * 2/7/2017	CHECKED - RAG	REVISED -		SCALE:	SHEET	OF	SHEETS	STA.	TO	STA.	CONTRACT NO. 62A08
		DATE - 12/23/2016	REVISED -									ILLINOIS FED. AID PROJECT

Rev 4-18-17

REV