

URBAN

URBAN

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE	
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	90% FED 10% ST 0021
20200100	EARTH EXCAVATION	CU YD	4331	4331
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	2424	2424
21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SO YD	2104	2104
21101615	TOPSOIL FURNISH AND PLACE, 4"	SO YD	23380	23380
25000210	SEEDING, CLASS 2A	ACRE	4.8	4.8
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	435	435
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	435	435
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	435	435
25100630	EROSION CONTROL BLANKET	SO YD	23380	23380
28000400	PERIMETER EROSION BARRIER	FOOT	3000	3000
30300001	AGGREGATE SUBGRADE IMPROVEMENT	CU YD	702	702
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	1391	1391
40800029	BITUMINOUS MATERIALS (TACK COAT)	POUND	13800	13800

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE	
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	90% FED 10% ST 0021
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SO YD	12417	12417
44201789	CLASS D PATCHES, TYPE II, 12 inch	SO YD	100	100
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SO YD	18248	18248
44201794	CLASS D PATCHES, TYPE III, 12 inch	SO YD	200	200
64200108	SHOULDER RUMBLE STRIPS, 8 INCH	FOOT	42084	42084
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	100	100
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6
66900200	NON-SPECIAL WASTE DISPOSAL	CU YD	2900	2900
67100100	MOBILIZATION	LSUM	1	1
6600450	SPECIAL WASTE PLANS AND REPORTS	LSUM	1	1
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	LSUM	1	1
6600530	SOIL DISPOSAL ANALYSIS	EACH	10	10
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	LSUM	1	1
70300100	SHORT TERM PAVEMENT MARKING	FOOT	5123	5123
70300150	SHORT TERM PAVEMENT MARKING REMOVAL	SO FT	1708	1708
70300520	PAVEMENT MARKING TAPE, TYPE III 4"	FOOT	5123	5123
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	42084	42084
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	513	513
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	411	411
	* SPECIALTY ITEM			

14

13

FILE NAME :	USER NAME = Bpgramax	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES		F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
OFFICE: District 1 Projects/Division 1/Design/Design/Design	PROJECT: 2015-0651	CHECKED -	REVISED -				332	2015-0651	WILL	64	3
PLOT SCALE = 100,000 / 1 in.	DATE -	REVISED -	REVISED -				CONTRACT NO. 62844				
PLOT DATE = 2/21/2017	DATE -	REVISED -	REVISED -				FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				

Rev 4-12-17

Rev