

# SCHEDULE OF QUANTITIES

| REINFORCED CONCRETE PIPE ELBOW 36" |          |         |
|------------------------------------|----------|---------|
| STATION                            | EACH     | REMARKS |
| RT 18+26.25                        | 1        | 6.72°   |
| <b>PROJECT TOTAL</b>               | <b>1</b> |         |

54215991

| CONCRETE END SECTION,<br>STANDARD 542001, 36", 1:2 |          |         |
|--|----------|---------|
| STATION  | EACH     | REMARKS |
| RT 19+79   | 1        |         |
| <b>PROJECT TOTAL</b>                               | <b>1</b> |         |

54261236

| PIPE CULVERTS, CLASS A, TYPE 1 15" |           |         |
|------------------------------------|-----------|---------|
| STATION                            | FOOT      | REMARKS |
| LT 21+73 - 22+02                   | 30        |         |
| <b>PROJECT TOTAL</b>               | <b>30</b> |         |

542A0220

| PIPE CULVERTS, CLASS A, TYPE 1 36" |            |         |
|------------------------------------|------------|---------|
| STATION                            | FOOT       | REMARKS |
| RT 17+94 - 19+79                   | 188        |         |
| <b>PROJECT TOTAL</b>               | <b>188</b> |         |

542A0241

| MANHOLES, TYPE A, 4'-DIAMETER,<br>TYPE 8 GRATE |          |         |
|--|----------|---------|
| STATION  | EACH     | REMARKS |
| 27.45', RT 17+93                               | 1        |         |
| <b>PROJECT TOTAL</b>                           | <b>1</b> |         |

50219000

| STEEL PLATE BEAM GUARDRAIL,<br>TYPE A, 6 FOOT POSTS |           |              |
|---|-----------|--------------|
| STATION   | FOOT      | REMARKS      |
| LT 18+72 - 19+10                                    | 38        |              |
| RT 18+85 - 19+10                                    | 25        | 1:16.3 FLARE |
| LT 20+90 - 21+15                                    | 25        | 1:17.4 FLARE |
| <b>PROJECT TOTAL</b>                                | <b>88</b> |              |

53000001

| TRAFFIC BARRIER TERMINAL, TYPE 6 |          |         |
|----------------------------------|----------|---------|
| STATION                          | EACH     | REMARKS |
| LT 19+10 - 19+55                 | 1        |         |
| RT 19+10 - 19+55                 | 1        |         |
| LT 20+45 - 20+90                 | 1        |         |
| RT 20+45 - 20+90                 | 1        |         |
| <b>PROJECT TOTAL</b>             | <b>4</b> |         |

53100085

| TRAFFIC BARRIER TERMINAL, TYPE 1<br>(SPECIAL) TANGENT |          |              |
|---|----------|--------------|
| STATION   | EACH     | REMARKS      |
| LT 18+20 - 18+72                                      | 1        |              |
| RT 18+34 - 18+85                                      | 1        | 1:16.3 FLARE |
| RT 20+90 - 21+42                                      | 1        | 1:19.8 FLARE |
| LT 21+15 - 21+67                                      | 1        | 1:17.4 FLARE |
| <b>PROJECT TOTAL</b>                                  | <b>4</b> |              |

53100167

| CHANGEABLE MESSAGE SIGN        |           |            |
|--------------------------------|-----------|------------|
| STATION                        | CAL DA    | REMARKS    |
| KLEMM ROAD AND EXCHANGE STREET | 30        | SOUTHBOUND |
| KLEMM ROAD AND DANNE ROAD      | 30        | NORTHBOUND |
| <b>PROJECT TOTAL</b>           | <b>60</b> |            |

X7015005

| SIGN PANEL - TYPE 1  |          |                                  |
|----------------------|----------|----------------------------------|
| STATION              | SO FT    | REMARKS                          |
| RT 19+10             | 6        | W3-3 SIGNAL AHEAD (30x30)        |
| RT 19+10             | 2        | W16-8P "EXCHANGE ST." (VARIESx8) |
| <b>PROJECT TOTAL</b> | <b>8</b> |                                  |

72000100

| TERMINAL MARKER - DIRECT APPLIED |          |         |
|----------------------------------|----------|---------|
| STATION                          | EACH     | REMARKS |
| LT 18+20                         | 1        |         |
| RT 18+34                         | 1        |         |
| RT 21+42                         | 1        |         |
| LT 21+67                         | 1        |         |
| <b>PROJECT TOTAL</b>             | <b>4</b> |         |

72501000

| TELESCOPING STEEL SIGN SUPPORT |           |              |
|--------------------------------|-----------|--------------|
| STATION                        | FOOT      | REMARKS      |
| RT 19+10                       | 13        | SIGNAL AHEAD |
| <b>PROJECT TOTAL</b>           | <b>13</b> |              |

72800100

| PAINT PAVEMENT MARKING - LINE 4" |              |                       |
|----------------------------------|--------------|-----------------------|
| STATION                          | FOOT         | REMARKS               |
| 17+50 - 21+70                    | 840          | DBL YELLOW C/L        |
| LT 17+50 - 21+70                 | 420          | SOLID WHITE EDGE LINE |
| RT 17+50 - 21+70                 | 420          | SOLID WHITE EDGE LINE |
| <b>PROJECT TOTAL</b>             | <b>1,680</b> |                       |

78001110

| RAISED REFLECTIVE PAVEMENT MARKER |           |                      |
|-----------------------------------|-----------|----------------------|
| STATION                           | EACH      | REMARKS              |
| 17+75                             | 2         | TWO-WAY AMBER MARKER |
| 18+55                             | 2         | TWO-WAY AMBER MARKER |
| 19+35                             | 2         | TWO-WAY AMBER MARKER |
| 20+95                             | 2         | TWO-WAY AMBER MARKER |
| 21+35                             | 2         | TWO-WAY AMBER MARKER |
| <b>PROJECT TOTAL</b>              | <b>10</b> |                      |

78100100

| RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE) |          |                      |
|--|----------|----------------------|
| STATION                                    | EACH     | REMARKS              |
| 20+15                                      | 2        | TWO-WAY AMBER MARKER |
| <b>PROJECT TOTAL</b>                       | <b>2</b> |                      |

78100105

| GUARDRAIL REFLECTORS, TYPE A |          |         |
|------------------------------|----------|---------|
| STATION                      | EACH     | REMARKS |
| LT 18+72 - 20+90             | 4        |         |
| RT 19+10 - 20+90             | 4        |         |
| <b>PROJECT TOTAL</b>         | <b>8</b> |         |

78200005

| RAISED REFLECTIVE PAVEMENT MARKER REMOVAL |           |         |
|---|-----------|---------|
| STATION                                   | EACH      | REMARKS |
| 19+09 - 21+35                             | 13        |         |
| <b>PROJECT TOTAL</b>                      | <b>13</b> |         |

78300200

| SEEDING, CLASS 4B (SPECIAL) |             |         |
|-----------------------------|-------------|---------|
| STATION                     | ACRE        | REMARKS |
| LT 19+00 - 19+78            | 0.05        |         |
| LT 20+08 - 20+65            | 0.02        |         |
| RT 20+22 - 20+50            | 0.002       |         |
| <b>PROJECT TOTAL</b>        | <b>0.07</b> |         |

X2502019\*

| PAVEMENT REMOVAL (SPECIAL) |            |                        |
|----------------------------|------------|------------------------|
| STATION                    | SO YD      | REMARKS                |
| 17+50 - 19+57              | 531        | ±6.5" ROADWAY PAVEMENT |
| 20+43 - 21+70              | 314        | ±6.5" ROADWAY PAVEMENT |
| <b>PROJECT TOTAL</b>       | <b>845</b> |                        |

X4404400\*

| PAVED DITCH (SPECIAL) |            |         |
|-----------------------|------------|---------|
| STATION               | FOOT       | REMARKS |
| 20+33.17 - 21+42      | 110        |         |
| <b>PROJECT TOTAL</b>  | <b>110</b> |         |

X6061460\*

| REMOVE SIGN PANEL ASSEMBLY -<br>TYPE A (SPECIAL) |          |               |
|--|----------|---------------|
| STATION  | EACH     | REMARKS       |
| RT 19+08   | 1        | SIGNAL AHEAD  |
| LT 19+57   | 1        | OBJECT MARKER |
| RT 19+57   | 1        | OBJECT MARKER |
| LT 20+43   | 1        | OBJECT MARKER |
| RT 20+43   | 1        | OBJECT MARKER |
| <b>PROJECT TOTAL</b>                             | <b>5</b> |               |

X7240110\*

| FENCE (SPECIAL)      |           |         |
|----------------------|-----------|---------|
| STATION              | FOOT      | REMARKS |
| RT 19+65 - 19+80     | 27        |         |
| RT 20+32 - 20+50     | 43        |         |
| <b>PROJECT TOTAL</b> | <b>70</b> |         |

XX006653

| FENCE REMOVAL        |           |         |
|----------------------|-----------|---------|
| STATION              | EACH      | REMARKS |
| RT 19+65 - 19+80     | 32        |         |
| RT 20+19 - 20+50     | 58        |         |
| <b>PROJECT TOTAL</b> | <b>90</b> |         |

Z0022800

FILE: S:\PROJECTS\2011\130301\Create\DESIGN\STRUCT\20\_Drawing\130301\_Schedule of Quantities.dgn



|                |                   |
|----------------|-------------------|
| DESIGNED - MAC | REVISED - 4-11-17 |
| CHECKED - BKC  | REVISED -         |
| DRAWN - DAN    | REVISED -         |
| CHECKED - MAC  | REVISED -         |

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**SCHEDULE OF QUANTITIES**  
**T.R. 428 (KLEMM ROAD) OVER BRANCH OF PLUM CREEK**  
SHEET NO. 2 OF 2 SHEETS

|   |                        |             |                    |             |
|---|------------------------|-------------|--------------------|-------------|
| TWP. RTE. 428                           | SECTION 12-02110-01-BR | COUNTY WILL | TOTAL SHEETS 50    | SHEET NO. 9 |
| WHA# 1303014                            |                        |             | CONTRACT NO. 61D68 |             |
| ILLINOIS FED. AID PROJECT BROS-01911281 |                        |             |                    |             |