



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

April 14, 2023

SUBJECT: FAI Route I-88 (I-88/IL 92)
Project NHPP-ERIQ(194)
Section (161-1B-1,2&161-1HB-9))BDR
Rock Island County
Contract No. 64P85
Item No. 12, April 28, 2023 Letting
Addendum A

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Revised the Schedule of Prices.
2. Revised page i of the Table of Contents to the Special Provisions.
3. Revised pages 36-59 of the Special Provisions.
4. Revised sheets 4, 5, 30, 69, and 110 of the Plans.

Prime contractors must utilize the enclosed material when preparing their bid and must include any changes to the Schedule of Prices in their bid.

Very truly yours,

A handwritten signature in black ink, appearing to read 'Jack A. Elston'.

Jack A. Elston, P.E.
Bureau Chief, Design and Environment

TABLE OF CONTENTS

LOCATION OF PROJECT	1
DESCRIPTION OF PROJECT	1
SAW CUTTING.....	1
CHANGEABLE MESSAGE SIGN	2
ENGINEER’S FIELD OFFICE TYPE A (D2).....	2
TRAFFIC CONTROL PLAN (D2)	2
LINEAR DELINEATION PANELS, 6 INCH.....	4
HOT-MIX ASPHALT SHOULDER REMOVAL AND REPLACEMENT (SPECIAL).....	5
FRAMES AND GRATES TO BE ADJUSTED (SPECIAL).....	6
DEBRIS REMOVAL	6
ADJUST ROCKER AND SOLE PLATE.....	7
STRUCTURAL STEEL REMOVAL	8
CLEANING AND PAINTING CONTACT SURFACE AREAS OF EXISTING STEEL STRUCTURES	9
CLEANING AND PAINTING EXISTING STEEL STRUCTURES.....	14
CLEANING AND PAINTING BEARINGS	36
DECK SLAB REPAIR.....	60
BRIDGE DECK MICROSILICA CONCRETE OVERLAY.....	65
STRUCTURAL REPAIR OF CONCRETE	75
DIAMOND GRINDING AND SURFACE TESTING BRIDGE SECTIONS	84
BRIDGE DECK CONSTRUCTION.....	89
BRIDGE DECK GROOVING (LONGITUDINAL)	90
HOT DIP GALVANIZING FOR STRUCTURAL STEEL	91
BAR SPLICERS.....	94
BLENDED FINELY DIVIDED MINERALS (BDE).....	94
COMPENSABLE DELAY COSTS (BDE)	95
DISADVANTAGED BUSINESS ENTERPRISE PARTICIPATION (BDE)	98
PERFORMANCE GRADED ASPHALT BINDER (BDE)	107
SOURCE OF SUPPLY AND QUALITY REQUIREMENTS (BDE)	111
SPEED DISPLAY TRAILER (BDE)	112
STEEL COST ADJUSTMENT (BDE).....	113
SUBCONTRACTOR AND DBE PAYMENT REPORTING (BDE)	115

CLEANING AND PAINTING BEARINGS

Description: This work shall consist of the satisfactory cleaning and painting of the steel materials on the existing bridge bearings as indicated on the plans and to the satisfaction of the Engineer. This work also includes cleaning and painting all appurtenances associated with the bearings including retainer angles or plates and anchors at the bridge seats, if present.

The work also includes the satisfactory collection and disposal of paint cleaning residues and all debris generated by the cleaning process in accordance with the specifications. Containment of paint cleaning residues per IDOT GBSP 26 or 60 will not be required, but manual tools with vacuum systems shall be utilized to complete the work.

Materials: Paint materials shall be according to the following special provision:

- 1) GBSP 25, "Cleaning and Painting Existing Steel Structures"

Construction Requirements: The existing bridge bearings shall be cleaned and painted in accordance with the following special provision:

- 1) GBSP 25, "Cleaning and Painting Existing Steel Structures"

Method of Measurement: This work will be measured for payment per Each completed and accepted.

Basis of Payment: This work will be paid for at the contract unit price per each for CLEANING AND PAINTING BEARINGS, which price shall include all material, equipment, and labor to satisfactorily complete the work.

Revised April 14, 2023

This page left blank intentionally.

This page left blank intentionally.

This page left blank intentionally.

This page left blank intentionally.

This page left blank intentionally.

This page left blank intentionally.

This page left blank intentionally.

This page left blank intentionally.

This page left blank intentionally.

This page left blank intentionally.

This page left blank intentionally.

This page left blank intentionally.

This page left blank intentionally.

This page left blank intentionally.

This page left blank intentionally.

This page left blank intentionally.

This page left blank intentionally.

This page left blank intentionally.

This page left blank intentionally.

This page left blank intentionally.

This page left blank intentionally.

This page left blank intentionally.

This page left blank intentionally.