



# Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

April 18, 2023

SUBJECT: Route FAU 9884 (Belvidere Road)  
Section 21-00689-00-SP  
Winnebago County  
Contract No. 85739  
Item 153  
April 28, 2023 Letting  
Addendum A

## NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

### **1. Revised page 11 of the Special Provisions.**

Prime contractors must utilize the enclosed material when preparing their bid and must include any changes to the Schedule of Prices in their bid.

Very truly yours,

A handwritten signature in black ink, appearing to read 'Jack A. Elston'.

Jack A. Elston, P.E.  
Bureau Chief, Design and Environment

~~Milled pavement shall be resurfaced before opening the road to traffic.~~

Milled pavement shall be resurfaced within 10 calendar days.

Two (2) changeable message signs shall be placed on this project two (2) weeks prior to the start of work informing the public of lane closures. Location of the message signs will be determined by the Resident Engineer.

The Contractor shall furnish, erect and maintain signs and message boards as detailed in the Highway Standards and as directed by the Engineer. This work will be paid for at the contract unit price per LUMPSUM for TRAFFIC CONTROL AND PROTECTION SPECIAL.

#### SIGN PANEL TYPE 1 SPECIAL

This work shall consist of furnishing, fabricating, and/or installing sign panels, complete with sign faces, legend, and supplemental sign panels in accordance with Section 720 of the Standard Specifications for Road and Bridge Construction adopted on Jan 1, 2022.

All yellow color signs shall be of Reflective Sheeting Type AP meeting the specifications for reflective sheeting shown in the "Manual on Uniform Traffic Control Devices" 2009 Edition, and shall conform to the "State of Illinois Supplement to the Manual of Uniform Traffic Control Devices for Streets and Highways 2009 and all applicable sections of "Standard for Road and Bridge Construction" adopted Jan 1, 2022 and the 'Supplemental Specifications and Recurring Special Provisions" adopted January 1, 2023.

The sign panels shall be manufactured, furnished, and installed in accordance with the requirements for sign panels in Section 720 and Section 1091 of the "Standard Specifications for Road and Bridge Construction", adopted Jan 1, 2022 and Standards 720001 and 720006.

Each complete sign shall have a sticker either in symbol or words, the name of the fabricator, the year of fabrication and "WINNEBAGO COUNTY HIGHWAY DEPARTMENT" on the back of the sign face at the lower edge of the sign. The letter size shall be 3/8" height. Sign faces, which are installed without this information, will not be accepted.

#### Plaques:

All plaques shall be manufactured, furnished and installed in accordance with the requirements of section 720 of the Standard Specifications for Road and Bridge Construction.

All sign base/ panels shall have mill test report included with the shipment showing compliance with applicable sections of the "Manual on Uniform Traffic Control Devices" 2009 Edition with the "2009 Illinois Supplement" and all applicable sections of the "Standard Specifications for Road and Bridge Construction", adopted Jan 1, 2022 and the "Supplemental Specifications and Recurring Special Provisions" adopted Jan 1, 2023. The mill test report will not be paid for separately and it shall be incidental to the cost each of sign and post.

See the plans, the summary of quantities and the schedule of quantities for detail.

Before starting the installation of sign panel assemblies, the bidder shall contact JULIE for the exact location of all utilities in the field for each location.