INDEX TO SHEETS

SHEET TITLE
COVER SHEET - INDEX TO SHEETS
QUANTITIES

SITE PLAN AND CONTROL

CONSTRUCTION SAFETY PHASING PLAN (CSPP)

CONSTRUCTION SAFETY PHASING NOTES - 1

CONSTRUCTION SAFETY PHASING NOTES - 2

EXISTING CONDITIONS AND PROPOSED REMOVALS

TYPICAL SECTIONS
PROPOSED GEOMETRY AND JOINTING PLAN
PAVING DETAILS - 1

PAVING DETAILS - 2
STAKING PLAN
DRAINAGE AND LANDSCAPING PLAN
DRAINAGE DETAILS

INDEX TO SECTIONS

CROSS SECTIONS - 1

CROSS SECTIONS - 2 CROSS SECTIONS - 3

JOINT UTILITY LOCATING INFORMATION FOR EXCAVATORS

www.illinois1call.com

SHEET NUMBER

15

17

Know what's **below. Call** before you dig.


CITY OF DEKALB DEKALB COUNTY, ILLINOIS


CONSTRUCTION PLANS FOR DEKALB TAYLOR MUNICIPAL AIRPORT

REMOVE AND REPLACE A PORTION OF THE AIRCRAFT PARKING APRON

ILLINOIS PROJECT: DKB-4924 S.B.G. PROJECT: 3-17-SBGP-184

MARCH 3, 2023






EXCAVATING AT 811 DEKALB TAYLOR MUNICIPAL AIRPORT

CALL J.U.L.I.E. BEFORE

TOWNSHIP: 40 NORTH RANGE: 5 EAST SECTION: 17, 18 AND 19 COUNTY: DEKALB TOWNSHIP: CORTLAND

DESIGN INFORMATION

DESIGN AIRCRAFT APPROACH CATEGORY D
DESIGN AIRCRAFT GROUP III (GULFSTREAM V)



CALL J.U.L.I.E. FOR UTILITY INFORMATION AT 811. CALL J.U.L.I.E. FOR UTILITY INFORMATION AT 811. CITY OF DEKALB DEKALB TAYLOR MUNICIPAL AIRPORT 3232 PLEASANT STREET DEKALB, ILLINOIS 60115 Telephone: 815.748.8102 APPROVED BY RENEE RIANI/AIRPORT MANAGER MARCH 3

THE LOCATION, SIZE AND TYPE OF MATERIAL OF EXISTING UNDERGROUND UNITIES INDICATED ON THE PLANS IS NOT REPRESENTED AS BEING ACCURATE, SUFFICIENT OR COMPLETE IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO

DETERMINE ACTUAL LOCATIONS OF ALL SUCH FACILITIES, INCLUDING SERVICE

DETERMINE AT ORAL ECONTINS OF ALL SOOT PACIETIES, INCLUDING SERVICE CONNECTIONS TO UNDERGROUND UILITIES, PRIOR TO CONSTRUCTION, THE CONTRACTOR SHALL NOTIFY UTILITY COMPANIES OF HIS OPERATIONAL PLANS, OBTAIN FROM RESPECTIVE UTILITY COMPANIES DETAILED INFORMATION AND

ASSISTANCE RELATIVE TO THE LOCATION OF THEIR FACILITIES AND THE WORKING SCHEDULE OF THE COMPANIES FOR REMOVAL OR ADJUSTMENT WHERE REQUIRED IN THE EVENT AN UNEXPECTED UTILITY INTERFERENCE IS ENCOUNTERED DURING

CONSTRUCTION, THE CONTRACTOR SHALL IMMEDIATELY NOTIFY THE UTILITY COMPANY OF JURISDICTION AND THE ONE-CALL NOTICE SYSTEM. THE ENGINEER SHALL ALSO BE IMMEDIATELY NOTIFIED. ANY SUCH UTILITY OR SERVICES SHALL BE

LOCATION MAP

SITE PLAN

| SUMMARY OF QUANTITIES | | | | |
|-----------------------|------------------------------------|------|----------|-----------------|
| ITEM | DESCRIPTION | UNIT | QUANTITY | RECORD QUANTITY |
| AR150510 | ENGINEER'S FIELD OFFICE | LS | 1.00 | |
| AR150520 | MOBILIZATION | LS | 1.00 | |
| AR152410 | UNCLASSIFIED EXCAVATION | CY | 850.00 | |
| AR152480 | SHOULDER ADJUSTMENT | SY | 600.00 | |
| AR208515 | POROUS GRANULAR EMBANKMENT | CY | 225.00 | |
| AR209606 | CRUSHED AGGREGATE BASE COURSE - 6" | SY | 5,350.00 | |
| AR401610 | BITUMINOUS SURFACE COURSE | TON | 50.00 | |
| AR401900 | REMOVE BITUMINOUS PAVEMENT | SY | 5,300.00 | |
| AR403610 | BITUMINOUS BASE COURSE | TON | 250.00 | |
| AR501510 | 10" PCC PAVEMENT | SY | 4,950.00 | |
| AR501530 | PCC TEST BATCH | EACH | 1.00 | |
| AR501900 | REMOVE PCC PAVEMENT | SY | 35.00 | |
| AR510900 | REMOVE TIE DOWN | EACH | 7.00 | |
| AR510901 | REMOVE TIE DOWN - TYPE A | EACH | 5.00 | |
| AR602510 | BITUMINOUS PRIME COAT | GAL | 110.00 | |
| AR603510 | BITUMINOUS TACK COAT | GAL | 80.00 | |
| AR620900 | PAVEMENT MARKING REMOVAL | SF | 1,450.00 | |
| AR705526 | 6" PERFORATED UNDERDRAIN W/SOCK | LF | 1,250.00 | |
| AR705610 | CONCRETE HEADWALL FOR UNDERDRAIN | EACH | 1.00 | |
| AR705640 | UNDERDRAIN CLEANOUT | EACH | 8.00 | |
| AR705900 | REMOVE UNDERDRAIN | LF | 100.00 | |
| AR705904 | REMOVE UNDERDRAIN CLEANOUT | EACH | 2.00 | |
| AR901510 | SEEDING | ACRE | 0.15 | |
| AR908515 | HEAVY-DUTY HYDRAULIC MULCH | ACRE | 0.15 | |

IL. CONTRACT: **DK063**

IL. LETTING ITEM: 01A IL. PROJECT: **DKB-4924** S.B.G. PROJECT: **3-17-SBGP-184**

SURVEY BOOK # ----

| CONTET BOOK # | | | |
|---------------|-----------|------|--|
| | REVISIONS | | |
| NUMBER | BY | DATE | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |

THIS BAR IS EQUAL TO 2" AT FULL SCALE (34X22).


DEKALB TAYLOR MUNICIPAL AIRPORT DEKALB, ILLINOIS REMOVE AND REPLACE A PORTION OF THE AIRCRAFT PARKING APRON QUANTITIES


CRAWFORD, MURPHY & TILLY, INC.
CONSULTING ENGINEERS
License No. 184-000613

DESIGN BY: CMT-RFD DRAWN BY: CMT-RFD CHECKED BY: CMT-RFD APPROVED BY: DJK 3/3/2023 DATE: JOB No: 210248-02

FINAL

SHEET 2 OF 18 SHEETS





GENERAL

- THE CONTRACTOR AND ALL SUBCONTRACTORS SHALL FOLLOW THE REQUIREMENTS OF THE AIRPORT'S APPROVED CONSTRUCTION SAFETY AND PHASING PLAN (CSPP), FAA AC 150/5370-2G OR LATEST EDITION, AND ALL AIRPORT SAFETY AND SECURITY REQUIREMENTS
- PRIOR TO THE NOTICE TO PROCEED, THE CONTRACTOR SHALL SUBMIT TO THE AIRPORT THROUGH THE RESIDENT ENGINEER, FOR APPROVAL A SAFETY PLAN COMPLIANCE DOCUMENT (SPCD) IN ACCORDANCE WITH FAA AC 150/5370-2G OR LATEST EDITION. NO CONSTRUCTION ACTIVITY SHALL BEGIN UNTIL THE AIRPORT HAS APPROVED THE SPCD.
- THE CSPP COVERS OPERATIONAL SAFETY. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE INDIVIDUAL SAFETY OF HIS/HER PERSONNEL AND MEETING OSHA REQUIREMENTS.
- A MINIMUM OF 10 DAYS PRIOR TO THE NOTICE TO PROCEED THE CONTRACTOR SHALL PROVIDE A LIST OF SUBCONTRACTORS AND MATERIAL SUPPLIERS.
- ALL CONTRACTOR COSTS ASSOCIATED WITH THE REQUIREMENTS LISTED ON THIS SHEET SHALL BE CONSIDERED INCIDENTAL TO THE CONTRACT

1. COORDINATION

- PRIOR TO THE START OF CONSTRUCTION THE CONTRACTOR SHALL ATTEND A PRE-CONSTRUCTION CONFERENCE WITH THE AIRPORT, RESIDENT ENGINEER, AND ILLINOIS DIVISION OF AERONAUTICS (IDA). THE COST OF PREPARING FOR AND ATTENDING THE PRE-CONSTRUCTION CONFERENCE SHALL BE INCIDENTAL TO THE CONTRACT.
- ON OR BEFORE THE PRE-CONSTRUCTION CONFERENCE, THE CONTRACTOR SHALL SUBMIT A PROPOSED SCHEDULE FOR THE PROJECT. THE SCHEDULE SHALL INCLUDE A START AND COMPLETION DATE FOR EACH ITEM OF WORK. THE SCHEDULE SHALL BE UPDATED ON A WEEKLY BASIS. ALL COSTS ASSOCIATED WITH THE SCHEDULE SHALL BE INCIDENTAL TO THE CONTRACT.
- DURING CONSTRUCTION THE CONTRACTOR SHALL ATTEND A WEEKLY COORDINATION MEETING WITH THE AIRPORT STAFF AND RESIDENT ENGINEER. ALL COSTS ASSOCIATED WITH ATTENDING THE WEEKLY MEETING SHALL BE INCIDENTAL TO THE CONTRACT.

2. PHASING

- TOTAL CONTRACT TIME SHALL BE 47 CALENDAR DAYS.
- PHASING SHALL BE AS NOTED BELOW AND AS SHOWN ON THE SITE PLAN SHEETS

WORK AREAS AND DESCRIPTIONS

MOBILIZATION

COMPLETE MOBILIZATION DURING THE MOBILIZATION TIME PERIOD.

WORK AREAS

WORK AREA GENERALLY INCLUDES PAVEMENT REMOVALS, UNDERGROUND DRAIN REMOVALS, UNCLASSIFIED EXCAVATION, UNDERDRAIN IMPROVEMENTS, CONCRETE PAVING, ASPHALT PAVING, AND LANDSCAPING.

RESTRICTIONS

GENERAL (ALL WORK AREAS)

ALL WORK AREAS ARE LOCATED INSIDE THE AOA SECURITY FENCE, AND ARE SUBJECT TO THE LIMITATIONS DESCRIBED IN SPECIFICATIONS, PART 1 - GENERAL PROVISIONS.

WORK CONDUCTED UTILIZING EXTENDED CLOSURES OF AIRFIELD PAVEMENTS AS INDICATED IN THE PLANS WILL ALLOW THE CONTRACTOR TO CONDUCT WORK 24 HOURS A DAY, 7 DAYS A WEEK OR UNLESS SPECIFICALLY NOTED FOR THE RESTRICTIONS IN EACH WORK AREA. THE CLOSURES WILL ALLOW THE CONTRACTOR TO COMPLETE ALL WORK INSIDE THE RESPECTIVE TOFA. OFZ OR RSA. AND TO A DISTANCE OUTSIDE THESE AREAS AS NOT TO RE-ENCROACH THE TOFA, OFZ OR RSA WITH MANPOWER OR EQUIPMENT ONCE THE CLOSURE PERIOD IS CONCLUDED.

SIMULTANEOUS CLOSURES OF AIRFIELD PAVEMENTS TO COMPLETE WORK IN MORE THAN ONE WORK AREA AT A TIME WILL NOT BE ALLOWED EXCEPT

THE APRON MUST BE OPEN FOR THE AIRVENTURE OSHKOSH FLY-IN SCHEDULED IN JULY. THE TIME PERIOD OF JULY 4 - JULY 31, 2024 SHALL HAVE ALL PAVEMENT AREAS AVAILABLE FOR USE FOR AIR TRAFFIC. THIS EVENT MUST BE ACCOUNTED FOR IN THE CONSTRUCTION SCHEDULE.

WORK AREA 1A

AN EXTENDED CLOSURE OF A PORTION OF THE APRON AND TAXIWAY A IS REQUIRED TO COMPLETE WORK. TAXIWAY A WILL BE CLOSED WEST OF TAXIWAY B3. ALL LOCATIONS WITHIN THE TOFA WILL BE RESTORED TO FAA SAFETY CRITERIA BEFORE RE-OPENING THE TAXIWAYS AT END OF THE CLOSURE PERIOD.

3. AREAS AND OPERATIONS AFFECTED BY THE CONSTRUCTION ACTIVITY

- ALL RUNWAYS, TAXIWAYS AND APRONS SHALL BE KEPT OPEN TO AIRCRAFT TRAFFIC DURING CONSTRUCTION EXCEPT AS NOTED ON THE PHASING
- WHEN CONFLICTS ARISE BETWEEN CONSTRUCTION ACTIVITIES AND AIRCRAFT OPERATIONS AND SAFETY, AIRCRAFT OPERATIONS AND SAFETY SHALL TAKE PRECEDENCE AND SHALL GOVERN. FINAL AUTHORITY IN THE APPROVAL OF CONSTRUCTION SEQUENCING LIES WITH THE AIRPORT.
- ALL CONSTRUCTION TRAFFIC SHALL IMMEDIATELY YIELD TO ONCOMING AIRCRAFT AT ALL TIMES.

4. NAVAIDS THAT COULD BE AFFECTED

- 1. THE CONTRACTOR MUST COORDINATE WITH AIRPORT OPERATIONS/ENGINEER IN ADVANCE FOR ANY WORK WITHIN A NAVAID CRITICAL AREA OR AFFECTING THE VISUAL, TRANSMITTED SIGNAL OR POWER SUPPLY OF A NAVAID.
- 2. EDGE LIGHTS, THRESHOLD LIGHTS, VISUAL AIDS AND ALL ILS EQUIPMENT SHALL BE SHUT OFF FOR THE DURATION OF A CLOSURE PERIOD ON ANY ASSOCIATED PAVEMENTS. IF THE LIGHTING CIRCUIT MUST BE ON FOR OPEN PAVEMENT AREAS, CLOSED PAVEMENT AREA LIGHTS SHALL BE COVERED COMPLETELY.
- EXCEPT WHERE NOTED IN THE PLANS, EXISTING COMMUNICATIONS EQUIPMENT AND NAVIGATIONAL AIDS (NAVAIDS) SHALL NOT BE DISTURBED BY THE CONTRACTOR AND SHALL BE PROTECTED FROM
- 4. PRIOR TO BEGINNING SITE WORK, CONTRACTOR SHALL COORDINATE THROUGH AIRPORT OPERATIONS TO LOCATE, AND THE CONTRACTOR TO MARK ALL UNDERGROUND COMMUNICATIONS CABLES AND FACILITIES, WITHIN THE PROJECT AREA
- 5. IF CONTRACTOR CAUSES INTERRUPTION OF POWER OR COMMUNICATIONS TO A NAVAID CONTRACTOR SHALL REPAIR WITHIN 24 HOURS AT THE CONTRACTOR'S COST, CONTRACTOR MUST COORDINATE REPAIR WITH AIRPORT OPERATIONS BEFORE ANY REPAIR IS MADE.

5. CONTRACTOR ACCESS

- CONTRACTOR ACCESS SHALL BE AS NOTED BELOW AND AS SHOWN ON THE SITE PLAN AND CONSTRUCTION ACTIVITY PLAN SHEETS. ALL COSTS RELATING TO CONTRACTOR'S ACCESS AND SECURITY SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR
- THE CONTRACTOR IS TO ACCESS THE SITE USING THE GATE(S) SHOWN. THE CONTRACTOR SHALL BE RESPONSIBLE FOR KEEPING THE ACCESS GATE CLOSED DURING WORK HOURS
- CONTRACTOR SHALL OBTAIN ALL NECESSARY PERMITS AND TEMPORARY EASEMENTS FOR THE PUBLIC ACCESS ROAD(S) SHOWN AND SHALL COMPLY WITH ALL REQUIREMENTS, LOAD RESTRICTIONS, & TRAFFIC CONTROL SIGNAGE REQUIRED BY THE CITY, COUNTY, TOWNSHIP, OR I.D.O.T.
- CONTRACTOR'S VEHICLES AND EQUIPMENT SHALL BE MARKED AND FLAGGED PER SECTION 70-10 OF THE STANDARD SPECIFICATIONS. MAXIMUM HEIGHT OF CONTRACTOR'S
- DRIVERS OF TRUCKS CONTAINING MATERIAL DELIVERIES (AGGREGATE, ASPHALT, ETC.) NEED NOT OBTAIN AN AIRPORT ID BADGE BUT SHALL BE REQUIRED TO SUBMIT THEIR NAME, DRIVER'S LICENSE NUMBER TRUCK LICENSE PLATE NUMBER AND NAME OF TRUCKING COMPANY TO THE PRIME CONTRACTOR PRIOR TO ENTERING THE JOBSITE. WHILE INSIDE THE AOA FENCE, THE TRUCK DRIVERS SHALL BE ESCORTED BY THE CONTRACTOR PERSONNEL THAT HAS OBTAINED PROPER DRIVING PRIVILEGES.
- CONTRACTOR WORK CREWS MUST MAINTAIN RADIO CONTACT WITH THE AIRPORT UNICOM (122.70 MHZ) AT ALL TIMES WHEN INSIDE THE AIRPORT OPERATIONS AREA (AOA). THE CONTRACTOR SHALL SUPPLY ALL APPROPRIATE RADIOS NEEDED FOR COMMUNICATIONS AND ONLY HIS PERSONNEL WHO HAVE SUCCESSFULLY SATISFIED THE AIRPORT OF THEIR COMPETENCE MAY OPERATE THESE BADIOS
- THE CONTRACTORS STORAGE AND STAGING AREAS WILL BE AS SHOWN ON THE SITE PLAN.
- THE CONTRACTOR SHALL KEEP A RECORD OF THE NAMES OF ALL EMPLOYEES ENTERING THE JOB SITE ON A DAILY BASIS. A RECORD OF EACH SUBCONTRACTOR ENTERING THE JOB SITE SHALL ALSO BE KEPT BY THE CONTRACTOR
- WHEN THE CONTRACTOR IS NOT WORKING, EQUIPMENT SHALL BE STORED AT THE STAGING AREAS.
- DURING ADVERSE WEATHER THE CONTRACTOR SHALL MAINTAIN ACCESS TO THE WORK AT NO ADDITIONAL COST TO THE CONTRACT. NO EXTENSION OF THE CONTRACT TIME WILL BE CONSIDERED FOR DELAYS DUE TO LACK OF ADEQUATE ACCESS TO THE WORK SITE.

- 11. THE CONTRACTOR WILL BE PERMITTED TO STORE **EQUIPMENT AND MATERIALS ONLY AT THE LOCATIONS** SHOWN. PARKED EQUIPMENT AND MATERIAL STOCKPILES SHALL NOT PENETRATE SURFACES DEFINED BY F.A.R. TITLE 14 PART 77 - OBJECTS AFFECTING NAVIGABLE AIRSPACE EXISTING TURF AREAS DISTURBED BY THE CONTRACTOR'S OPERATIONS SHALL BE RESTORED BY HIM AT HIS EXPENSE TO THE SATISFACTION OF THE RESIDENT ENGINEER AND THE
- ALL CONSTRUCTION TRAFFIC OPERATING ON, OR CROSSING RUNWAYS, TAXIWAYS AND APRONS OPEN TO AIRCRAFT TRAFFIC SHALL BE UNDER CONTROL BY A FLAGMAN OR ESCORT IN RADIO CONTACT WITH THE COMMON TRAFFIC ADVISORY FREQUENCY. THE CONTRACTOR SHALL PROVIDE HIS OWN FLAGMEN.
- THE CONTRACTOR SHALL THOROUGHLY CLEAN ALL CONSTRUCTION AREAS AND HAUL ROUTES WHICH WILL BE OPENED TO AIR TRAFFIC TO THE SATISFACTION OF AIRPORT OPERATIONS OR THE RESIDENT ENGINEER. A POWER BROOM AND OPERATOR SHALL BE ON SITE AT ALL TIMES WHEN ACTIVE PAVEMENTS ARE UTILIZED FOR CONSTRUCTION
- 14. ALL PAVEMENTS, DRIVES OR ANY OTHER AREAS UTILIZED BY THE CONTRACTOR FOR HAUL ROADS OR STORAGE AREAS SHALL BE MAINTAINED AND REPAIRED TO THE SAME CONDITION OR BETTER THAN THEY WERE PRIOR TO BEGINNING CONSTRUCTION, NO ADDITIONAL COMPENSATION WILL BE MADE TO THE CONTRACTOR FOR THIS WORK.
- ALL VEHICLE AND EQUIPMENT OPERATORS USED BY THE CONTRACTOR SHALL BE PROPERLY TRAINED BY THE
- THE CONTRACTOR SHALL NOTIFY THE AIRPORT IF CONSTRUCTION ACTIVITY WILL REQUIRE THE BLOCKAGE OF EMERGENCY ACCESS TO THE AIRPORT

6. WILDLIFE MANAGEMENT

- THE CONTRACTOR SHALL NOTIFY THE AIRPORT OR THE RESIDENT ENGINEER IF ANY WILDLIFE IS SEEN ENTERING THE AIRPORT
- CONTRACTOR ACCESS GATES SHALL REMAIN CLOSED WHEN THE CONTRACTOR IS NOT WORKING.
- THE CONTRACTOR SHALL DISPOSE OF ALL TRASH INCLUDING FOOD SCRAPS IN APPROVED CONTRACTOR PROVIDED CONTAINERS.

7. FOREIGN OBJECT DEBRIS (FOD) MANAGEMENT

- THE CONTRACTOR SHALL PICK UP ANY FOREIGN OBJECT DEBRIS (FOD) SEEN ON THE AIRFIELD PAVEMENTS.
- THE CONTRACTOR SHALL SECURE ALL LOOSE ITEMS FROM VEHICLES PRIOR TO DRIVING ON AIRFIELD PAVEMENTS.

8. HAZARDOUS MATERIALS (HAZMAT) MANAGEMENT

THE CONTRACTOR SHALL DEVELOP A HAZMAT MANAGEMENT PLAN AND KEEP COPIES ON THE JOBSITE OF MATERIAL SAFETY DATA SHEETS (MSDS) FOR ALL MATERIALS HANDLED ON THE JOBSITE.

9. NOTIFICATION OF CONSTRUCTION ACTIVITIES

- THE CONTRACTOR SHALL PROVIDE A 24 HOUR EMERGENCY CONTACT PERSON AND PHONE NUMBER.
- THE CONTRACTOR SHALL GIVE A MINIMUM OF 10 DAYS NOTICE TO THE FAA AND AIRPORT PRIOR TO THE CLOSURE OF ANY RUNWAY SO THAT THE FAA MAY DEACTIVATE THE FAA - OWNED NAVAIDS.
- THE CONTRACTOR SHALL GIVE A MINIMUM 30 DAYS NOTICE TO THE AIRPORT, AND PRIOR TO THE PRE-CONSTRUCTION CONFERENCE, PRIOR TO CLOSING ANY RUNWAY OR TAXIWAY PAVEMENT SO THAT THE PROPER NOTAMS MAY BE ISSUED BY THE AIRPORT FOR COORDINATION WITH THE AIRPORT TENANTS
- FOR ANY EQUIPMENT USED BY THE CONTRACTOR WITH A HEIGHT GREATER THAN 25', THE CONTRACTOR SHALL PROVIDE TO THE AIRPORT THE TYPE OF EQUIPMENT, TOTAL HEIGHT, AND LOCATION WHERE THE EQUIPMENT WILL BE USED. THE AIRPORT WILL SUBMIT FAA FORM 7460-1 TO THE FAA FOR AN AIRSPACE STUDY. NO EQUIPMENT WITH A HEIGHT GREATER THAN 25' SHALL BE USED UNTIL A DETERMINATION FROM FAA IS RECEIVED.
- 5. IN THE EVENT OF AN EMERGENCY, THE CONTRACTOR SHALL CALL 911.

10. INSPECTION REQUIREMENTS

- THE CONTRACTOR SHALL INSPECT THE JOBSITE DAILY TO ENSURE COMPLIANCE WITH THE CSPP. THE CHECKLIST FOUND IN APPENDIX 3 OF FAA AC 150/5370-2G OR LATEST EDITION MAY BE USED TO AID IN THE INSPECTIONS
- THE CONTRACTOR SHALL REQUEST OPERATIONAL INSPECTION OF EACH PHASE WORK AREA PRIOR THE AREA BEING REOPENED. THE AIRPORT WILL DETERMINE IF THE WORK AREA IS ALLOWED TO BE

11. UNDERGROUND UTILITIES

- IT WILL BE NECESSARY FOR THE CONTRACTOR TO MAKE HIS OWN FIELD INVESTIGATION TO DETERMINE THE EXACT LOCATION OF THE UNDERGROUND UTILITIES AT CRITICAL POINTS. THE LOCATION OF UNDERGROUND UTILITIES AS INDICATED ON THE PLANS HAS BEEN OBTAINED FROM EXISTING RECORDS. NEITHER THE OWNER NOR THE ENGINEER ASSUMES ANY RESPONSIBILITY IN RESPECT TO THE ACCURACY, COMPLETENESS OR SUFFICIENCY OF THE INFORMATION. ANY UTILITY, INCLUDING AIRFIELD ELECTRICAL CABLE AND LIGHTS, DAMAGED BY THE CONTRACTOR SHALL BE REPAIRED BY HIM AT HIS OWN EXPENSE IN A MANNER WHICH IS SATISFACTORY TO THE ENGINEER AND TO THE OWNER OF THE UTILITY. ANY REPAIRS THAT MUST BE MADE BY THE OWNER OF THE UTILITY SHALL HAVE THE COST REIMBURSED TO THE UTILITY BY THE CONTRACTOR. AIRFIELD LIGHTING CABLES DAMAGED BY THE CONTRACTOR SHALL BE REPAIRED BY A QUALIFIED ELECTRICIAN WITH THE COSTS TO BE BORNE BY THE CONTRACTOR.
- BEFORE INITIATING ANY DIGGING, DRILLING OR EXCAVATING ON THE AIRPORT PROPERTY, THE CONTRACTOR SHALL CALL J.U.L.I.E. AND CONTACT THE LOCAL FAA OFFICE TO ARRANGE FOR LITHLITY LOCATES. SEE SECTION 70-17 OF THE SPECIAL PROVISIONS FOR UTILITY CONTACT INFORMATION.

12. PENALTIES

NONCOMPLIANCE BY THE CONTRACTOR WITH AIRPORT RULES AND REGULATIONS OR FAILURE TO COMPLY WITH THE AIRPORT'S APPROVED CSPP AND THE CONTRACTOR'S APPROVED SPCD MAY RESULT IN FINES AS ALLOWED BY LAW.

13. SPECIAL CONDITIONS

ADJACENT CONSTRUCTION MAY IMPACT THE OPERATIONS OF THE CONTRACTOR. SEE THE COORDINATION NOTES FOR ADDITIONAL INFORMATION.

14. RUNWAY AND TAXIWAY VISUAL AIDS

- ALL RUNWAYS, TAXIWAYS, AND APRONS SHALL BE KEPT OPEN TO AIRPORT TRAFFIC DURING CONSTRUCTION EXCEPT AS NOTED IN
- IF ANY RUNWAY OR TAXIWAY CLOSURES ARE REQUESTED BY THE CONTRACTOR AND APPROVED BY THE AIRPORT, THE CONTRACTOR SHALL USE MARKING, LIGHTING AND SIGNS THAT FOLLOWING THE REQUIREMENTS OF FAA AC 150/5370-2G OR LATEST EDITION

15. MARKING AND SIGNS FOR ACCESS ROUTES

BARRICADES AND SIGNS SHALL BE USED ALONG THE CONTRACTOR'S ACCESS ROUTE AS DETAILED ON THE CONSTRUCTION ACTIVITY PLAN SHEETS.

16. HAZARD MARKING AND LIGHTING

- THE CONTRACTOR SHALL FURNISH, ERECT, AND MAINTAIN MARKINGS AND ASSOCIATED LIGHTING OF OPEN TRENCHES, EXCAVATIONS, TEMPORARY STOCKPILES, AND HIS/HER CONSTRUCTION EQUIPMENT.
- ALL CONSTRUCTION EQUIPMENT SHALL BE FLAGGED AND/OR LIGHTED IN ACCORDANCE WITH FAA ADVISORY CIRCULAR 150/5370-2G AND 150/5210-5D OR LATEST EDITION AT ALL TIMES WHILE OPERATING ON AIRPORT PROPERTY. THE MAXIMUM EQUIPMENT HEIGHT IS 25'.
- BARRICADES SHALL BE PLACED AT THE LOCATIONS SHOWN ON THE CONSTRUCTION ACTIVITY PLAN SHEET OR AS DIRECTED BY THE
- THE CONTRACTOR SHALL INSPECT THE BARRICADES ONCE DURING EACH WORK DAY TO INSURE PROPER PLACEMENT AND PROPER OPERATION OF THE RED LIGHTS AND FLAG PLACEMENT.

IL. CONTRACT: **DK063**

S.B.G. PROJECT: 3-17-SBGP-184

IL. LETTING ITEM: 01A IL. PROJECT: DKB-4924

URVEY BOOK # ---

| | REVISIONS | |
|--------|-----------|------|
| NUMBER | BY | DATE |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

THIS BAR IS FOUAL TO 2"

AT FULL SCALE (34X22).

NOTES P B, ILLINOIS ACE A PORTION C **PHASING** B, ILLIN SAFETY PA

AIRPOR'

DEKALB

TAYLOR DEKAL ND REPL CRAFT R CONSTRUCTION A Ш **EMOV**

HY & NEERS U

DESIGN BY CMT-RFD DRAWN BY CMT-RFD CHECKED BY CMT-RFD APPROVED BY 3/3/2023 JOB No 210248-02

FINAL

SHEET 5 OF 18 SHEETS

17. WORK ZONE LIGHTING FOR NIGHTTIME CONSTRUCTION


- WORK PERFORMED BY THE CONTRACTOR OUTSIDE OF DAYLIGHT HOURS SHALL BE DONE UNDER SUFFICIENT ARTIFICIAL AREA LIGHTING TO ALLOW FOR PROPER CONSTRUCTION METHODS AND INSPECTION
- LIGHTS SHALL CONSIST OF VEHICLE OR MOVABLE POLE MOUNTED FLOODLIGHTS AND/OR SPOTLIGHTS OF SUFFICIENT NUMBER TO ILLUMINATE THE WORK AREA. VEHICLE HEADLIGHTS WILL BE ALLOWED ONLY IN ADDITION TO OTHER LIGHTS MENTIONED ABOVE, LIGHTING SHALL NOT INTERFERE WITH AIR OPERATIONS. ANY WORK BEING PERFORMED UNDER INSUFFICIENT ARTIFICIAL LIGHTING, IN THE RESIDENT ENGINEER'S JUDGEMENT, SHALL BE STOPPED UNTIL SUCH TIME AS ADDITIONAL LIGHTING IS PROVIDED. ALL WORK PERFORMED DURING THAT TIME WILL NOT BE ACCEPTABLE UNTIL PROPER INSPECTION AND TESTING CAN BE MADE.

18. PROTECTION

- 1. ALL WORK REQUIRED INSIDE OF THE RUNWAY SAFETY AREA WILL REQUIRE THE
- 2. ALL WORK REQUIRED ON AN ACTIVE TAXIWAY OR INSIDE OF AN ACTIVE TAXIWAY OBJECT FREE AREA, WILL REQUIRE THE TAXIWAY TO BE CLOSED.

19. OTHER LIMITATIONS ON CONSTRUCTION

- IF, DURING CONSTRUCTION, AN EMERGENCY IS DECLARED BY THE AIRPORT, THE CONTRACTOR SHALL IMMEDIATELY CLEAR THE PAVEMENT OF ALL VEHICLES, PERSONNEL AND EQUIPMENT.
- BROKEN CONCRETE, BROKEN ASPHALT, RUBBISH FROM DEMO, AND OTHER MISCELLANEOUS DEBRIS SHALL BE DISPOSED OF OFF AIRPORT PROPERTY, UNLESS OTHERWISE SPECIFIED.
- THE CONTRACTOR WILL BE RESPONSIBLE FOR COORDINATING THE AIRSPACE FOR THE CONSTRUCTION EQUIPMENT THAT IS TALLER THAN THAT SPECIFIED ON THE PLANS WITH THE FAA. THIS PROCESS MAY TAKE UP TO 12 WEEKS TO
- THE CONTRACTOR SHALL BE RESPONSIBLE FOR MEGGAR TESTING ALL EXISTING CIRCUITS PRIOR TO CONSTRUCTION AND FOLLOWING CONSTRUCTION AS SPECIFIED IN THE CONTRACT DOCUMENTS.




CONSTRUCTION SETBACK LINE DETAIL

CONSTRUCTION SETBACK NOTES

- 1. CONTRACTOR SHALL MARKER THE RUNWAY SAFETY AREA AND TAXIWAY CONSTRUCTION SETBACK DETAIL AS DIRECTED BY THE RESIDENT ENGINEER
- 2. ALL COST ASSOCIATED WITH THE CONSTRUCTION SETBACK LINE SHALL BE CONSIDERED INCIDENTAL TO THE CONTRACT.

PAYMENT FOR ALL CONSTRUCTION SAFETY MEASURES AND TEMPORARY CONSTRUCTION INCLUDING BUT NOT LIMITED TO TEMPORARY TAXIWAY EDGE LIGHTS AND CABLING, CABLE JUMPERS AND CONNECTIONS, TAXIWAY EDGE SAFETY TREATMENT, COMPACTED MILLINGS WEDGE AND ALL REMOVALS OF TEMPORARY MEASURES AND CONSTRUCTION SHALL BE CONSIDERED INCIDENTAL TO THE CONTRACT.





CONSTRUCTION EQUIPMENT AND VEHICLE SIGNAL FLAG

SIGNAL FLAG NOTES


- ALL CONTRACTOR VEHICLES AND EQUIPMENT SHALL DISPLAY COMPANY LOGO PLACARDS AND FLAG.
- WHEN WORKING PRIOR TO DAWN OR AFTER DUSK, A 360 DEGREE ROTATING AMBER BEACON IS REQUIRED ON ALL EQUIPMENT AND
- CONTRACTOR SHALL REPLACE FLAGS THAT ARE WORN AND

AIRFIELD LIGHTS AND SIGNS NOTES

CONTRACTOR SHALL COVER ALL AIRFIELD SIGNS AND TAXIWAY LIGHTS ON CLOSED TAXIWAYS UNTIL THE TAXIWAY IS RE-OPENED FOR AIRCRAFT USE. THE METHOD AND MATERIALS USED TO COVER THE SIGNS AND LIGHTS SHALL MEET THE ENGINEER'S AND AIRPORT'S APPROVAL. COST INCIDENTAL TO THE CONTRACT. REMOVING LAMPS FROM ENERGIZED FIXTURES AS A MEANS TO REMOVE THE LIGHTS OR FIXTURES FROM SERVICE SHALL NOT BE ACCEPTABLE


CONTRACTOR SHALL PLAN AND PERFORM HIS WORK SO AS NOT TO INTERFERE OR HINDER THE PROGRESS, WORK OR HAUL ROAD ACCESS OF OTHER CONTRACTORS (SEE SPECIAL PROVISIONS SECTION 50-05). THE PRIME CONTRACTOR WILL BE RESPONSIBLE TO COORDINATE CONSTRUCTION ACTIVITIES AND ACCESS BETWEEN ALL ON-SITE CONTRACTORS SUBCONTRACTORS. IT IS ANTICIPATED THE FOLLOWING PROJECTS MAY BE UNDER CONSTRUCTION CONCURRENTLY BUT NOT WITHIN LIMITS OF THIS PROJECT:

REHABILITATE RUNWAY 9/27



IDOT TYPE II BARRICADE

NOT TO SCALE



AIRSIDE LOW PROFILE LIGHTED BARRICADE

BARRICADE NOTES

- 1. FLASHER OR STEADY BURN LIGHTS SHALL BE BATTERY OPERATED. LENS SHALL BE RED
- 2. FACING OF BARRICADE SHALL BE COVERED WITH REFLECTIVE TAPE OR PAINT.
- BARRICADES TO BE PLACED WITH A MAXIMUM OF 4' SPACING END TO END UP TO THE EDGE OF PAVEMENT ALONG OPERATIONAL PAVEMENT ADJACENT TO CONSTRUCTION AS DIRECTED BY THE RESIDENT ENGINEER. ALTERNATE FLASHER OR STEADY BURN LENSES SO THAT EVERY OTHER LENS IS ROTATED 90°.
- 4. FLASHER OR STEADY BURN LIGHTS SHALL BE SECURED TO THE BARRICADES, AS APPROVED BY THE RESIDENT ENGINEER
- 5. BARRICADES SHALL BE OF LOW MASS, EASILY COLLAPSIBLE UPON CONTACT WITH AN AIRCRAFT OR ANY OF IT COMPONENTS, AND WEIGHTED TO AVOID BEING BLOWN OVER.
- 6. BARRICADES SHALL BE OF A COMMERCIAL DESIGN AND SHALL MEET CURRENT FAA
- 7. PLACE ALL BARRICADES OUTSIDE RUNWAY SAFETY AREAS AND OUTSIDE TAXIWAY
- 8. ALL COST ASSOCIATED WITH THE LOW PROFILE BARRICADES SHALL BE CONSIDERED INCIDENTAL TO THE CONTRACT.

IL. CONTRACT: DK063 IL. LETTING ITEM: 01A IL. PROJECT: DKB-4924 S.B.G. PROJECT: 3-17-SBGP-184

SURVEY BOOK # ---

| | REVISIONS | |
|--------|-----------|------|
| NUMBER | BY | DATE |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| 0 | 1 | 2 |
| | | |
| | | |

AT FULL SCALE (34X22).

3 NOTES 픋

R MUNICIPAL AIRPORT LB, ILLINOIS LACE A PORTION OF THI PARKING APRON **PHASING** SAFETY TAYLOR I DEKALE DEKAL AND REPLAIRCRAFT ONSTRUCTION Ш **EMOV**

 $\ddot{\mathbf{o}}$

% S.


DEKALB


U

DESIGN BY CMT-RFD DRAWN BY: CMT-RFD CHECKED BY: CMT-RFD APPROVED BY DATE 3/3/2023 JOB No: 210248-02


FINAL

SHEET 6 OF 18 SHEETS






NEW TERMINAL APRON (SECTION A-A)




EXISTING TERMINAL APRON DEMOLITION (SECTION A-A)

NOT TO SCALE




TURF SHOULDER NOTES:


- 1. TILL AND PULVERIZE EXISTING TURF SHOULDER IN PLACE (COST INCIDENTAL TO SEEDING PAY ITEM).
- 2. LIMITS OF TURF SHOULDER SHALL BE ADJUSTED IN THE FIELD BY THE RESIDENT ENGINEER AS REQUIRED.
- 3. TURF SHALL BE SMOOTHLY GRADED TO THE SATISFACTION OF THE
 RESIDENT ENGINEER BEFORE
 SEEDING. ADDITIONAL
 TOPSOIL WILL BE REQUIRED FOR TURF SHOULDER RESTORATION AND SHALL BE INCIDENTAL TO SHOULDER ADJUSTMENT PAY ITEM.




TURF SHOULDER DETAIL

NOT TO SCALE







ASPHALT PAVEMENT EDGE DETAIL (TYPICAL)

IL. CONTRACT: **DK063** IL. LETTING ITEM: 01A IL. PROJECT: DKB-4924 S.B.G. PROJECT: 3-17-SBGP-184

| SURVEY BOOK | <# | |
|-------------|--------------|-------|
| | REVISIONS | |
| NUMBER | BY | DATE |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| 0 | 1 | 2 |
| THIS | BAR IS EQUAL | TO 2" |

AT FULL SCALE (34X22).

Ŧ


DEKALB TAYLOR MUNICIPAL AIRPORT DEKALB, ILLINOIS REMOVE AND REPLACE A PORTION OF TH AIRCRAFT PARKING APRON TYPICAL SECTIONS


HMU


DESIGN BY: CMT-RFD DRAWN BY: CMT-RFD CHECKED BY: CMT-RFD APPROVED BY DATE 3/3/2023 JOB No: 210248-02

FINAL

SHEET 8 OF 18 SHEETS








REINFORCED FILLET/TAPER SECTION STEEL DETAIL

WIRE FABRIC NOTES:

- 1. PANELS TO BE REINFORCED WITH WIRE FABRIC DENOTED AS "R" ON THE JOINTING PLAN DRAWINGS.
- 2. WIRE FABRIC SHALL BE PLACED AT THE VERTICAL POSITION OF T/3 AS SHOWN.
- 3. WHEN A STRUCTURE IS LOCATED WITHIN A PANEL, WIRE FABRIC SHALL BE PLACED TO WITHIN 3" OF THE STRUCTURE
- 4. MINIMUM WELDED WIRE FABRIC LAP IS 18 INCHES.
- 5. ALL WELDED WIRE FABRIC SHALL BE GRADE 60.
- 6. THE AREA OF WELDED WIRE FABRIC SHALL PROVIDE AT LEAST 0.05% OF REINFORCEMENT AREA TO UNIT CONCRETE AREA, ASSUMING GRADE 60 STEEL.



T = PCC PAVEMENT THICKNESS

URVEY BOOK # ---REVISIONS NUMBER BY DATE THIS BAR IS FOUNDED TO 2" AT FULL SCALE (34X22).

IL. CONTRACT: **DK063**

IL. LETTING ITEM: 01A IL. PROJECT: DKB-4924

S.B.G. PROJECT: 3-17-SBGP-184

픋

ALB TAYLOR MUNICIPAL AIRPORT DEKALB, ILLINOIS E AND REPLACE A PORTION OF TH AIRCRAFT PARKING APRON

EMOV

DEKALB TAYLOR DEKALE

DETAILS

AVING


N.T.S.

WELDED WIRE FABRIC SLAB THICKNESS SUGGESTED FABRIC SIZE 6 x 6 - W 4.0 x W 4.0 6 x 6 - W 5.5 x W 5.5 6 x 6 - W 5.5 x W 5.5 6 x 6 - W 7.5 x W 7.5 23" - 24"

DOWELS ARC WELDED ALTERNATELY TO TOP SPACER BARS #9 GA. WIRE SPACER 5'-0" APART SEE NOTE 1 SEE NOTES 2 & 3 - SPACING AS SHOWN IN JOINTING DETAILS O GA WIRE CHAIRS WELDED TO TOP & BOTTOM SPACER BARS (SEE DETAIL) O GA. WIRE TOP & BOTTOM SPACER BARS - 2 PER ASSEMBLY


DOWEL BASKET ASSEMBLY DETAIL

N.T.S.



DOWEL BAR INSTALLATION DETAIL

N.T.S.



FILLET SHALL STOP AT JOINT IN ADJACENT PAVEMENT

PAVEMENT JOINTS (TYPICAL)

(3) - 10' X #5 TIE BARS EQUALLY SPACED, CONTINUOUS THROUGH JOINTS.

EDGE OF FILLET

JOINTS IN FILLET SHALL BE @ 90° ANGLES TO THE PAVEMENT EDGE.

3' MINIMUM (TYPICAL)

CONTINOUS THROUGH JOINTS.

DENOTES ODD SHAPED REINFORCED PANELS TO

SHAPED PANELS SHALL BE REINFORCED. (REINFORCEMENT NOT SHOWN)

BE REINFORCED WITH DEFORMED WIRE FARRIC AS SHOWN ON THIS SHEET. ALL NON RECTANGULAR

FILLET DETAIL AND FILLET REINFORCING LAYOUT

TYPICAL DOWEL BASKET ELEVATION DETAIL SHOWING CHAIR

DOWEL BASKET DETAILS


N.T.S.


DOWEL BASKET NOTES

- #9 GA. WIRE SPACER BAR ARC WELDED TO THE BOTTOM OF TOP SPACER BAR. (MAY BE MECHANICALLY ATTACHED IN LIEU OF WELDING) 3 REQUIRED PER UNIT.
- 2. DOWEL BAR DIAMETER, LENGTH & SPACING SHALL BE AS SHOWN IN TABLE 1.
- 3. DOWELS SHALL BE EPOXY COATED FULL LENGTH OF DOWEL. IMMEDIATELY PRIOR TO PAVING, THE FREE END OF EACH DOWEL SHALL BE LUBRICATED OR OILED, FOR HALF THE LENGTH OF THE DOWEL.
- 4. T = PCC PAVEMENT THICKNESS

| TABLE 1 | | | | | | | |
|--------------------------|---------|-------------------|----------|-------------------------|----------|-----------|----------|
| PAVEMENT DOWEL THICKNESS | | DOWEL BAR DETAILS | | | | BAR DETAI | LS |
| T - INCHES | DIA. | LENGTH | SPACING | THICKNESS T - INCHES | BAR SIZE | LENGTH | SPACING |
| 5 - 7 | 3/4 " | 18" | 12" O.C. | 6 OR LESS | #4 | 20" | 36" O.C. |
| 7.5 - 12 | 1" | 18" | 12" O.C. | GREATER THAN 6 | #5 | 30" | 30" O.C. |
| 12.5 - 16 | 1 1/4 " | 20" | 15" O.C. | | | | |
| 16.5 - 20 | 1½" | 20" | 18" O.C. | | | | |
| 20.5 - 24 | 2" | 24" | 18" O.C. | | | | |

NOTE: ALL DOWELS CENTERED ON JOINT UNLESS OTHERWISE NOTED





DOWEL PLACEMENT DETAIL


N.T.S.

LEU DESIGN BY:

CMT-RFD DRAWN BY: CMT-RFD CHECKED BY: CMT-RFD APPROVED BY 3/3/2023 JOB No: 210248-02

FINAL

SHEET 10 OF 18 SHEETS




16.5 - 20


1½"

18" O.C

NOTE: ALL DOWELS CENTERED ON JOINT UNLESS OTHERWISE NOTED



CHAMFER/BEVEL JOINT DETAIL



JOINT SEALING AT CONCRETE ASPHALT INTERFACE NOTE: JOINT DIMENSIONS SHALL MEET MANUFACTURER'S RECOMMENDATION

JOINT SEALANT NOTES:

- 1. FACTOR, W/D. FIELD POURED SEALANTS REQUIRE DIFFERENT SEALANT RESERVOIR TO PROVIDE PROPER SHAPE.
- 2. BACKER ROD AND PREMOLDED COMPRESSIBLE MATERIAL MUST BE COMPATIBLE WITH THE DESIRED SHAPE FACTOR. TYPE OF LIQUID SEALANT USED AND SIZED TO PROVIDE THE DESIRED SHAPE
- 3. PLACE TOP OF BACKUP MATERIAL AS SHOWN TO CONFORM TO MANUFACTURER'S SHAPE FACTOR, SEALANT DEPTH ("D") IS MEASURED FROM THE HIGHEST SHAPE FACTORS FOR OPTIMUM PERFORMANCE. CONTRACTOR SHALL SUBMIT MFG. RECOMMENDATIONS ON JOINT RESERVOIR WITH SEALANT SUBMITTAL
- 4. SEALING PROCEDURES SHALL BE IN ACCORDANCE WITH THE MANUFACTURER'S RECOMMENDATIONS.
- ROUTING AND SEALING OF ALL BITUMINOUS AND PCC PAVEMENTS SHALL BE CONSIDERED INCIDENTAL TO THE PORTLAND CEMENT CONCRETE PAVEMENT PAY ITEM.

- POURING OPERATIONS OF THE CLOSURE LANES TO PREVENT VEHICLES FROM ENTERING PLASTIC CONCRETE. IN THE EVENT A VEHICLE ENTERS THE CONCRETE BEFORE A MINIMUM COMPRESSIVE STRENGTH OF 3,500 PSI HAS BEEN OBTAINED, SAID PAVEMENT SHALL BE REMOVED AND REPLACED AT THE CONTRACTOR'S EXPENSE.
- ALL DOWEL BARS SHALL BE SECURELY HELD IN PLACE BY MEANS OF A DOWEL BAR ASSEMBLY WHICH WILL ENSURE THAT THEY WILL REMAIN PARALLEL TO THE PAVEMENT LANES. THE DOWEL BAR ASSEMBLIES SHALL BE APPROVED BY THE RESIDENT ENGINEER PRIOR TO INSTALLATION. ALTERNATE METHODS OF PLACEMENT OF DOWEL BARS MAY BE PROPOSED BY THE CONTRACTOR TO BE APPROVED BY THE ENGINEER. TRANSVERSE DOWEL BAR IMPLANTING WILL NOT BE ALLOWED.
- ALL TIE BARS AND MESH SHALL BE SECURELY HELD IN PLACE BY SUPPORT PINS OR OTHER APPROVED METHODS TO PREVENT SHIFTING DURING AND AFTER CONCRETE PLACEMENT.

- 6. THE INITIAL SAWCUT SHALL BE MADE TO THE 1/8" WIDTH INDICATED. INITIAL SAWING TO THE DIMENSIONS OF THE SECOND SAWCUT WILL NOT BE ALLOWED.
- COST OF ALL JOINT SAWING, CLEANING AND SEALING SHALL BE CONSIDERED INCIDENTAL TO THE ASSOCIATED PAY ITEM AND NO SEPARATE PAYMENT SHALL BE MADE.
- SHOULD THE POURING OPERATION REQUIRE THE INSERTION OF AN INTERMEDIATE HEADER, A DOWEL BASKET ASSEMBLY OR OTHER APPROVED METHOD OF DOWEL BAR PLACEMENT SHALL BE
- EPOXY-COATED DOWEL BASKET ASSEMBLIES MEETING IDOT APPROVAL MAY BE PROPOSED BY THE CONTRACTOR TO BE APPROVED BY THE RESIDENT ENGINEER. DOWELS IN THE APPROVED BASKET ASSEMBLIES SHALL CONFORM TO TABLE 1.
- 10. CONCRETE / BITUMINOUS INTERFACE SHALL BE SEALED PER DETAIL THIS SHEET.
- 11. CONTRACTOR SHALL CONSTRUCT A 1/4" CHAMFER ON ALL CONCRETE JOINTS AT NO ADDITIONAL
- 12. JOINTS SHALL BE DRY AND CLEAN BEFORE SEALING OPERATIONS BEGIN.

| SURVEY BOOK | | |
|-------------|-------------------------------|------|
| | REVISIONS | 3 |
| NUMBER | BY | DATE |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| 0 | 1 | 2 |
| | BAR IS EQUAL ULL SCALE (3- | |
| | | |

IL. CONTRACT: **DK063**

IL. LETTING ITEM: 01A

IL. PROJECT: DKB-4924 S.B.G. PROJECT: 3-17-SBGP-184

DEKALB TAYLOR MUNICIPAL AIRPOI DEKALB, ILLINOIS EMOVE AND REPLACE A PORTION OF AIRCRAFT PARKING APRON EMOV

2

DETAILS


AVING


HY & NEERS ΣU

| DESIGN BY: | CMT-RFD |
|--------------|-----------|
| DRAWN BY: | CMT-RFD |
| CHECKED BY: | CMT-RFD |
| APPROVED BY: | DJK |
| DATE: | 3/3/2023 |
| JOB No: | 210248-02 |


FINAL

SHEET 11 OF 18 SHEETS





TYPICAL UNDERDRAIN DETAIL PAVEMENT EDGE



BELOW PAVEMENT

UNDERDRAIN CLEAN-OUT DETAIL


SIDE VIEW

NOT TO SCALE

UNDERDRAIN CLEANOUT NOTES

1. CLEANOUTS IN NEW PAVEMENT SHALL BE CAST IN PLACE AT THE TIME

FINISH GRADE (PAVEMENT OR TURF) TEE OR WYE FITTING 6" NON-PERFORATED PVC PIPE AS REQUIRED



- ITEM 610 PCC

UNDERDRAIN
CLEAN-OUT DETAILS
NOT TO SCALE

IL. CONTRACT: **DK063**IL. LETTING ITEM: **01A**IL. PROJECT: **DKB-4924**S.B.G. PROJECT: **3-17-SBGP-184**

SUBVEY BOOK # -

| SURVEY BOO | N# | |
|------------|-----------|------|
| | REVISIONS | |
| NUMBER | BY | DATE |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| 0 | 1 | 2 |
| | | |

THIS BAR IS EQUAL TO 2" AT FULL SCALE (34X22).

AT FULL SCALE (34X22).

DEKALB TAYLOR MUNICIPAL AIRPORT
DEKALB, ILLINOIS
REMOVE AND REPLACE A PORTION OF THE
AIRCRAFT PARKING APRON
DRAINAGE DETAILS


©copyright CMT, Inc.
D, MURPHY & TILLY, INC.
ING ENGINEERS
No. 184–000613


CRAWFORD, MURPHY & CRAWFORD, MURPHY & CONSULTING ENGINEERS License No. 184-00061

DESIGN BY: CMT-RFD
DRAWN BY: CMT-RFD
CHECKED BY: CMT-RFD
APPROVED BY: DJK
DATE: 3/3/2023
JOB No: 210248-02


FINAL

SHEET 14 OF 18 SHEETS







| TOTAL VOLUME AT STATION 420+50.00 | | | |
|-----------------------------------|----------|--|--|
| UNCLASSIFIED EXCAVATION | 54.40 SF | | |
| TOPSOIL FILL | 0.89 SF | | |
| TOPSOIL CUT | 0.05 SF | | |
| | | | |



| TOTAL VOLUME AT STATION 420+00.00 | | | |
|-----------------------------------|----------|--|--|
| UNCLASSIFIED EXCAVATION | 69.23 SF | | |
| TOPSOIL FILL | 0.05 SF | | |
| TOPSOIL CUT | 0.66 SF | | |



| TOTAL VOLUME AT STATION 419+66.76 | |
|-----------------------------------|----------|
| UNCLASSIFIED EXCAVATION | 76.71 SF |
| TOPSOIL FILL | 0.00 SF |
| TOPSOIL CUT | 0.92 SF |
| | |



| TOTAL VOLUME AT STATION 419+51.76 | |
|-----------------------------------|----------|
| UNCLASSIFIED EXCAVATION | 83.28 SF |
| TOPSOIL FILL | 0.00 SF |
| TOPSOIL CUT | 0.24 SF |

LEGEND



NEW 12" AVERAGE PAVEMENT REMOVAL (PCC / BITUMINOUS)

NEW GROUND LINE

EXISTING GROUND LINE

NOTES

TOPSOIL CUT AND FILL IN PROPOSED TURF AREAS ARE NOT INCLUDED IN THE EARTHWORK QUANTITIES AND ARE CONSIDERED INCIDENTAL TO (AR152840) SHOULDER ADJUSTMENT.

IL. CONTRACT: DK063 IL. LETTING ITEM: 01A IL. PROJECT: DKB-4924 S.B.G. PROJECT: 3-17-SBGP-184

SURVEY BOOK # ---

| REVISIONS | | | |
|-----------|----|------|--|
| NUMBER | BY | DATE | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |

THIS BAR IS EQUAL TO 2"

AT FULL SCALE (34X22).

王

DEKALB TAYLOR MUNICIPAL AIRPORT DEKALB, ILLINOIS REMOVE AND REPLACE A PORTION OF TH AIRCRAFT PARKING APRON **CROSS SECTIONS**


PHY & TILLY, INEERS

CMT 1


DESIGN BY: CMT-RFD DRAWN BY: CMT-RFD CHECKED BY: CMT-RFD APPROVED BY DJK DATE: 3/3/2023 JOB No: 210248-02

FINAL


SHEET 16 OF 18 SHEETS



| TOTAL VOLUME AT STATION 422+00.00 | | |
|-----------------------------------|----------|--|
| UNCLASSIFIED EXCAVATION | 46.82 SF | |
| TOPSOIL FILL | 0.88 SF | |
| TOPSOIL CUT | 0.02 SF | |



| TOTAL VOLUME AT STATION 421+50.00 | | |
|-----------------------------------|----------|--|
| UNCLASSIFIED EXCAVATION | 44.16 SF | |
| TOPSOIL FILL | 5.12 SF | |
| TOPSOIL CUT | 0.00 SF | |



| TOTAL VOLUME AT STATION 421+00.00 | |
|-----------------------------------|----------|
| UNCLASSIFIED EXCAVATION | 47.18 SF |
| TOPSOIL FILL | 3.17 SF |
| TOPSOIL CUT | 0.00 SF |

LEGEND



NEW PAVEMENT STRUCTURE

NEW 12" AVERAGE PAVEMENT REMOVAL (PCC / BITUMINOUS)

NEW GROUND LINE

— EXISTING GROUND LINE

TOPSOIL CUT AND FILL IN PROPOSED TURF AREAS ARE NOT INCLUDED IN THE EARTHWORK QUANTITIES AND ARE CONSIDERED INCIDENTAL TO (AR152840) SHOULDER ADJUSTMENT.

IL. CONTRACT: **DK063** IL. LETTING ITEM: **01A** IL. PROJECT: DKB-4924

S.B.G. PROJECT: 3-17-SBGP-184

| SURVEY BOOK # | | | | | |
|---------------|----|------|--|--|--|
| REVISIONS | | | | | |
| NUMBER | BY | DATE | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |

THIS BAR IS EQUAL TO 2" AT FULL SCALE (34X22).

DEKALB TAYLOR MUNICIPAL AIRPORT DEKALB, ILLINOIS REMOVE AND REPLACE A PORTION OF TH AIRCRAFT PARKING APRON **CROSS SECTIONS**

뿓

PHY & TILLY, INEERS

CMT

DESIGN BY: CMT-RFD DRAWN BY: CMT-RFD CHECKED BY: CMT-RFD APPROVED BY: 3/3/2023 210248-02 JOB No:

FINAL

SHEET 17 OF 18 SHEETS

909 908


907

906

905

904 903

902



1\$0 150 140 130 120 110 100 90 80 70 60 50 40 30 20 10 **0** 10 20 30 40 50 60 70 80 90 100 1\$\dagger{0}\$

422 46

909

908

907

906

905

904

903 902

TOTAL VOLUME AT STATION 422+46.76 UNCLASSIFIED EXCAVATION 36.41 SF TOPSOIL FILL TOPSOIL CUT 0.57 SF

TOTAL VOLUME AT STATION 422+36.76

32.61 SF

0.33 SF

0.00 SF

UNCLASSIFIED EXCAVATION

TOPSOIL FILL

TOPSOIL CUT




— — EXISTING GROUND LINE

TOPSOIL CUT AND FILL IN PROPOSED TURF AREAS ARE NOT INCLUDED IN THE EARTHWORK QUANTITIES AND ARE CONSIDERED INCIDENTAL TO (AR152840) SHOULDER ADJUSTMENT.

LEGEND





NEERS

FINAL SHEET 18 OF 18 SHEETS

210248-02

JOB No:

SURVEY BOOK # ---REVISIONS

IL. CONTRACT: **DK063** IL. LETTING ITEM: 01A IL. PROJECT: DKB-4924 S.B.G. PROJECT: 3-17-SBGP-184

NUMBER BY DATE

THIS BAR IS EQUAL TO 2" AT FULL SCALE (34X22).

뿓

DEKALB TAYLOR MUNICIPAL AIRPORT DEKALB, ILLINOIS REMOVE AND REPLACE A PORTION OF TH AIRCRAFT PARKING APRON

CROSS SECTIONS