
07A IDOT LETTING APRIL 28, 2023


DUPAGE AIRPORT AUTHORITY WEST CHICAGO, ILLINOIS CONSTRUCTION PLANS FOR DUPAGE AIRPORT

CONSTRUCT NEW AUTOMOBILE PARKING LOT

ILLINOIS PROJECT: DPA-4980

ISSUED FOR BID MARCH 3, 2023





PROJECT

LOCATION MAP

SITE PLAN

INDEX TO SHEETS

- COVER SHEET 1
- SUMMARY OF QUANTITIES 2.
- SITE PLAN AND PROJECT CONTROL PLAN З.
- SEQUENCE OF CONSTRUCTION 4.
- SEQUENCE OF CONSTRUCTION GENERAL NOTES AND DETAILS 5.
- EXISTING CONDITIONS PLAN 6.
- DEMOLITION PLAN 7
- **GEOMETRY PLAN 1** 8.
- **GEOMETRY PLAN 2** 9.
- 10. GEOMETRY PLAN 3
- 11. GEOMETRY PLAN 4
- 12. TYPICAL SECTIONS
- 13. GRADING PLAN 1
- 14. GRADING PLAN 2
- 15. GRADING PLAN 3
- 16. UTILITY PLAN
- 17. STORM SEWER PROFILES
- 18. STORM AND LIGHTING SCHEDULE
- 19. WATERMAIN PLAN AND PROFILE
- 20. BORING LOGS
- 21. CIVIL DETAILS 1
- 22. CIVIL DETAILS 2
- 23. CIVIL DETAILS 3
- 24. CIVIL DETAILS 4
- 25. STORM WATER POLLUTION PREVENTION PLAN 26. STORM WATER POLLUTION PREVENTION PLAN NOTES AND DETAILS
- 27. MARKING, SIGNING AND RESTORATION PLAN

DUPAGE AIRPORT TOWNSHIP: 40 NORTH WAYNE TOWNSHIP RANGE: 9 EAST (SECTIONS: 31) DUPAGE COUNTY J.U.L.I.E Know what's **below.** Call before you dig. JOINT UTILITY LOCATING INFORMATION FOR EXCAVATORS www.illinois1call.com THE LOCATION. SIZE AND TYPE OF MATERIAL OF EXISTING UNDERGROUND UTLITIES INDICATED ON THE PLANS IS NOT REPRESENTED AS BEING ACCURATE, SUFFICIENT OR COMPLETE IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO DETERMINE ACTUAL LOCATIONS OF ALL SUCH FACILITIES, INCLUDING SERVICE CONNECTIONS TO UNDERGROUND UTILITIES, PRIOR TO CONSTRUCTION, THE CONTRACTOR SHALL NOTIFY UTILITY COMPANIES OF HIS OPERATIONAL PLANS, OBTAIN FROM RESPECTIVE UTILITY COMPANIES DETAILED INFORMATION AND ASSISTANCE BELATIVE TO THE LOCATION OF THEIR FACILITIES AND THE WORKING SCHEDULE OF THE COMPANIES FOR REMOVAL OR ADJUSTMENT WHERE REQUIRED IN THE EVENT AN UNEXPECTED UTILITY INTERFERENCE IS ENCOUNTERED DURING CONSTRUCTION, THE CONTRACTOR SHALL IMMEDIATELY NOTIFY THE UTILITY COMPANY OF JURISDICTION AND THE ONE-CALL NOTICE SYSTEM. THE ENGINEER SHALL ALSO BE IMMEDIATELY NOTIFIED. ANY SUCH UTILITY OR SERVICES SHALL BE RESTORED TO SERVICE AT ONCE AND PAID FOR BY THE CONTRACTOR AT NO

ADDITIONAL COST TO THE CONTRACT CALL J.U.L.I.E. FOR UTILITY INFORMATION AT 811.

DU091 TOTAL SHEETS = 27

CONSULTING ENGINEERS License No. 184-000613	LLT, INO.
SUBMITTED BY	DANIEL L. PAPE
DATE	
DUPAGE AIRPORT AUTHORITY	
DuPage Airport	
2700 INTERNATIONAL DRIVE SUITE 200 WEST CHICAGO, IL. 60185	ulu Da
APPROVED BY	MARK DOLES
DATE03/09/2	/ EXECUTIVE DIRECTOR 023

NCMT

21002032-00

CATIEL L. OT

ITEM	DESCRIPTION	UNIT	ESTIMATED QUANTITY	RECORD QUANTIT
BASE BID	·			
AR106905	REMOVE LIGHT POLE AND FIXTURE	EACH	3	
AR150510	ENGINEER'S FIELD OFFICE	L SUM	1	
AR150520	MOBILIZATION	L SUM	1	
AR152410	UNCLASSIFIED EXCAVATION	CU YD	2,755	
AR152540	SOIL STABILIZATION FABRIC	SQ YD	2,430	
AR156510	SILT FENCE	FOOT	410	
AR156520	INLET PROTECTION	EACH	7	
AR208515	POROUS GRANULAR EMBANKMENT	CU YD	540	
AR208608	8" AGGREGATE BASE COURSE	SQ YD	2,426	
AR401610	BITUMINOUS SURFACE COURSE	TON	270	
AR401900	REMOVE BITUMINOUS PAVEMENT	SQ YD	18	
AR403610	BITUMINOUS BASE COURSE	TON	540	
AR602510	BITUMINOUS PRIME COAT	GALLON	1,150	
AR603510	BITUMINOUS TACK COAT	GALLON	690	
AR701512	12" RCP, CLASS IV	FOOT	100	
AR751411	INLET - TYPE A	EACH	2	
AR751943	ADJUST MANHOLE	EACH	4	
AR751983	RECONSTRUCT MANHOLE	EACH	1	
AR754410	COMB CONCRETE CURB AND GUTTER	FOOT	660	
AR760000	WATER MAIN CONNECTIONS	EACH	2	
AR760312	12" WATER MAIN	FOOT	330	
AR760800	FIRE HYDRANT	EACH	2	
AR760900	REMOVE WATER MAIN	FOOT	320	
AR760905	REMOVE FIRE HYDRANT	EACH	2	
AR760947	ADJUST WATER VALVE	EACH	1	
AR770945	ADJUST SANITARY MANHOLE	EACH	2	
AR800152	EXPLORATORY TRENCH	FOOT	80	
AR800153	POTHOLING EXISTING UTILITIES	CAL DAY	4	
AR800171	PAINT PAVEMENT MARKING - LETTERS & SY	SQ FT	91	
AR800172	PAINT PAVEMENT MARKING - LINE 4"	FOOT	1,480	
AR800185	CONCRETE PARKING BLOCK	EACH	3	
AR901510	SEEDING	ACRE	1	
AR908510	MULCHING	ACRE	1	
AR910201	SIGN PANEL	SQ FT	24.5	
AR910246	SIGN SUPPORT	FOOT	63.5	


ITEM		DESCRIPTION	UNIT	ESTIMATED QUANTITY	RECORD QUANTITY
ADDITIVE ALTE	RN/	ATE NO. 1 - PARKING LOT LIGHTING			
AS106960		RELOCATE LIGHT POLE	EACH	3	
AS110610		ELECTRICAL HANDHOLE	EACH	1	
AS800031		NEW DOUBLE MAST ARM - 4 FOOT	EACH	3	
AS800108		2-1/C #8 XLP-USE WITH 1-1/C #8 GND IN 1-1/4" UD	FOOT	432	
AS910120		ROADWAY LIGHT FIXTURE	EACH	6	

ITEM	DESCRIPTION	UNIT	ESTIMATED QUANTITY	RECORD QUANTITY
ADDITIVE ALTER	RNATE NO. 2 - EAST AUTOMOBILE PARKING LOT	·		
AT152410	UNCLASSIFIED EXCAVATION	CU YD	1,591	
AT152540	SOIL STABILIZATION FABRIC	SQ YD	1,160	
AT156520	INLET PROTECTION	EACH	1	
AT208515	POROUS GRANULAR EMBANKMENT	CU YD	270	
AT208606	6" AGGREGATE BASE COURSE	SQ YD	46	
AT208608	8" AGGREGATE BASE COURSE	SQ YD	1,156	
AT401610	BITUMINOUS SURFACE COURSE	TON	120	
AT403610	BITUMINOUS BASE COURSE	TON	240	
AT501506	6" PCC PAVEMENT	SQ YD	46	
AT602510	BITUMINOUS PRIME COAT	GALLON	504	
AT603510	BITUMINOUS TACK COAT	GALLON	152	
AT620510	PAVEMENT MARKING	SQ FT	200	
AT701515	15" RCP, CLASS IV	FOOT	118	
AT751540	MANHOLE 4'	EACH	1	
AT751940	ADJUST INLET	EACH	1	
AT751927	REPLACE FRAME AND GRATE	EACH	1	
AT754410	COMB CONCRETE CURB AND GUTTER	FOOT	572	
AT800060	DUMPSTER ENCLOSURE	L SUM	1	
AT901510	SEEDING	ACRE	0.50	
AT908510	MULCHING	ACRE	0.50	
AT910230	HANDICAP SIGN	EACH	2	
AT910243	SIGN SUPPORT	EACH	1	
AT910420	BOLLARD	EACH	5	


dpa - tbcInt_SOUTH AUTO.dwg

DATE: Friday, March 10, 2023 5.37:12 PM FILE: K:\DupageAp21002032-00_SouthAutoParkingLot\Dra

IL. CONTRA	G ITEM	: 07A		
SURVEY BOO	K #			
	REVIS	SIONS	;	
NUMBER	В	Y	DATE	Ξ
0	1		2	
	BAR IS ULL SC			
DUPAGE AIRPORT WEST CHICAGO, ILLINOIS	CONSTRUCT NEW AUTOMOBILE PARKING LOT		SUMMARY OF QUANTITIES	
	CONSULTING ENGINEERS License No. 184-000613		DUPAGE AIRPORT	AUTHORITY
DESIGN BY:			JJM	
DRAWN BY:	<i>.</i>			
CHECKED BY			DKP DLP	
DATE:		03/0	3/2023	
JOB No:		21002	2032-00	
011557	FIN			
SHEET	2 0	F 27	SHE	=15



TE: Friday, March 10, 2023 5:37:22 PM



SURVEY BOOK # REY NUMBER	EM: 07A JPA-4980 VISIONS BY DATE 1 2
	I IS EQUAL TO 2" SCALE (34X22).
DUPAGE AIRPORT WEST CHICAGO, ILLINOIS CONSTRUCT NEW AUTOMOBILE PARKING LOT	SEQUENCE OF CONSTRUCTION
© CENT Inc. CENTREPAT CENTREPAT A TILLY, INC. CENTREPAT A TILLY, INC. LICENES ENGINEERS	DUPAGE AIRPORT AUTHORITY
DESIGN BY: DRAWN BY:	JJM
CHECKED BY:	DKP
APPROVED BY: DATE:	DLP 03/03/2023
JOB No:	21002032-00
F	FINAL

GENERAL NOTES


- THE SUGGESTED SEQUENCE OF CONSTRUCTION SHOWN IS INTENDED TO ALLOW FOR THE ORDERLY CONSTRUCTION OF THE PROPOSED IMPROVEMENTS WHILE MAINTAINING VEHICLE ACCESS AT ALL TIMES. THE PHASING SHOWN IS A SUGGESTED SEQUENCE OF CONSTRUCTION ONLY. THIS SEQUENCE MAY BE MODIFIED HOWEVER, ALTERNATE STAGING PLANS MUST MAINTAIN AIRPORT OPERATIONS TO THE SATISFACTION OF THE AIRPORT EXECUTIVE DIRECTOR AND RESIDENT ENGINEER.
- 2. ALL OPERATIONS SHALL BE IN CONFORMANCE WITH AC 150/5370 (LATEST EDITION) "OPERATIONAL SAFETY ON AIRPORTS DURING CONSTRUCTION"
- 3. CONTRACTOR'S EQUIPMENT SHALL BE STORED IN THE EQUIPMENT AND MATERIAL STORAGE/STAGING AREA WHEN CONSTRUCTION IS NOT IN PROGRESS. NO EXCEPTIONS FOR SLOW MOVING EQUIPMENT SHALL BE ALLOWED
- 4 THE AIBPORT EXECUTIVE DIRECTOR SHALL HAVE FINAL SAY IN THE APPROVAL OF THE CONSTRUCTION OPERATING PHASING AND SEQUENCE AS IT RELATES TO PEDESTRIAN AND VEHICULAR SAFETY
- 5. ALL EXISTING PAVEMENTS, DRIVES OR ANY OTHER AREAS USED AS A HAUL ROAD OR STORAGE AREA BY THE CONTRACTOR SHALL BE RESTORED IN KIND TO THEIR PRE-CONSTRUCTION CONDITION OR TO THE SATISFACTION OF THE RESIDENT ENGINEER AND AIRPORT MANAGER. THE COST OF MAINTAINING, REPAIRING OR CONSTRUCTING THESE PAVEMENTS AND AREAS SHALL BE INCIDENTAL TO THE CONTRACT, EXISTING AREAS OUTSIDE THE PROJECT LIMITS WHICH ARE DISTURBED BY THE CONTRACTOR'S OPERATIONS SHALL BE RESTORED BY HIM AT HIS EXPENSE TO THE SATISFACTION OF THE RESIDENT ENGINEER AND THE AIRPORT EXECUTIVE DIRECTOR.
- 6. THE CONTRACTOR SHALL KEEP ALL TRUCKS, EQUIPMENT AND MATERIALS OFF OF THE TENANT PARKING LOTS AND DRIVEWAYS OUTSIDE OF THE PROJECT LIMITS EXCEPT AS SHOWN OR WITH THE PRIOR PERMISSION OF THE ENGINEER AND AIRPORT.
- 7. WORK PERFORMED BY THE CONTRACTOR OUTSIDE OF DAYLIGHT HOURS SHALL BE DONE UNDER SUFFICIENT ARTIFICIAL LIGHTING TO ALLOW FOR PROPER CONSTRUCTION METHODS AND INSPECTIONS. LIGHT SHALL CONSIST OF MOVABLE POLE MOUNTED FLOODLIGHTS AND/OR SPOTLIGHTS OF SUFFICIENT NUMBER TO ILLUMINATE THE WORK AREA. VEHICLE HEADLIGHTS WILL BE ALLOWED ONLY IN ADDITION TO OTHER LIGHTS MENTIONED ABOVE. LIGHTING SHALL BE AS APPROVED BY THE ENGINEER AND SHALL NOT BE USED IF THEY AFFECT FLIGHT SAFETY. CONTRACTOR'S WORK HOURS SHALL BE IN ACCORDANCE WITH LOCAL ORDINANCES.
- 8. THE CONTRACTOR WILL BE REQUIRED TO HAVE A SWEEPER AVAILABLE FOR USE AT ALL TIMES. MATERIAL TRACKED ON TO THE PAVEMENT SHALL BE CONTINUALLY REMOVED WITH SAID SWEEPER. THIS SWEEPING SHALL NOT BE PAID FOR SEPARATELY BUT SHALL BE CONSIDERED INCIDENTAL TO THE CONTRACT.
- 9. MATERIALS REMOVED FROM THE PROJECT WILL BECOME PROPERTY OF THE CONTRACTOR AND SHALL BE DISPOSED OF OFF AIRPORT PROPERTY, UNLESS NOTED OTHERWISE
- 10. PAYMENT FOR TRAFFIC CONTROL INCLUDING, BUT NOT LIMITED TO BARRICADES, CONSTRUCTION FENCE, SIGNING, ETC. SHALL NOT BE PAID SEPARATELY, BUT SHALL BE CONSIDERED INCIDENTAL TO THE CONTRACT. BARRICADES SHALL HAVE FLASHING YELLOW LIGHT(S) AND CONFORM TO IDOT STANDARD 701901-08, TYPE II AND TYPE III. SIGNS SHALL BE CONSIDERED INCIDENTAL TO THE CONTRACT
- 11. THE CONTRACTOR SHALL CONTACT THE AIRPORT EXECUTIVE DIRECTOR THROUGH THE RESIDENT ENGINEER TEN (10) WORKING DAYS IN ADVANCE OF THE START OF CONSTRUCTION SO THAT THE APPROPRIATE NOTAMS MAY BE ISSUED.
- 12. IN THE CASE OF AN EMERGENCY, CONTRACTOR SHALL NOTIFY AIRPORT EXECUTIVE DIRECTOR AND THE RESIDENT ENGINEER IMMEDIATELY.
- 13. DURING ADVERSE WEATHER, THE CONTRACTOR SHALL MAKE PROVISIONS FOR ACCESS TO THE WORK AT NO ADDITIONAL COST TO THE CONTRACT, NO EXTENSION OF CONTRACT TIME WILL BE CONSIDERED FOR DELAYS DUE TO LACK OF ADEQUATE ACCESS TO THE WORK
- 14. DUPAGE AIRPORT WILL BE IN OPERATION DURING THE CONSTRUCTION OF THIS PROJECT. COORDINATION OF WORK WITH THE AIRPORT IS MANDATORY SO AS TO MINIMIZE IMPACTS ON AIRPORT OPERATIONS.
- 15. APPROXIMATE LOCATION OF HAUL ROUTES ON THE AIRPORT SITE ARE SHOWN ON THE GENERAL PROJECT LAYOUT AND THE PHASING PLANS. IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO COORDINATE OFF-SITE HAUL ROUTES (STATE HIGHWAYS, COUNTY ROADS OR CITY STREETS) WITH THE APROPRIATE OWNER WHO HAS JURISDICTION OVER THE AFFECTED ROUTE. ON-SITE ROADS USED AS HAUL ROUTES SHALL BE MAINTAINED BY THE CONTRACTOR AND SHALL BE RESTORED AT THE CONTRACTOR'S EXPENSE TO THEIR ORIGINAL CONDITION UPON COMPLETION OF BEING USED AS A HAUL ROUTE. THE BEFORE AND AFTER CONDITION OF ON-SITE HAUL ROUTES SHALL BE JOINTLY INSPECTED AND DETERMINED BY THE CONTRACTOR AND THE ENGINEER. FENCING, DRAINAGE, GRADING AND OTHER MISCELLANEOUS CONSTRUCTION REQUIRED TO CONSTRUCT TEMPORARY HAUL ROUTES OR ACCESS POINTS ON THE AIRPORT WILL BE THE CONTRACTOR'S TOTAL RESPONSIBILITY AND SHALL BE APPROVED BY THE ENGINEER PRIOR TO THE WORK. ALL ON-SITE ACCESS ROADS TO AIRPORT FACILITIES SHALL REMAIN OPEN AND MAINTAINED AT ALL TIMES
- 16. MOBILIZATION/EQUIPMENT STORAGE AREA WILL BE MADE AVAILABLE FOR CONTRACTOR'S MOBILIZATION AND STORAGE AS SHOWN ON THE PLANS. THIS AREA SHALL BE RESTORED TO THE ORIGINAL CONDITION UPON COMPLETION OF THE PROJECT AT THE CONTRACTOR'S EXPENSE.
- 17. LOCATION OF KNOWN EXISTING AIRPORT UNDERGROUND CABLES ARE SHOWN ON THE PLANS AND MUST BE VERIFIED BY THE CONTRACTOR. REPAIR OF DAMAGED CABLE MUST BE STARTED IMMEDIATELY AND CONTINUED UNTIL COMPLETED. ALL SUCH REPAIRS SHALL BE IN ACCORDANCE WITH THE SPECIFICATIONS, OR AS DIRECTED BY THE OWNER OF THE CABLE OR FACILITY, AND SHALL BE AT THE CONTRACTOR'S EXPENSE. IF FAA CABLES ARE DAMAGED, REPAIRS SHALL BE DONE FROM PREVIOUS EXISTING TERMINATION POINT TO PREVIOUS EXISTING TERMINATION POINT IN ACCORDANCE WITH FAA REQUIREMENTS AND IN THE PRESENCE OF A FAA REPRESENTATIVE. THE OWNER MAY ELECT TO HAVE THE REPAIR PERFORMED BY OTHERS IN WHICH CASE THE CONTRACTOR SHALL BE RESPONSIBLE FOR PAYING THE INCURRED COSTS OF REPAIRS
- 18. COORDINATION MEETINGS THE CONTRACTOR SHALL CONDUCT WEEKLY COORDINATION MEETINGS TO DISCUSS WORK AREAS AND SCHEDULING, ETC. WITH THE ENGINEER, AIRPORT OPERATIONS, FAA, AND OTHER APPROPRIATE OFFICIALS. MINUTES FROM THE WEEKLY MEETINGS SHALL BE PREPARED BY THE CONTRACTOR, FURNISHED TO ALL ATTENDEES PRIOR TO THE SUBSEQUENT MEETING, AND KEPT ON FILE AT THE FIELD OFFICE. THE COORDINATION MEETING COSTS SHALL BE CONSIDERED INCIDENTAL TO THE PROJECT

- 19. THE CONTRACTOR SHALL PROVIDE THE PHONE NUMBERS OF THREE PERSONNEL, INCLUDING THE PROJECT SUPERINTENDENT, WHO MAY BE CONTACTED IN AN EMERGENCY. PERSONNEL SHALL BE ON CALL 24 HOURS PER DAY FOR MAINTAINING AIRPORT HAZARD LIGHTING AND BARRICADES.
- 20. ALL EXISTING TAXIWAY AND RUNWAY AIRFIELD LIGHTING CIRCUITS, FAA CABLES AND OTHER ELECTRICAL CABLES SHALL REMAIN IN SERVICE AT ALL TIMES. ALL EXISTING LIGHTING AND VAULT EQUIPMENT SHALL REMAIN IN SERVICE UNTIL PROPOSED IMPROVEMENTS ARE INSTALLED AND OPERATIONAL, UNLESS OTHERWISE APPROVED BY THE ENGINEER. ANY CABLES DAMAGED BY THE CONTRACTOR SHALL BE IMMEDIATELY REPAIRED AT HIS EXPENSE. ANY NECESSARY TEMPORARY JUMPER CABLES SHALL BE CONSIDERED INCIDENTAL TO THE CONTRACT.
- 21. COORDINATION BY THE CONTRACTOR WITH THE EXISTING UTILITIES SHALL BE COMPLETED BEFORE CONSTRUCTION IS STARTED. CONTRACTOR IS REFERRED TO SECTION 50-17 OF THE SPECIAL PROVISIONS FOR SPECIFIC REQUIREMENTS. THE LOCATION OF UNDERGROUND UTILITIES AS INDICATED ON THE PLANS HAS BEEN OBTAINED FROM EXISTING RECORDS. NEITHER THE OWNER OR THE DESIGN ENGINEER ASSUME ANY RESPONSIBILITY WHATSOEVER IN RESPECT TO THE ACCURACY, COMPLETENESS OR SUFFICIENCY OF THE INFORMATION. THERE IS NO GUARANTEE, EITHER EXPRESSED OR IMPLIED THAT THE LOCATIONS, SIZE AND TYPE MATERIAL OF EXISTING UNDERGROUND UTILITIES AS INDICATED ARE REPRESENTATIVE OF THOSE TO BE ENCOUNTERED DURING CONSTRUCTION. IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO DETERMINE THE ACTUAL LOCATION OF ALL SUCH FACILITIES, INCLUDING SERVICE CONNECTIONS TO UNDERGROUND UTILITIES, PRIOR TO CONSTRUCTION, THE CONTRACTOR SHALL NOTIFY THE UTILITY COMPANY OF HIS OPERATIONAL PLANS. THE CONTRACTOR SHALL MAKE ARRANGEMENTS FOR DETAILED INFORMATION AND ASSISTANCE IN LOCATING UTILITIES. IN THE EVENT AN UNEXPECTED UTILITY INTERFERENCE IS ENCOUNTERED DURING CONSTRUCTION, THE CONTRACTOR SHALL IMMEDIATELY NOTIFY THE UTILITY COMPANY, THE RESIDENT ENGINEER AND THE AIRPORT MANAGER. ANY SUCH MAINS AND/OR SERVICES DISTURBED BY THE CONTRACTOR'S OPERATIONS SHALL BE RESTORED IMMEDIATELY AT HIS EXPENSE TO THE SATISFACTION OF THE RESIDENT ENGINEER AND AIRPORT EXECUTIVE DIRECTOR
- 22. CONTRACTOR WILL BE REQUIRED TO PUT AIRPORT FLAGS OR A WORKING BEACON LIGHT ON ALL EQUIPMENT AT ALL TIMES DURING CONSTRUCTION. SEE FLAG DETAIL
- 23. PREPARE A SAFETY PLAN COMPLIANCE DOCUMENT. THE SAFETY PLAN COMPLIANCE DOCUMENT (SPCD) DETAILS HOW THE CONTRACTOR WILL COMPLY WITH THE CSPP. ALSO, IT WILL NOT BE POSSIBLE TO DETERMINE ALL SAFETY PLAN DETAILS (FOR EXAMPLE SPECIFIC HAZARD FOULPMENT AND LIGHTING. CONTRACTOR'S POINTS OF CONTACT, CONSTRUCTION EQUIPMENT HEIGHTS) DURING THE DEVELOPMENT OF THE CSPP. THE SUCCESSFUL CONTRACTOR MUST DEFINE SUCH DETAILS BY PREPARING AND SPCD THAT THE AIRPORT OPERATOR REVIEWS FOR APPROVAL PRIOR TO ISSUANCE OF A NOTICE-TO-PROCEED. THE SPCD IS A SUBSET OF THE CSPP, SIMILAR TO HOW A SHOP DRAWING REVIEW IS A SUBSET TO THE TECHNICAL SPECIFICATIONS.


-	


ADJACENT CONSTRUCTION


	CR
IPTION	GROUND ELEVATION
BID	756
ALT 1	755
ALT 2	755
G AREA	754
AREA	754
	IPTION E BID ALT 1 ALT 2 G AREA E AREA




SHEET 5 OF 27 SHEETS









Ϋ́́́ UPDATE I AVOLIT






UPDATE BY: Tony Marin LAYOUT: PROPOSED GEOMETRY PI

E: Friday, March 10, 2023 5:39:03 PM K:DupageApi2102032-00 SouthAutoParkingLot(Draw/Sheets/21002



UPDATE BY: Tony Mar LAYOUT: PROPOSED




UPDATE BY: Tony Marin LAYOUT: TYPICAL SECTION

E: Friday, March 10, 2023 5:39:29 PM


DAT


IL. CONTRACT: I IL. LETTING ITEM IL. PROJECT: DP/		
SURVEY BOOK #		
REVIS		
NUMBER B	Y DATE	_
		_
0 1	2	
THIS BAR IS AT FULL SC	EQUAL TO 2" ALE (34X22).	
DUPAGE AIRPORT WEST CHICAGO, ILLINOIS CONSTRUCT NEW AUTOMOBILE PARKING LOT	TYPICAL SECTIONS	
Converting Construction CrawFord, Murphy & TILLY, INC. Consulting EngineErs License No. 184-000613	DUPAGE AIRPORT AUTHORITY	
DESIGN BY: DRAWN BY:	JJM	
CHECKED BY:	JMM DKP	-
APPROVED BY:	DLP	
DATE: JOB No:	03/03/2023 21002032-00	
JUB NO:		
SHEET 12 O	F 27 SHEETS	




EARTHWORK						
	CUT (CYD)	FILL (CYD)	TOTAL (CYD)			
BASE BID	2,833	78	2,755 CUT			
WITH ADD ALT 2	4,419	78	4,346 CUT			

Ϋ́, Β̈́, UPDATE






BY: 1 PRC



Ϋ́ UPDATE






DRAINAGE NOTES

- 2.
- STRUCTURES.
- 4. UTILITY CROSSINGS.
- 6.
- 7. INSTALLED
- 8.
- 9.

- ALLOWED FOR THIS WORK.
- CONTRACTOR
- A RESULT OF THE WORK.



					STRUCTURE SCHE	DULE				
STRUCTURE	STATION	OFFSET	NORTHING	EASTING	RIM ELEVATION	INVERT ELEVATION	TYPE	SIZE	FRAME AND GRATE LID BASE BID	FRAME AND GRATE LID ADD ALT 2
ADJUST EX SAN MH 1	10+44.10	7.122	1907397.2650	1004333.7970	751.03	INV (N) = 739.37 INV (E) = 739.38	EXISTING	EXISTING	EXISTING	EXISTING
ADJUST EX SAN MH 2	13+10.92	8.213	1907396.1740	1004600.6170	753.73	INV (E) = 740.49 INV (W) = 740.47	EXISTING	EXISTING	EXISTING	EXISTING
CB #005 (BY OTHERS)	11+00	1.000	1907403.3373	1004389.6985	0.00	INV (E) = 744.18 INV (N) = 744.18	EXISTING	EXISTING	TYPE 23 FRAME OPEN LID	TYPE 23 FRAME OPEN LID
CB #006 (BY OTHERS)	12+00	1.000	1907403.3307	1004489.9414	753.50	INV (E) = 746.34 INV (W) = 743.66 INV (S) = 742.64	EXISTING	EXISTING	TYPE 1 FRAME OPEN LID	TYPE 1 FRAME OPEN LID
CB #007 (BY OTHERS)	13+10.58	1.000	1907403.3434	1004600.2793	753.50	INV (E) = 746.89 INV (W) = 746.89	EXISTING	EXISTING	TYPE 1 FRAME OPEN LID	TYPE 1 FRAME OPEN LID
CB #008 (BY OTHERS)	14+17.90	1.000	1907403.3432	1004707.5949	753.92	INV (E) = 748.47 INV (W) = 747.43 INV (N) = 747.43	EXISTING	EXISTING	TYPE 23 FRAME OPEN LID	TYPE 1 FRAME OPEN LID
CB #012	15+73.60	-9.000	1907507.5661	1004763.7847	753.70	INV (SW) = 749.17	А	4	N/A	TYPE 1 FRAME OPEN LID
CB #013	11+42.35	38.152	1907366.2352	1004432.0482	754.42	INV (E) = 750.42	А	2	TYPE 8 GRATE	TYPE 8 GRATE
CB #014	12+42.53	18.152	1907366.2352	1004532.2330	754.20	INV (W) = 750.17	А	2	TYPE 8 GRATE	TYPE 8 GRATE
EXISTING SAN MH #3	12+42.53	18.152	1907492.6344	1004332.7119	752.96	INV (SE) = 748.67 INV (S) = 738.95 INV (N) = 738.95	EXISTING	EXISTING	EXISTING	EXISTING
MH #001 (BY OTHERS)	10+85.35	-173.382	1907577.7687	1004375.0446	754.54	INV (N) = 749.44 INV S = 749.44 INV (E) = 749.82	EXISTING	EXISTING	EXISTING	EXISTING
MH #002 (BY OTHERS)	10+85.35	-125.359	1907529.7463	1004375.0446	754.52	INV (N) = 749.20 INV (S) = 746.52 INV (E) = 749.82	EXISTING	EXISTING	EXISTING	EXISTING
MH #003 (BY OTHERS)	10+85.35	-92.977	1907497.3644	1004375.0446	754.58	INV (N) = 746.36 INV (S) 746.36 INV (E) = 749.89 INV (SW) = 749.89	EXISTING	EXISTING	EXISTING	EXISTING
MH #004 (BY OTHERS)	10+85.35	-36.000	1907440.3885	1004375.0446	754.13	INV (N) = 746.07 INV (E) = 748.92 INV (S) = 744.37	EXISTING	EXISTING	EXISTING	EXISTING
MH #009 (BY OTHERS)	16+43.81	-50.616	1907577.7687	1004722.1685	754.31	INV (N) = 749.42 INV (S) = 749.42 INV (W) 749.63	EXISTING	EXISTING	EXISTING	EXISTING
MH #010 (BY OTHERS)	15+95.78	-50.614	1907529.7490	1004722.1717	754.30	INV (N) = 749.18 INV (S) = 749.18 INV (W) = 749.62	EXISTING	EXISTING	EXISTING	EXISTING
MH #011 (BY OTHERS)	15+47.89	-50.611	1907481.8491	1004722.1721	754.29	INV (N) = 748.94 INV (S) = 747.83 INV (W) = 749.60	EXISTING	EXISTING	EXISTING	EXISTING

* *

.

*

- SCHEDULE NOTES:
 NORTHING AND EASTING FOR MANHOLES IS TO CENTER OF STRUCTURE.
 D/S: DOWNSTREAM.
 LENGTH OF PIPE FROM MANHOLE TO MANHOLE IS FROM CENTER OF STRUCTURE.
 RCCP: REINFORCED CONCRETE CIRCULAR PIPE, CLASS IV.
 PVC: POLYVINYL CHLORIDE PIPE, SDR 26.
 MANHOLES SHALL BE IDOT STANDARD 602401-07.
 CONTRACTOR SHALL VERIFY RIM AND INVERT ELEVATIONS ON EXISTING DRAINAGE STRUCTURES THAT ARE TO BE CONNECTED TO, ADJUSTED OR RECONSTRUCTED BEFORE ORDERING MATERIAL (INCIDENTAL TO CONTRACT).
 FRAME AND LIDS SHALL BE IDOT STANDARD 604001-05, 604036-03 AND 604086-05.
 EXISTING STRUCTURES TO BE ADJUSTED OR RECONSTRUCTED SHALL SALVAGE AND REUSE EXISTING FRAMES AND GRATES OR PROVIDE NEW FRAMES AS INDICATED.
- * INSTALLED BY OTHERS. ADJUST AS NECESSARY TO MEET FINAL GRADES

DATE: FILE:


	OTHERS)	16+43.81	-50.616	1907577.76	87 1004722.	1685	754.
MH #010 (BY	OTHERS)	15+95.78	-50.614	1907529.74	90 1004722.	1717	754.3
MH #011 (BY	OTHERS)	15+47.89	-50.611	1907481.84	91 1004722.	1721	754.2
		PIPE SCH	EDULE]	
PIPE NAME	UPSTREAM INLET	DOWNSTREAM INLET	PIPE TYPE	LENGTH	SLOPE		
PIPE NAME PIPE 1			PIPE TYPE 15" RCCP	LENGTH 40	SLOPE 0.48%	*	
	INLET	INLET		-		*	
PIPE 1	INLET MH #004	INLET CB #005	15" RCCP	40	0.48%	*	
PIPE 1 PIPE 2	INLET MH #004 CB #006	INLET CB #005 CB #005	15" RCCP 15" RCCP	40 105	0.48%	*	
PIPE 1 PIPE 2 PIPE 3	INLET MH #004 CB #006 CB #007	INLET CB #005 CB #005 CB #006	15" RCCP 15" RCCP 21" RCCP	40 105 110	0.48% 0.50% 0.50%	*	
PIPE 1 PIPE 2 PIPE 3 PIPE 4	INLET MH #004 CB #006 CB #007 CB #008	INLET CB #005 CB #005 CB #006 CB #007	15" RCCP 15" RCCP 21" RCCP 18" RCCP	40 105 110 107	0.48% 0.50% 0.50% 0.50%	* * *	
PIPE 1 PIPE 2 PIPE 3 PIPE 4 PIPE 5	INLET MH #004 CB #006 CB #007 CB #008 MH #011	INLET CB #005 CB #005 CB #006 CB #007 CB #008	15" RCCP 15" RCCP 21" RCCP 18" RCCP 18" RCCP 12" PVC	40 105 110 107 80	0.48% 0.50% 0.50% 0.50% 0.49%	* * *	
PIPE 1 PIPE 2 PIPE 3 PIPE 4 PIPE 5 PIPE 6	INLET MH #004 CB #006 CB #007 CB #008 MH #011 CB #006	INLET CB #005 CB #005 CB #006 CB #007 CB #008 EX MH	15" RCCP 15" RCCP 21" RCCP 18" RCCP 12" PVC 24" RCCP	40 105 110 107 80 25	0.48% 0.50% 0.50% 0.50% 0.49% 0.56%	* * * *	


NOTE: *BY OTHERS **ADD ALT 2


		LIGHTING SCHEE	OULE (ADD ALT 1)		
STRUCTURE	STATION	OFFSET	NORTHING	EASTING	GROUND ELEVATION
LIGHT POLE #1	11+41.18	36.5	1907371.8029	1004425.9252	754.55
LIGHT POLE #2	12+47.81	36.5	1907371.7984	1004532.5574	754.85
LIGHT POLE #3	13+54.05	36.5	1907371.7921	1004638.7943	754.64

NOTE: CENTER OF POLE 3.3' OFF BACK OF CURB

IL. CONTRACT: DU091 IL. LETTING ITEM: 07A IL. PROJECT: DPA-4980					
		NS DATE			
	∠	STORM AND LIGHTING SCHEDULE			
	CONSULTING ENGINEEHS License No. 184-000613	DUPAGE AIRPORT AUTHORITY			
DESIGN BY:		JJM			
	/ :	DKP			
	BY:	DLP			
DATE:		03/03/2023			
JOB No:		1002032-00			
		- 1			
	IL. LETTINC IL. PROJECT SURVEY BOO NUMBER DIDAGE AIBORT THIS AT F DESIGN BY: CHCKED BY APPROJECTION CHCKED BY APPROJECTION	IL. LETTING ITEM: 0 IL. PROJECT: DPA-45 SURVEY BOOK # REVISIO NUMBER BY I THIS BAR IS EQUAL AT FULL SCALE OUNCLIVE ENCIDENTIAL SCALE I DESIGN BY: DESIGN BY: DESIGN BY: CHECKED BY: APPROVED BY: JOB NO: 2 ZOB NO: 2 Z			







Wang Engineering				в				.OG B-02	atum: NAVD	88	Page	1 af 1	
angeng@wangeng.com 145 N Main Street ombard, IL 60148 elephone: (630) 953-9928	Project	DuP	ag	e Co	unty	Airpo	Jaco ort E	bs Ea uilding and Parking Lot St	evation: 754. orth: 190764 ast: 1004664 lation: NA	3.89 ft			
ax: (630) 953-9938	Location				We	st C	hica	jo, Illinois O	ffset: NA				
SOIL AND ROCK	Depth (ft)	Sample Type	Sample No.	SPT Values (blw/6 in)	Qu (fsf)	Maisture Content (%)	Profile	SOIL AND ROCK	Depth (ft) Sample Type	Sample No. SPT Values (blw/6 in)	हि	Moisture Content (%)	
10-inch thick, dark brown LE 753.8 CLAY with sand (CL)s 	DIL/-	ľ	1	4 7 9	NA	21		1sand and gravel (ML)sg; mois RDR Stiff to very stiff, gray SILTY CLAY with sand (CL-ML)s to SIIty Clayey SAND (SC-SM), little gravel; damp to moist	2-/	11 3 5 7	1.50 P	12	
RDF Dense, gray Sandy SILT wit gravel s(ML)gs; damp	R 2/ -	X	2	8 22 13	NP	10		724.6 Boring terminated at 30.00 ft	30 ⁻	12 5 8 9	2.30 B	10	
748.4 Stiff to very stiff (2.79B), bla brown, and gray LEAN CLA' (CL), trace gravel; damp RDF	ck, - Y -	X	3	5 5 6	1.50 P	25							
Medium dense, brown SILT sand (ML)s, trace gravel; mo 744.1RDI Hard, brown LEAN CLAY (C	oist ₁₀ R 2	X	4	4 5 8	NP	11			35				
trace gravel; damp RDf	R2	X	5	4 7 11	5.90 B	16			-				
738.4	15	X	6	9 9 <u>12</u>	4.84 B	21			40				
Dense, white, well-graded GRAVEL (GW); damp 735.5cobble fragme RDf Dense, grav SILT (ML), trac	22-/-	X	7	10 31 17	NP	4			-				
gravel; damp RDF 734.1 Very stiff, gray LEAN CLAY	₹ 220_/	X	8	8 8 9	NP	16			45_				
732.9 (CL), trace gravel; damp -RDI Medium dense, gray SILT w 73 ^{1,6} sand (ML)s, trace gravel; m -RDI -RDI	ith vist	X	9	4 8 8	3.28 B	16			-				
RDI sand lens; satural Medium dense, gray SILT w GENEI	ted/ - ith 25_/		10	4 6 6	NP	10		WATER	50_				
gin Drilling 10-14-2021				Iling		10-14	-20		¥				
illing Contractor Wang Testin iller RH&JD Logger illing Method 2,25" ID HSA; bo	g Servic E. Y	:es /im		Drill Rij	g 2 ecked	0D50)T [8 C. N	D%] At Completion of Drilling arin Time After Drilling	¥ NA NA	DRY			

wangeng@wange 1145 N Main Stree Lombard, IL 6014 Telephone: (630) Fax: (630) 953-99	et 8 953-9928	Client Project Location	DuPa	je Co	WE unty	l Job Airpo) No. Jaco ort E	: 206-3 obs Buildin	B-03 36-05 g and Parking Lot nois	Datu Eleva North East: Static Offse	tion: 190 1004 2n: N/	752. 7516 397.	79 f 3.28	ft	Page	1 of 1
E DE	L AND ROCK SCRIPTION	80	Sample Type recovery Sample No.	SPT Values (blw/6 in)	Qu (tsf)	Moisture Content (%)	Profile	Elevation (ft)	SOIL AND ROO DESCRIPTION	N		Sample Type	Sample No.	SPT Values (blw/6 in)	Qu (tsf)	Moisture Content (%)
752.0 with sand	wn LEAN CLAY (0 rel; damp	OIL-/	1	8 7 6	> 4.50 P	15				RDR 2-		X	11	10 10 11	3.20 B	11
sand (CL)	RD	th / -	2	2 4 6	6.23 B	22		722.8 BC	ring terminated at 30.	00 ft	30	X	12	8 8 8	2.71 B	11
LEAN CL	AY (CL); damp RDR tter; possible cobi L ₁ (%)=29, P ₁ (%)	bles =17	3	6 6 7	5.25 B	18										
	%Gravel= %Sand= %Silt=5 %Clay=3	7.4	4	6 7 7	3.12 B	19					- 35_					
		-	5	12 13 13	NA	17					-					
		15	6	12 9 8	2.71 B	16					40					
		-	7	6 6 8	1.72 B	17					-					
732.3 Medium d	ense, gray SILT v	20	8	6 6 7	2.13 B	16					45_					
729.8 Stiff to ver	ry stiff, gray SILTY	R'2	× 1	6 7 7	NP	12					-					
CLAY with Silty Claye	n sand (CL-ML)s t ey SAND (SC-SM el; damp to moist	o]		7 8 8	1.50 P	11			WATI		50_		~ 7	_		
Deale Dates						0.44	1.00	14								
	10-14-2021 Wang Tootis		nplete D						While Drilling					RY RY		
	Wang Testir								At Completion of Drilli				U	NT		
	JD Logger								Time After Drilling		IA IA					
Unling Method	2.25" ID HSA; b	oring ba	ickfille	a upo	on co	mple	tion		Depth to Water			kimate	e ba	indary		
									batenan coil funar: the ac	fuel tracel	ion ma	w bo	- or	uni		

	Wang				в	OR		GI	OG	B-05					Page	2 af 2
	Engineering				-				.: 206-3		Datum: N					
	wangeng@wangeng.com I 145 N Main Street	Client									Elevation North: 19					
L	ombard, IL 60148									g and Parking Lot	East: 100 Station: N		97 f	t		
	Telephone: (630) 953-9928 Fax: (630) 953-9938	Location								nois	Offset: N					
F	1		0	Ι.		_		-	1			6		-		
Profile	SOIL AND ROCK	Depth (ft)	Sample Type	Sample No.	SPT Values (biw/6 in)	o (tst)	Maisture Content (%)	Profile	Elevation (ft)	SOIL AND ROC DESCRIPTION		Sample Typ	Sample No.	SPT Values (blw/6 in)	Qu (tsf)	Maisture Content (%)
	%Silt=: %Clay=!	35.7														
Í	Dense, gray SILT with sand (ML)s, trace gravel; moist to															
	-10	55	X	18	10 13 30	NP	12									
	697.6	-														
80	Slow hard drilling from 56.5 58.5 feet	to														
80	possible bo	lder														
100	Boring terminated at 58.50	ft _														
		60														
		-														
		-														
		-														
		-														
		-														
		65														
		-														
		1														
		-														
		-														
		-														
		70														
		-														
		_														
		-														
		-														
		-														
		75														
-	GENE	RAL N	ОТ	FS		<u> </u>		L	L	WATE	R LEVE		ΔΤ	Δ		
в	egin Drilling 10-15-2021				illing		10-15	-202	21	While Drilling	<u><u><u>R</u></u></u>					
D	rilling Contractor Wang Testir	ng Servi	ces	1	Drill Ri	g 2	0D50	DT [8	80%]	At Completion of Drillin						
	riller RH&JD Logger									Time After Drilling	NA					
P	rilling Method 2.25" ID HSA to backfilled upon completion		otary	<i>i</i> .m	ud th	erea	fter;	bori	ng	Depth to Water 3 The stratification lines represent	sent the acor	oximate	e boi	Indary		
	backnieu upon completio	u				******				between soil types: the actu	al transition n	ay be	orad	ual		


Wang Engineering Wangeng@wangeng.com 1145 N Main Street Lombard, IL 60148 Telephone: (630) 953-9628 Fax: (630) 953-9638	Project Du	Pag	je Co	WE	l Job Airpo	No. Jaco	SB-01 86-05 g and Parking Lot nois	ot Station: NA						
		Sample No.	SPT Values (blw/6 in)	Qu (tsf)	Moisture Content (%)	Profile	Elevation (ft)	SOIL AND ROC DESCRIPTION		Sample Type	Sample No.	SPT Values (blw/6 in)	Qu (tsf)	Moisture Content (%)
9-inch thick, black LEA with sand (CL)s; moist 7513	PSOIL-	1	4 5 9 11	4.76 B	21									
1 damp	FILL///	2	10 8 7 7	7.22 B	22									
sand (CL)s; damp Buried TC 7480 Hard, brown LEAN CL4 damp	Y (CL);	3	2 3 8 11	NP	16									
Medium dense, brown s sand (ML)s; damp Hard, brown LEAN CLA		4	8 11 15 13	> 4.50 P	15									
trace gravel; damp F 743.6L _L (%)=26, P	DR 2-3	5	9 10 11 33	5.74 B	17									
%Sa	d=10.4													
	15													
	-													
	20_													
	-													
	25													
GE	NERAL NO	TES	3	-		L		WATE	R LEVE	LC		A		
Begin Drilling 10-14-2021 Drilling Contractor Wang Te Driller RH&JD Log	Comple sting Service: per E. Yir	ste D S N	rilling Drill Ri Ch	g 2 ecked	0D50	OT [8 C. M	0%] Iarin	While Drilling At Completion of Drillin Time After Drilling	⊽ ▼ NA		DF	RY RY		
Drilling Method 2.25" ID HS/	, poring back	ome	u upo	и) CO	mple	uon		Depth to Water	ssent the approval transition m	oximal tay be	le bou gradu	ndary Ial.		


DATE FILE:


Marin UPDATE BY: Tony


Lombard, IL 60148 Telephone: (630) 953 Fax: (630) 953-9938

(ft)











L DE S S S







100 P.S.I. TABLE

THRUST BLOCK DETAIL

NOT TO SCALE







PLAN

N.T.S

	TABLE												
DEN	D	SIZE											
BEN	D	6"	8"	10"	12"	16"	20"	24"	30"	36"			
°+	G	6"	8"	10"	1'-0"	1'-4"	1'-8"	2'-0"	2'-6"	3'-0"			
1/4°	н	1'-2"	1'-4"	1'-6"	1'-8"	2'-0"	2'-4"	2'-8"	3'-2"	3'-10"			
÷	J	7"	7"	8"	8"	9"	10"	1'-0"	1'-1"	1'-2"			
1/2°	G	9"	1'-0"	1'-6"	1'-4"	2'-3'	3'-0"	3'-6"	4'-2"	5'-4"			
	Н	1'-2"	1'-4"	1'-6"	1'-8"	2'-0"	2'-4"	2'-8"	3'-2"	4'-0"			
22	J	8"	9"	10"	11"	1'-2"	1'-4"	1'-6"	1'-9"	2'-0"			
	G	1'-3"	1'-8"	2'-1"	2'-6"	3'-4"	4'-2"	5'-0"	6'-3"	7'-6"			
45°	н	1'-2"	1'-4"	1'-6"	1'-10"	2'-6"	3'-0"	3'-4"	4'-0"	5'-0"			
	J	8"	9"	10"	11"	1'-2"	1'-4"	1'-9"	2'-3"	2'-8"			

NOTES:


1. ALL H & J DIMENSIONS TO BE AS REQ'D. TO REACH UNDISTURBED EARTH BUT NOT LESS THAN LISTED ON THRUST BLOCK TABLE.

2. ALL POURED CONCRETE SHALL BE 3000 P.S.I. @ 28 DAYS.

ALL POURED CONCRETE SHALL BE LAID THE FULL WIDTH OF 3. TRENCH FROM UNDISTURBED WALL TO UNDISTURBED WALL



NOT TO SCALE



PLAN


N.T.S.

FITTING

- 3. ALL STRAPS TO BE 3"W. X 1/2" WROUGHT IRON. APPLY TWO COATS OF APPROVED BITUMINOUS PAINT TO EXPOSED STRAP.
- 4. ALL RODS TO BE WROUGHT IRON AS SHOWN ON TABLE, THREADED ONE END AND BENT THE OTHER. APPLY TWO COATS OF APPROVED BITUMINOUS PAINT TO EXPOSED AREAS.

THRUST BLOCK DETAIL FOR VERTICAL ALIGNMENT CONCAVE DOWNWARD

NOT TO SCALE



PLAN OF TEE

N.T.S.

TABLE

6" 8" 10" 12" 16"

1'-3" 1'-6" 1'-9" 2'-0" 2'-3" 2'-0" 2'-6" 2'-9" 3'-0" 4'-0"

1'-9" 2'-3" 2'-6" 2'-6" 2'-6"

SIZE

3'-6"


NOTES


- ALL BENDS, TEES, PLUGS, FITTINGS OR OTHER SIGNIFICANT CHANGES IN ALIGNMENT SHALL BE BRACED WITH POURED CONCRETE THRUST BLOCKS FITTINGS WITH RETAINING GLANDS WILL NOT BE ALLOWED.
- "C' DIMENSION SHALL BE AS REQUIRED TO REACH UNDISTURBED EARTH BUT NOT LESS THAN VALUE LISTED IN TABLE.
- 3. DIMENSIONS "A" AND "B" ARE BASED ON INTERNAL PIPE PRESSURE OF 100 P.S.I. AND BEARING ON THE UNDISTURBED SOIL OF 1500 P.S.F.
- 4. "B"= HEIGHT OF THRUST BLOCK

20"	24"	30"	36"			
4'-0"	4'-3"	4'-6"	5'-0"			
2'-6"	2'-9"	3'-0"	4'-0"			
5'-0"	5'-9"	5'-9" 6'-6"				
4'-8"	5'-0"	5'-4"	6'-0"			
2'-8"	3'-8"	4'-6"	5'-6"			
7'-6"	8'-6"	8'-6"	10'-0"			
5'-6"	6'-0"	6'-6"	7'-6"			
4'-6"	5'-6"	6'-0"	6'-0"			
8'-0"	9'-6"	11'-0"	11'-6"			

ALL POURED CONCRETE SHALL BE LAID ON UNDISTURBED EARTH AFTER EXCAVATION ACCORDING TO DIMENSIONS INDICATED ON THRUST BLOCK DIMENSION TABLE OR IT SHALL BE LAID THE FULL WIDTH OF TRENCH FROM UNDISTURBED WALL TO UNDISTURBED WALL BUT NOT LESS THAN LISTED ON THRUST BLOCK TABLE.

2. ALL POURED CONCRETE SHALL BE 3000 P.S.I. @ 28 DAYS.





STORM WATER POLLUTION PREVENTION NOTES:

THE FOLLOWING IS THE ESTABLISHED BEST MANAGEMENT PRACTICES TO BE INCORPORATED IN THE PROJECT TO DIRECT THE CONTRACTOR IN THE PLACEMENT OF TEMPORARY EROSION CONTROL SYSTEMS AND TO PROVIDE A STORM WATER POLLUTION PREVENTION PLAN FOR COMPLIANCE WITH NPDES.

THE PURPOSE OF THIS PLAN IS TO MINIMIZE EROSION WITHIN THE CONSTRUCTION SITE AND TO LIMIT SEDIMENTS FROM LEAVING THE SITE BY UTILIZING PROPER TEMPORARY EROSION CONTROL SYSTEMS AND PROVIDING GROUND COVER WITHIN A REASONABLE AMOUNT

CERTAIN FROSION CONTROL FACILITIES SHALL BE INSTALLED BY THE CONTRACTOR AT THE REGINNING OF CONSTRUCTION. OTHER TEMS SHALL BE INSTALLED BY THE CONTRACTOR AS DIRECTED BY THE EXGINEER ON A CASE BY CASE SITUATION DEPENDING ON THE CONTRACTOR'S SEQUENCE OF ACTIVITIES, TIME OF YEAR, AND EXPECTED WEATHER CONDITIONS.

THE CONTRACTOR SHALL INSTALL PERMANENT EROSION CONTROL SYSTEMS AND SEEDING WITHIN A TIMEERAME SPECIFIED HEREIN AND AS DIRECTED BY THE ENGINEET, THEREFORE MINIMIZING THE AMOUNT OF AREA SUSCEPTIBLE TO REOSION AND REDUCING TH AMOUNT OF TEMPORARY SEEDING, WHICH WILL BE THE CONTRACTOR'S COST. THE ENGINEER WILL DETERMINE IF ANY TEMPORARY EROSION CONTROL SYSTEMS SHOWN IN THE PLAN CAN BE DELETED AND IF ANY ADDITIONAL TEMPORARY EROSION CONTROL SYSTEMS. WHICH ARE NOT INCLUDED IN THIS PLAN, SHALL BE ADDED. THE CONTRACTOR SHALL PERFORM ALL WORK AS DIRECTED BY THE ENGINEER AND AS SHOWN ON THE PLANS.

SITE DESCRIPTION

THE FOLLOWING IS A DESCRIPTION OF THE CONSTRUCTION ACTIVITY WHICH IS THE SUBJECT OF THIS PLAN:

THIS PROJECT CONSISTS OF CONSTRUCTING A NEW PARKING LOT AT DUPAGE AIRPORT. THE PROJECT INCLUDES PAVEMENT DEMOLITION, DRAINAGE SYSTEMS INSTALLATION, SITE GRADING, ASPHALT PAVEMENT, CONCRETE CURB AND GUTTER, AND PAVEMENT

THE FOLLOWING IS A DESCRIPTION OF THE INTENDED SEQUENCE OF MAJOR ACTIVITIES:

- 1. INSTALL TEMPORARY EROSION CONTROL MEASURES.
- 2. DRAINAGE SYSTEM AND SITEWORK.
- 3. CONSTRUCT NEW PARKING LOT.
- 4. REMOVAL AND DISPOSAL OF TEMPORARY EROSION CONTROL MEASURES.

AREA OF CONSTRUCTION SITE

THE TOTAL AREA OF THE CONSTRUCTION SITE IS APPROXIMATELY 0.69 ACRES OF WHICH 0.69 ACRES WILL BE DISTURBED BY EXCAVATION, GRADING AND OTHER ACTIVITIES.

DRAINAGE TRIBUTARIES AND SENSITIVE AREAS RECEIVING RUNOFF FROM THIS CONSTRUCTION SITE:

THE CONSTRUCTION SITE DRAINS INTO STORM SEWER SYSTEMS THAT OUTLET INTO KRESS CREEK

SEDIMENTATION AND EROSION CONTROL NOTES

THE RESIDENT ENGINEER WILL PERFORM PERIODIC INSPECTION OF THE SITE TO IDENTIFY POTENTIAL SEDIMENT AND EROSION

ALL SOIL EROSION AND SEDIMENT CONTROL PRACTICES ARE REFERENCED FROM THE ILLINOIS URBAN MANUAL, UNLESS OTHERWISE STATED

THE DRAWINGS, SPECIFICATIONS AND SPECIAL PROVISIONS WILL ENSURE THAT EXISTING VEGETATION IS PRESERVED WHERE ATTAINABLE AND DISTURBED PORTIONS OF THE SITE WILL BE STABILIZED. STABILIZATION PRACTICES INCLUDE SEEDING AND MULCHING AS DIRECTED BY THE ENGINEER. STABILIZATION MEASURES SHALL BE INITIATED WITHIN SEVEN (7) DAYS OF DISTURBANCE

DESCRIPTION OF STABILIZATION PRACTICES DURING CONSTRUCTION:

DURING CONSTRUCTION, AREAS OUTSIDE THE CONSTRUCTION LIMITS AS OUTLINED PREVIOUSLY HEREIN SHALL BE PROTECTED. THE CONTRACTOR SHALL NOT USE THIS AREA FOR STAGING (EXCEPT AS DESCRIBED ON THE PLANS AND DIRECTED BY THE ENGINEER), PARKING OF VEHICLES OR CONSTRUCTION FOUIPMENT, STORAGE OF MATERIALS, OR OTHER CONSTRUCTION **BELATED ACTIVITIES**

- WITHIN THE CONSTRUCTION LIMITS, AREAS WHICH MAY BE SUSCEPTIBLE TO EROSION AS DETERMINED BY THE ENGINEER SHALL REMAIN UNDISTURBED UNTIL FULL SCALE CONSTRUCTION IS UNDERWAY TO PREVENT UNNECESSARY SOIL EROSION.
- 2. EARTH STOCKPILES SHALL BE TEMPORARILY SEEDED, AT THE CONTRACTORS EXPENSE, IF THEY ARE TO REMAIN UNUSED FOR MORE THAN FOURTEEN DAYS
- 3. AS CONSTRUCTION PROCEEDS, THE CONTRACTOR SHALL INSTITUTE THE FOLLOWING AS DIRECTED BY THE ENGINEER
- A. PLACE TEMPORARY EROSION CONTROL FACILITIES AT LOCATIONS SHOWN ON THE PLANS.
- EXCAVATED AREAS AND EMBANKMENT AREAS SHALL BE PERMANENTLY SEEDED IMMEDIATELY AFTER FINAL GRADING. I NOT, THEY SHALL BE TEMPORARILY SEEDED, AT THE CONTRACTOR'S COST, IF NO CONSTRUCTION ACTIVITY IN THE AREA IS PLANNED FOR SEVEN DAYS
- 4 CONSTRUCTION EQUIPMENT SHALL BE STORED AND FUELED ONLY AT DESIGNATED LOCATIONS ALL NECESSARY MEASURES SHALL BE TAKEN TO CONTAIN ANY FUEL OR POLLUTANT IN ACCORDANCE WITH EPA WATER QUALITY REGULATIONS. LEAKING EQUIPMENT OR SUPPLIES SHALL BE IMMEDIATELY REPAIRED OR REMOVED FROM THE SITE.
- 5. SEDIMENT COLLECTED DURING CONSTRUCTION OF THE VARIOUS TEMPORARY EROSION CONTROL SYSTEMS SHALL BE DISPOSED OF OFF SITE ON A REGULAR BASIS AS DIRECTED BY THE ENGINEER. THE COST OF THIS MAINTENANCE SHALL BE INCIDENTAL TO THE COST OF THE PROJECT
- 6. THE TEMPORARY EROSION CONTROL SYSTEMS SHALL BE REMOVED AS DIRECTED BY THE ENGINEER AFTER USE IS NO ONGER NEEDED OR NO LONGER FUNCTIONING. THE COST OF THIS REMOVAL SHALL BE INCIDENTAL TO THE CONT

DESCRIPTION OF STRUCTURAL PRACTICES AFTER FINAL GRADING:

TEMPORARY EROSION CONTROL SYSTEMS SHALL BE LEFT IN PLACE WITH PROPER MAINTENANCE UNTIL PERMANENT EROSION CONTROL IS IN PLACE AND WORKING PROPERLY AND ALL PROPOSED TURF AREAS ARE SEEDED AND ESTABLISHED.

ONCE PERMANENT EROSION CONTROL SYSTEMS AS PROPOSED IN THE PLANS ARE FUNCTIONAL AND ESTABLISHED, TEMPORARY ITEMS SHALL BE REMOVED, CLEANED UP, AND DISTURBED TURF RESEEDED.

MAINTENANCE AFTER CONSTRUCTION

CONSTRUCTION IS COMPLETE AFTER FINAL ACCEPTANCE BY THE ILLINOIS DIVISION OF AERONAUTICS. MAINTENANCE UP TO THIS DATE WILL BE REQUIRED BY THE CONTRACTOR.

SOIL EROSION AND SEDIMENT CONTROL NOTES:

- ALL TREE PROTECTION, SEDIMENT CONTROL MEASURES, AND PERMANENT AND TEMPORARY STORM WATER PRACTICES SHALL BE IN PLACE PRIOR TO STARTING CONSTRUCTION.
- NO WORK SHALL BE PERFORMED IN FLOWING WATER, WORK IN AND NEAR FLOWING WATER SHALL BE ISOLATED FROM CONCENTRATED FLOWS OR STREAM FLOWS AT ALL TIMES. THE USE OF EARTHEN MATERIAL FOR ISOLATION WILL NOT BE ACCEPTABLE
- 3. CONSTRUCTION MATERIALS AND/OR OTHER STOCKPILES SHALL NOT BE LOCATED ON STREAM BANKS NOR IN THE PATH OF STREAM FLOW
- 4. TEMPORARY EROSION CONTROL DEVICES SHALL BE CONSTRUCTED AS SHOWN ON THE PLANS OR AS DIRECTED BY THE ENGINEER.
- 5. PERMANENT SEEDING SHALL BE USED WHENEVER POSSIBLE. UNDER NO CIRCUMSTANCES SHALL THE CONTRACTOR PROLONG GRADING OR SHAPING SO THAT THE ENTIRE PROJECT CAN BE PERMANENTLY SEEDED AT ONE TIME.
- 6. THE CONTRACTOR SHALL INSPECT ADJACENT STREETS DAILY AND CLEAN ADJACENT STREETS WHEN NECESSARY ADJACENT STREETS SHALL BE KEPT FREE OF SOIL AND DEBRI
- 7. SHOULD IT BE NECESSARY TO REMOVE ANY FROSION CONTROL DEVICES FOR CONSTRUCTION REASONS. THE CONTRACTOR SHALL FIRST OBTAIN PERMISSION AND SHALL REPLACE AND/OR REPAIR THE REMOVED DEVICES THE SAME DAY. THE COST OF REMOVING AND REPLACING THE DEVICE SHALL BE CONSIDERED INCIDENTAL TO THE CONTRACT.
- 8. ALL OTHER SOIL EROSION AND SEDIMENT CONTROL DEVICES AND MEASURES DEEMED NECESSARY BY THE RESIDENT ALL OTHER OUE DOWN AND DEDMILTER OWNED AND MERSONED DELMED REDUCTION OF THE REDUCTION OF THE REDUCTION OF THE REDUCTION OF THE CONTRACTOR.
- 9. THE CONTRACTOR SHALL PROVIDE LOCATIONS FOR CONCRETE TRUCK WASHOUT, AS APPROVED BY THE ENGINEER, PRIOR TO ANY CONCRETE POURS. THESE LOCATIONS SHALL NOT BE NEAR ANY STREAM OR BODY OF WATER. LOCATIONS SHALL BE APPROVED BY THE ENGINEER PRIOR TO ANY CONCRETE POURS. ADDITIONALLY THE CONTRACTOR SHALL PROVIDE ADEQUATE FACILITIES TO WASH OUT PAVING EQUIPMENT AND FINISHING TOOLS. ALL WASTE WATER AND EXCESS CONCRETE MATERIALS SHALL BE CONTAINED BY AN APPROVED CONCRETE WASHOUT FACILITY.
- 10. THE CONTRACTOR SHALL COORDINATE CONSTRUCTION ACTIVITIES TO ENSURE THAT EROSION CONTROL MEASURES ARE CONSISTENT BETWEEN ALL PROJECT PHASES AND ALL SUB-CONTRACTORS
- 11. THE CONTRACTOR SHALL TAKE ALL PRECAUTIONS TO PROTECT WETLANDS TO REMAIN FROM DAMAGE BY SEDIMENT CONSTRUCTION EQUIPMENT, OR BY HIS PERSONNEL. THE CONTRACTOR SHALL ASSURE THAT DEBRIS OR ANY CONSTRUCTION MATERIAL IS NOT DISPOSED OF IN THE WETLANDS.
- 12. WATER PUMPED OR OTHERWISE DISCHARGED FROM THE SITE DURING CONSTRUCTION DEWATERING SHALL BE FILTERED.
- 13. SEDIMENT COLLECTED DURING CONSTRUCTION BY THE VARIOUS TEMPORARY EROSION CONTROL SYSTEMS SHALL BE DISPOSED OF ON A BEGULAR BASIS SEDIMENT SHALL BE REMOVED FROM FROSION CONTROL SYSTEMS WHEN THE HEIGHT OF THE SEDIMENT EXCEEDS ONE-HALF OF THE HEIGHT OF THE DEVICE OR AS RECOMMENDED BY THE MANUFACTURER, WHICHEVER IS LESS.
- 14. ALL EROSION CONTROL MEASURES SHALL BE KEPT OPERATIONAL AND MAINTAINED CONTINUOUSLY THROUGHOUT THE PERIOD OF LAND DISTURBANCE UNTIL PERMANENT SOIL EROSION AND SEDIMENT CONTROL MEASURES ARE OPERATIONAL
- 15. THE CONDITION OF THE CONSTRUCTION SITE FOR WINTER SHUTDOWN SHALL BE ADDRESSED EARLY IN THE FALL GROWING SEASON SO THAT SLOPES AND OTHER BARE EARTH AREAS MAY BE STABILIZED WITH TEMPORARY AND/OR PERMANENT VEGETATIVE COVER. ALL OPEN AREAS THAT ARE TO REMAIN IDLE THROUGHOUT THE WINTER SHALL RECEIVE TEMPORARY FROSION CONTROL MEASURES INCLUDING TEMPORARY SEEDING, MULCHING AND/OR FROSION CONTROL BLANKET PRIOR TO THE END OF THE FALL GROWING SEASON. THE AREAS TO BE WORKED BEYOND THE END OF THE GROWING SEASON MUST INCORPORATE SOIL STABILIZATION MEASURES THAT DO NOT RELY ON VEGETATIVE COVER SUCH AS EROSION CONTROL BLANKET AND HEAVY MULCHING.
- 16. PERMANENT STABILIZATION SHALL BE COMPLETED WITHIN 7 DAYS FOR AREAS WHERE WORK IS COMPLETED.

STAGING AND PROTECTION NOTES

- 1. THE CONTRACTOR SHALL BE REQUIRED TO PROVIDE STORM WATER POLILUTION PREVENTION DEVICES AT THE STAGING AREA. THESE DEVICES, INCLUDING INLET PROTECTIONS, SILT FENCE, BALES, DITCH CHECKS, STABILIZED CONSTRUCTION ENTRANCES, ETC., SHALL NOT BE PAID FOR, BUT SHALL BE CONSIDERED INCIDENTAL TO THE CONTRACT.
- 2. AT THE COMPLETION OF WORK, THE STAGING AREA SHALL BE RESTORED TO PRE-CONSTRUCTION CONDITIONS. AT NO ADDITIONAL COST TO THE CONTRACT. THIS WORK SHALL INCLUDE REMOVING ANY AND ALL STORM WATER POLLUTION PREVENTION DEVICES, RESTORING RUTTED AREAS, SEEDING AND MULCHING.
- 3. IT IS THE CONTRACTOR'S RESPONSIBILITY TO MAINTAIN THE STAGING AREA(S) IN A MANNER TO PREVENT POLLUTION AND SILTATION OF THE EXISTING STORM SEWER SYSTEM.
- 4. ALL EQUIPMENT FUELING AND GREASING SHALL BE COMPLETED AT THE STAGING AREA. SPILLS SHALL BE IMMEDIATELY CONTAINED AND THE AREA CLEANED AT NO ADDITIONAL COST THE CONTRACT.

NOTES:

- IN THE SPECIAL PROVISIONS.

- WITH THE FABRIC MATERIA

STEP

STEP 2

STEP 3

