

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
303	29R-T	McHENRY	88	11
STA.		TO STA.		
FED. ROAD DIST. NO. 1		ILLINOIS FED. AID PROJECT		
JOB D-91-190-01		CONTRACT NO. 62202		

ITEM M4060980 BITUMINOUS SURFACE REMOVAL-BUTT JOINT	
STATION TO STATION	AREA (Sq m)
0+881.40 TO 0+882.75	17
1+025.63 TO 1+026.98	26
TOTAL =	43

ITEM M3111100 SUB-BASE GRANULAR MATERIAL, TYPE B 100mm	
STATION TO STATION	AREA (Sq m)
0+925.00 TO 1+000.00	1279
TOTAL =	1279

ITEM M4402050 SIDEWALK REMOVAL		
STATION TO STATION	RIGHT (Sq m)	LEFT (Sq m)
0+645.05 TO 0+676.06	54.50	
0+661.14 TO 0+685.08		28.60
0+875.33 TO 0+982.78	114.53	
0+875.33 TO 0+982.78		130.87
* 0+658.50 TO 0+675.00		18.50
TOTAL (RIGHT + LEFT) =		347

ITEM M4428435 CLASS D PATCHES, TYPE IV, 275mm	
STATION TO STATION	AREA (Sq m)
0+656.87 TO 0+678.52, 10.19 m RT.	22
TOTAL =	22

ITEM M4400065 BITUMINOUS SURFACE REMOVAL 63mm	
STATION TO STATION	AREA (Sq m)
0+882.75 TO 0+925.00	541.53
1+000.00 TO 1+026.98	452.47
TOTAL =	994

ITEM M3530245 PORTLAND CEMENT CONCRETE BASE COURSE 245mm	
STATION TO STATION	AREA (Sq m)
0+925.00 TO 1+000.00	1162
TOTAL =	1162

ITEM M4240125 PORTLAND CEMENT CONCRETE SIDEWALK 125mm		
STATION TO STATION	RIGHT (Sq m)	LEFT (Sq m)
0+644.59 TO 0+647.68	6.50	
0+658.78 TO 0+661.14		4.90
0+982.78 TO 1+026.98		91.30
0+982.78 TO 1+026.98	92.10	
* 0+658.42 TO 0+675.00		29.20
TOTAL (RIGHT + LEFT) =		224

ITEM M2080150 TRENCH BACKFILL	
LOCATION	Cu m
SEWER ①	1.00
SEWER ②	15.00
SEWER ③	71.75
SEWER ④	2.84
SEWER ⑥	4.75
PART OF SEWER ⑥	13.96
SEWER ⑧	5.54
SEWER ⑨	6.16
TOTAL =	121

ITEM MX406770 POLYMERIZED LEVELING BINDER (MACHINE METHOD), SUPERPAVE, IL-4.75, N50, 19mm TO 25mm	
STATION TO STATION	(M TON)
0+881.40 TO 0+925.00	35.29
0+925.00 TO 1+000.00	69.51
1+000.00 TO 1+026.98	28.20
TOTAL =	133

ITEM M4402040 COMBINATION CURB AND GUTTER REMOVAL		
STATION TO STATION	RIGHT (m)	LEFT (m)
0+881.40 TO 1+026.98		145.58
0+881.40 TO 1+026.98	145.58	
0+666.20, 6.0m RT TO 0+670.04, 6.0m RT	3.84	
TOTAL (RIGHT + LEFT) =		295

ITEM 20101100 TREE TRUNK PROTECTION	
STATION	EACH
0+980.40, 15.30 m LT.	1
1+003.54, 12.93 m LT.	1
1+019.48, 11.34 m LT.	1
TOTAL =	3

ITEM M4427235 CLASS C PATCHES, TYPE II, 300mm	
LOCATION	Sq m
US 14 ROADWAY RESURFACING AREA	60
TOTAL =	60

ITEM MX406024* BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "D", N70, 38mm	
STATION TO STATION	(M TON)
0+881.40 TO 0+925.00	53.49
0+925.00 TO 1+000.00	105.65
1+000.00 TO 1+026.98	42.86
TOTAL =	202

ITEM M6060700 COMBINATION CONCRETE CURB AND GUTTER, TYPE B-15.60		
STATION TO STATION	RIGHT (m)	LEFT (m)
0+881.40 TO 0+986.00		104.60
0+881.40 TO 0+986.79	105.5	
0+994.60 TO 1+026.98		32.5
1+001.62 TO 1+026.98	25.4	
TOTAL (RIGHT + LEFT) =		268

ITEM M2010110 TREE REMOVAL (6 TO 15 UNITS DIAMETER)	
STATION	UNIT
0+966.57, 12.57 m LT.	6
TOTAL =	6

ITEM M4427435 CLASS C PATCHES, TYPE IV, 300mm	
LOCATION	Sq m
0+875.00 TO 0+930.40, 11.65 m LT.	45.24
US 14 ROADWAY RESURFACING AREA	39.76
TOTAL =	85

ITEM M4402000 PAVEMENT REMOVAL	
STATION TO STATION	AREA (Sq m)
0+666.00 TO 0+670.00, 3.9 m RT.	14.5
0+881.50 TO 0+885.00	55.25
0+925.00 TO 1+000.00	955.25
TOTAL =	1,025

ITEM MX606050* COMBINATION CONCRETE CURB AND GUTTER, TYPE M-5.60		
STATION TO STATION	RIGHT (m)	LEFT (m)
0+986.00 TO 0+944.60		9
0+986.79 TO 1+001.62	15	
TOTAL (RIGHT + LEFT) =		24

ITEM M4061000 BITUMINOUS REPLACEMENT OVER PATCHES	
STATION	M ton
NW CORNER OF BRIDGE ON PARKING LOT	6
TOTAL =	6

ITEM M4400375* BITUMINOUS REMOVAL OVER PATCHES 75 mm	
STATION	Sq m
NW CORNER OF BRIDGE ON PARKING LOT	29
TOTAL =	29

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
US 14 - MOKELER CREEK TO N. OF
IL. 173 AND AT UPRR

SCHEDULE OF QUANTITIES

SCALE: NONE DRAWN BY R.A.D.
DATE FEBRUARY, 2005 CHECKED BY DR, SSJ