

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	TOTAL	CONSTRUCTION TYPE CODE			
				ROAD	STA. 107+00 BOX CULVERT	STA. 110+00 BOX CULVERT	LIGHTING
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	6	6			
20100500	TREE REMOVAL, ACRES	ACRE	0.25	0.25			
20101100	TREE TRUNK PROTECTION	EACH	1	1			
20101350	TREE PRUNING (OVER 10 INCH DIAMETER)	EACH	1	1			
20200100	EARTH EXCAVATION	CU YD	2472	2472			
*20200200	ROCK EXCAVATION	CU YD	50		50		
20200410	EARTH EXCAVATION (SPECIAL)	CU YD	599	599			
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	160	60	100		
20300100	CHANNEL EXCAVATION	CU YD	1245	780	465		
20400800	FURNISHED EXCAVATION	CU YD	21	21			
20700220	POROUS GRANULAR EMBANKMENT	CU YD	405	215	190		
*21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	8612	8612			
*25000210	SEEDING, CLASS 2A	ACRE	1.00	1.00			
*25000312	SEEDING, CLASS 4A	ACRE	0.75	0.75			
*25000400	NITROGEN FERTILIZER NUTRIENT	POUND	161	161			
*25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	161	161			
*25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	161	161			
*25100105	MULCH, METHOD 1	ACRE	1.75	1.75			
*25100630	EROSION CONTROL BLANKET	SQ YD	6552	6552			
*25200110	SODDING, SALT TOLERANT	SQ YD	2152	2152			
*25200200	SUPPLEMENTAL WATERING	UNIT	15	15			
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	2889	2889			
28000300	TEMPORARY DITCH CHECKS	EACH	24	24			
28000400	PERIMETER EROSION BARRIER	FOOT	2272	2272			

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	TOTAL	CONSTRUCTION TYPE CODE			
				ROAD	STA. 107+00 BOX CULVERT	STA. 110+00 BOX CULVERT	LIGHTING
20200100	FILTER FABRIC FOR USE WITH RIP RAP	SQ YD	107				
28300400	AGGREGATE DITCH	TON	21	21			
28400100	GABIONS	CU YD	50			50	
31101200	SUB-BASE GRANULAR MATERIAL, TYPE B 4"	SQ YD	3613	3613			
35300400	PORTLAND CEMENT CONCRETE BASE COURSE 9"	SQ YD	2960	2960			
40300100	BITUMINOUS MATERIALS (PRIME COAT)	GAL	525	525			
40600300	AGGREGATE (PRIME COAT)	TON	8	8			
40600895	CONSTRUCTING TEST STRIP	EACH	2	2			
40601000	BITUMINOUS REPLACEMENT OVER PATCHES	TON	51	51			
44000100	PAVEMENT REMOVAL	SQ YD	7939	7939			
42001300	PROTECTIVE COAT	SQ YD	8	8			
44000140	BITUMINOUS REMOVAL OVER PATCHES 10"	SQ YD	592	592			
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	398	398			
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	193	193			
44201761	CLASS D PATCHES, TYPE I, 10 INCH	SQ YD	296	296			
44201765	CLASS D PATCHES, TYPE II, 10 INCH	SQ YD	296	296			
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	2220	2220			
48101620	AGGREGATE SHOULDERS, TYPE B 10"	SQ YD	1547	1547			
48202800	BITUMINOUS SHOULDERS SUPERPAVE 10"	SQ YD	2285	2285			
50100300	REMOVAL OF EXISTING STRUCTURES NO. 1	EACH	1			1	
50100400	REMOVAL OF EXISTING STRUCTURES NO. 2	EACH	1		1		
50104300	CONCRETE HEADWALL REMOVAL	CU YD	1.5			1.5	
50105220	PIPE CULVERT REMOVAL	FOOT	177	146	31		

#62391

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 U.S. ROUTE 14 OVER LAWRENCE CREEK
SUMMARY OF QUANTITIES
 DRAWN BY CLG
 CHECKED BY JJD
 DATE: 2-15-05

* SPECIALTY ITEM

Rev. 4-14-05



32875HT3.DGN