

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	TOTAL	CONSTRUCTION TYPE CODE			
				ROAD	STA. 107+00 BOX CULVERT	STA. 110+00 BOX CULVERT	LIGHTING
50200100	STRUCTURE EXCAVATION	CU YD	100		20	80	
51205200	TEMPORARY SHEET PILING	SQ FT	2005		1125	880	
51500100	NAME PLATES	EACH	2		1	1	
54001000	BOX CULVERT END SECTIONS	EACH	4		2	2	
54010507	PRECAST CONCRETE BOX CULVERT 5' x 7'	FOOT	60		60		
54010806	PRECAST CONCRETE BOX CULVERT 8' x 6'	FOOT	174		120	54	
54011205	PRECAST CONCRETE BOX CULVERT 12' x 5'	FOOT	108			108	
54104200	CORRUGATED STRUCTURAL PLATE PIPE ARCHES 51 SQ. FT	FOOT	38			38	
54200643	PIPE CULVERTS, TYPE 1, CORRUGATED STEEL OR ALUMINUM CULVERT PIPE 18"	FOOT	256	256			
54213873	STEEL END SECTIONS 18"	EACH	16	16			
60624600	CORRUGATED MEDIAN	SQ FT	76	76			
*63000005	STEEL PLATE BEAM GUARD RAIL, TYPE B	FOOT	850	850			
*63100167	TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (TANGENT)	EACH	5	5			
*63100169	TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (FLARED)	EACH	3	3			
63200305	STEEL PLATE BEAM GUARD RAIL REMOVAL	FOOT	313	313			
66500105	WOVEN WIRE FENCE, 4"	FOOT	181	181			
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6			
67100100	MOBILIZATION	L SUM	1	1			
70100200	TRAFFIC CONTROL AND PROTECTION, STANDARD 701331	EACH	2	2			
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	180	180			
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	792	792			

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	TOTAL	CONSTRUCTION TYPE CODE			
				ROAD	STA. 107+00 BOX CULVERT	STA. 110+00 BOX CULVERT	LIGHTING
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	8030	8030			
70300520	PAVEMENT MARKING TAPE, TYPE III, 4"	FOOT	9970	9970			
70301000	WORKZONE PAVEMENT MARKING REMOVAL	SQ FT	6266	6266			
70400100	TEMPORARY CONCRETE BARRIER	FOOT	1505	1505			
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	400	400			
*78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	6293	6293			
*78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	32	32			
*78200530	BARRIER WALL MARKERS, TYPE C	EACH	152	152			
78300100	PAVEMENT MARKING REMOVAL	SQ FT	1771	1771			
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	18	18			
*80700140	GROUND ROD, 5/8" DIA. X 10 FT	EACH	10				10
80800500	TEMPORARY WOOD POLE, 60 FT., CLASS 4	EACH	1				1
*80800525	TEMPORARY WOOD POLE, 60 FT., CLASS 4, 15 FT. MAST ARM	EACH	14				14
*81001100	UNIT DUCT, WITH 3 1/8 NO. 2 AND 1/8 NO. 4 GROUND CORD (WLD TYPE USE) 1/4" DIA. POLYETHYLENE	FOOT	20				20
*81800100	AERIAL CABLE, 3-1/8 NO. 3/0 ALUMINUM, WITH MESSENGER WIRE	FOOT	3000				3000
*82103400	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 400 WATT	EACH	14				14
*A2002566	TREE, CARPINUS CAROLINIANA (AMERICAN HORN- BEAM), 6' HEIGHT, SHRUB FORM, BALLED AND BURLAPPED	EACH	8	8			
*B2000566	TREE, AMELANCHIER CANADENSIS (SHADBLOW SERVICEBERRY), 6' HEIGHT, SHRUB FORM, BALLED AND BURLAPPED	EACH	12	12			
B4100110	REMOVAL OF TEMPORARY LIGHTING UNITS	EACH	14				14

* SPECIALTY ITEM

Applied Technologies

Rev. 4-14-05

Rev.

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
U.S. ROUTE 14 OVER LAWRENCE CREEK
SUMMARY OF QUANTITIES

DRAWN BY CLG
CHECKED BY JJD
DATE: 2-15-05

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
066	21 (B&G) R	McHENRY	66	4
STA.	TO STA.			
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT	#62391	

3287SHT3.DGN