

62583

SUMMARY OF QUANTITIES						
CODE NO.	ITEM	UNIT	90% FED. 10% STATE	QUANTITIES		
			URBAN	CIVIL	LIGHTING	SURVEILLANCE
			QUANTITY	J000	Y030-1E	Y032-1F
X7015050	PORTABLE CHANGEABLE MESSAGE SIGN	GAL MO	0	0	0	0
X7040600	FURNISH TEMPORARY CONCRETE BARRIER	FOOT	1,120	1,120	0	0
X7240600	REMOVE AND RE-ERECT EXISTING SIGN	EACH	5	5	0	0
X8040100	ELECTRIC CONNECTION TO SIGN STRUCTURE	EACH	71	0	71	0
B1023750	CONDUIT ENCASED, CONCRETE, 3" DIA., PVC	FOOT	126	0	0	126
X8100045	CONDUIT ENCASED, REINFORCED CONCRETE, 1-3" DIA., CNC	FOOT	252	0	252	0
X0324792	CONDUIT ENCASED, REINFORCED CONCRETE, 2-5" DIA., RGC, 2WIDE X 1 HIGH	FOOT	947	0	947	0
X8110110	CONDUIT ATTACHED TO STRUCTURE, 1" DIA. GALVANIZED STEEL, PVC COATED	FOOT	15,686	0	15,686	0
X8110115	CONDUIT ATTACHED TO STRUCTURE, 2" DIA. GALVANIZED STEEL, PVC COATED	FOOT	10,849	0	84	10,765
X8110121	CONDUIT ATTACHED TO STRUCTURE, 3" DIA. GALVANIZED STEEL, PVC COATED	FOOT	1,267	0	1,267	0
X8160160	UNIT DUCT, WITH 2-1/C NO. 4 AND 1/C NO. 4 GROUND, 600V (EPR-TYPE RHW), 1 1/4" DIA., POLYETHYLENE	FOOT	11,577	0	0	11,577
X8160370	UNIT DUCT, WITH 3-1/C NO. 4 AND 1/C NO. 6 GROUND, 600V (EPR-TYPE RHW), 1 1/4" DIA., POLYETHYLENE	FOOT	31,141	0	31,141	0
X8160380	UNIT DUCT, WITH 3-1/C NO. 2 AND 1/C NO. 4 GROUND, 600V (EPR-TYPE RHW), 1 1/4" DIA., POLYETHYLENE	FOOT	98,793	0	98,793	0
X8210020	TEMPORARY LUMINAIRE, SODIUM VAPOR, HIGH MAST, HORIZONTAL MOUNT, 400 WATT	EACH	22	0	22	0
X8210055	FLUORESCENT LUMINAIRE FOR SIGN LIGHTING	EACH	284	0	284	0
X8250070	TEMPORARY LIGHTING CONTROLLER (INSTALL ONLY)	EACH	2	0	2	0
X0324280	LIGHTING CONTROLLER, RADIO CONTROL, DUPLEX TYPE WITH SCADA AND VIDEO POWER	EACH	6	0	6	0
X8324181	DISCONNECT SIGN LIGHTING AND REMOVE WIRING TO NEAREST SPLICE	EACH	49	0	49	0
X8350205	LIGHT TOWER, 100 FT. MOUNTING HEIGHT, LUMINAIRE MT. - 12, INSTALL ONLY	EACH	42	0	42	0
X8350305	LIGHT TOWER, 110 FT. MOUNTING HEIGHT, LUMINAIRE MT. - 12, INSTALL ONLY	EACH	82	0	82	0
X8350405	LIGHT TOWER, 120 FT. MOUNTING HEIGHT, LUMINAIRE MT. - 12, INSTALL ONLY	EACH	11	0	11	0
X8420102	REMOVE EXISTING UNDERPASS LUMINAIRE, AND SALVAGE	EACH	384	0	384	0
X8710028	FIBER OPTIC CABLE 6 FIBERS, SINGLE MODE	FOOT	8,745	0	0	8,745
X8710029	FIBER OPTIC CABLE 24 FIBERS, SINGLE MODE	FOOT	0	0	0	0
X8710030	FIBER OPTIC CABLE 48 FIBERS, SINGLE MODE	FOOT	201,469	0	0	201,469
X8710035	FIBER OPTIC CABLE 96 FIBERS, SINGLE MODE	FOOT	61,654	0	0	61,654
X8801200	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 2-SECTION, BRACKET MOUNTED	EACH	2	0	0	2
X8801210	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 2-SECTION, POST MOUNTED	EACH	26	0	0	26
XX004046	AERIAL CABLE REMOVAL	FOOT	20,008	0	14,200	5,808
XX004383	RELOCATE EXISTING CONTROLLER AND TYPE IV CABINET, SPECIAL	EACH	1	0	0	1
XX104800	COMBINATION CONCRETE CURB AND GUTTER TYPE B-V, 12	FOOT	115	115	0	0
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	0	1	0



REVISIONS	
NAME	DATE
REVISION #4	3/24/05
REVISION #1	12/17/04

ILLINOIS DEPARTMENT OF TRANSPORTATION
F.A.I. 90/94 (DAN RYAN EXPRESSWAY)
31st STREET TO I-57

SUMMARY OF QUANTITIES

SCALE: NONE
DATE: October 29, 2004
DRAWN BY: CJM
CHECKED BY: JPC

03/21/2005 03:06:34 PM