

2227+00 2228+00 2229+00 2230+00 2231+00 2232+00

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
90/94	2003-0311	COOK	176	460
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		
		62583		

NB I-94 (DAN RYAN EXPWY)

TRAFFIC CONTROL AND PROTECTION (HWY. STD. 701601), LUMP SUM

6' COMB. C&G REMOVAL  
2 S.Y. SUB BASE GRANULAR MATERIAL, TYPE B 6"  
6' COMB. CONC. C&G, TYPE B-V.12  
2 S.Y., PROTECTIVE COAT

PROPOSED LIGHTING CONTROLLER "O"

FOR INFORMATION ONLY TO BE BUILT IN CONTRACT 62694 HMLT FOUNDATION (WALL MOUNT)

600P1

23 S.Y. PAVED SHOULDER REMOVAL  
23 S.Y. BITUMINOUS SHOULDERS SUPERPAVE, 6"

LIMIT OF BIT. SURFACE REMOVAL 1 1/2", 78 S.Y.  
LIMIT OF BIT. CONC. SURFACE COURSE, 1 1/2"  
SUPERPAVE MIX "D" N70, 7 TONS  
BIT. MATERIALS (PRIME COAT), 0.01 TONS  
AGGREGATE (PRIME COAT), 0.2 TONS  
PAVEMENT REMOVAL, 17 S.Y.  
SUB BASE GRANULAR MATERIAL, TYPE B 6", 17 S.Y.  
P.C.C. BASE COURSE, 10.5", 17 S.Y.

S. STATE STREET

E. 91st STREET

MATCHLINE NB STA. 2233+00.00

2233+00 2234+00 2235+00 2236+00 2237+00

PROPOSED NB I-94

NB I-94 (DAN RYAN EXPWY)

SIDEWALK REMOVAL, 27 S.F.  
P.C.C. SIDEWALK 5", 27 S.F.  
PROTECTIVE COAT, 3 S.Y.  
(SIDEWALK SHALL BE REPAIRED TO NEAREST JOINT)

TOPSOIL, FURNISH AND PLACE 4", 7 S.Y.  
SODDING, SALT TOLERANT, 7 S.Y.

6' COMB. C&G REMOVAL  
1 S.Y. SUB BASE GRANULAR MATERIAL, TYPE B 6"  
6' COMB. CONC. C&G, TYPE B-V.12  
2 S.Y., PROTECTIVE COAT

C.R.I. & P. R.R.


BELT RY.

600P2


FOR INFORMATION ONLY TO BE BUILT IN CONTRACT 62694 HMLT FOUNDATION (WALL MOUNT)

S. STATE STREET

MATCHLINE NB STA. 2233+00.00



LOCATION MAP



**LEGEND:**

EROSION CONTROL BLANKET, SEEDING, CLASS 2A, NITROGEN, PHOSPHORUS, AND POTASSIUM FERTILIZER NUTRIENTS, TOPSOIL FURNISH AND PLACE, 4"

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
F.A.I. 90/94 (DAN RYAN EXPRESSWAY)  
31st STREET TO I-57  
**RESTORATION PLAN**  
NB I-94 (DAN RYAN EXPRESSWAY)  
NB I-94 STA. 2227+00.00 TO 2237+00.00  
SCALE: 1"=20'  
DATE: OCTOBER 29, 2004  
DRAWN BY: RTM, JPA  
CHECKED BY: JPM, MAG

TYLIN INTERNATIONAL

11/23/2004 02:56:00 PM