

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
305	2004-108 BR	COOK	72	3

CONTRACT NO. 62853

# SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	URBAN TOTAL QUANTITY	ROADWAY	BRIDGE (WOLF ROAD)	BRIDGE (WEST FRONTAGE ROAD)	BRIDGE (EAST FRONTAGE ROAD)	BRIDGE (WISCONSIN CENTRAL RAILROAD)	SIGNAL (WOLF ROAD)					
				CONSTRUCTION TYPE CODE (100% STATE)										
				1000	SFTY-2A	SFTY-2A	SFTY-2A	SFTY-2A	Y031-1F					
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	179	179	0	0	0	0	0					
21101645	TOPSOIL FURNISH AND PLACE, 12"	SQ YD	806	806	0	0	0	0	0					
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	10	10	0	0	0	0	0					
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	10	10	0	0	0	0	0					
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	10	10	0	0	0	0	0					
25200110	SODDING, SALT TOLERANT	SQ YD	806	806	0	0	0	0	0					
25200200	SUPPLEMENTAL WATERING	UNIT	40	40	0	0	0	0	0					
28000510	INLET FILTERS	EACH	7	7	0	0	0	0	0					
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	1.1	1.1	0	0	0	0	0					
40600300	AGGREGATE (PRIME COAT)	TON	4	4	0	0	0	0	0					
40600980	BITUMINOUS SURFACE REMOVAL - BUTT JOINT	SQ YD	386	386	0	0	0	0	0					
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	253	253	0	0	0	0	0					
44000030	BITUMINOUS SURFACE REMOVAL (VARIABLE DEPTH)	SQ YD	1405	1405	0	0	0	0	0					
44000100	PAVEMENT REMOVAL	SQ YD	732	732	0	0	0	0	0					
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	369	369	0	0	0	0	0					
44000600	SIDEWALK REMOVAL	SQ FT	200	200	0	0	0	0	0					
44001205	BITUMINOUS CONCRETE SURFACE REMOVAL COMPLETE	SQ YD	837	0	367	240	230	0	0					
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	68	68	0	0	0	0	0					
44003100	MEDIAN REMOVAL	SQ FT	3577	3577	0	0	0	0	0					
50102400	CONCRETE REMOVAL	CU YD	19.7	0	11	2.4	6.3	0	0					
50104100	BRIDGE HANDRAIL REMOVAL	FOOT	66	0	0	0	66	0	0					
50300110	PREFORMED JOINT SEAL 1 3/4"	FOOT	132	0	70	31	31	0	0					
50300120	PREFORMED JOINT SEAL 2 1/2"	FOOT	132	0	70	31	31	0	0					
50300255	CONCRETE SUPERSTRUCTURE	CU YD	86.9	0	72.1	5	9.8	0	0					
50300260	BRIDGE DECK GROOVING	SQ YD	868	0	433	220	215	0	0					
50300300	PROTECTIVE COAT	SQ YD	1138	0	573	310	255	0	0					
50301200	CONCRETE WEARING SURFACE	SQ YD	903	0	433	240	230	0	0					
50301245	FORMED CONCRETE REPAIR (DEPTH EQUAL TO OR LESS THAN 5")	SQ FT	<del>680</del>	0	<del>500</del>	<del>30</del>	<del>100</del>	<del>40</del>	0					
<del>50301250</del>	<del>FORMED CONCRETE REPAIR (DEPTH GREATER THAN 5")</del>	<del>SQ FT</del>	<del>200</del>		<del>150</del>	<del>10</del>	<del>25</del>	<del>15</del>						
50400605	PRECAST PRESTRESSED CONCRETE DECK BEAMS (33" DEPTH)	SQ FT	1210	0	1210	0	0	0	0					
50500405	FURNISHING AND ERECTING STRUCTURAL STEEL	POUND	5465	0	2150	1684	1631	0	0					

\* SPECIALTY ITEM

CONSTRUCTION TYPE CODE SFTY-3N

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
PALATINE ROAD UNDER W.C.R.R. UNDER W. FRONTAGE RD.,  
UNDER E. FRONTAGE RD. & UNDER WOLF RD.

### SUMMARY OF QUANTITIES

SCALE: NONE  
DATE: 02/05

DRAWN BY: ACE/CAD  
CHECKED BY: TAE



Rev.

HW 12 99 02 508/02/03 454 15 15 AM CONSULTING ENGINEERS