

SUMMARY OF QUANTITIES

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
305	2004-108 BR	COOK	72	5

CONTRACT NO. 62853

CODE NO.	ITEM	UNIT	URBAN TOTAL QUANTITY	ROADWAY	BRIDGE (WOLF ROAD)	BRIDGE (WEST FRONTAGE ROAD)	BRIDGE (EAST FRONTAGE ROAD)	BRIDGE (WISCONSIN CENTRAL RAILROAD)	SIGNAL (WOLF ROAD)					
				CONSTRUCTION TYPE CODE (100% STATE)										
				1000	SFTY-2A	SFTY-2A	SFTY-2A	SFTY-2A	Y031-IF					
* 81500200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	14	0	0	0	0	0	14					
* 87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	FOOT	1105	0	0	0	0	0	1105					
* 87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	2032	0	0	0	0	0	2032					
* 87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	FOOT	1667	0	0	0	0	0	1667					
* 87301305	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR	FOOT	1634	0	0	0	0	0	1634					
* 87900200	DRILL EXISTING HANDHOLE	EACH	2	0	0	0	0	0	2					
* 88600100	DETECTOR LOOP, TYPE I	FOOT	132	0	0	0	0	0	132					
* 89000100	TEMPORARY TRAFFIC SIGNAL INSTALLATION	EACH	1	0	0	0	0	0	1					
* 89502200	MODIFY EXISTING CONTROLLER	EACH	1	0	0	0	0	0	1					
* 89502300	REMOVE ELECTRIC CABLE FROM CONDUIT	FOOT	5281	0	0	0	0	0	5281					
X0320047	REMOVAL OF EXISTING PRECAST PRESTRESSED CONCRETE DECK BEAMS	SQ FT	1210	0	1210	0	0	0	0					
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	48	48	0	0	0	0	0					
X0323818	CLEANING AND PAINTING EXPOSED REBAR	SQ FT	5	0	0	5	0	0	0					
X0712400	TEMPORARY PAVEMENT	SQ YD	732	732	0	0	0	0	0					
X4066426	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "D", N70	TON	179	179	0	0	0	0	0					
X4067100	POLYMERIZED LEVELING BINDER (MACHINE METHOD), SUPERPAVE, IL-4.75, N50	TON	119	119	0	0	0	0	0					
X7015000	CHANGEABLE MESSAGE SIGN	CAL MO	10	10	0	0	0	0	0					
X7030130	PAVEMENT MARKING TAPE, TYPE III 4", SPECIAL	FOOT	11659	11659	0	0	0	0	0					
* X8730250	ELECTRIC CABLE IN CONDUIT NO. 20 3/C, TWISTED, SHIELDED	FOOT	856	0	0	0	0	0	856					
* X8950200	REBUILD EXISTING HANDHOLE	EACH	1	0	0	0	0	0	1					
Z0002600	BAR SPLICERS	EACH	148	0	148	0	0	0	0					
Z0003700	BEARING PAD ADJUSTMENT	EACH	84	0	32	26	26	0	0					
Z0007300	BRIDGE SIDEWALK REPAIR (FULL DEPTH)	SQ FT	27	0	0	0	27	0	0					
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1	0	0	0	0	0					
[]* Z0030240	IMPACT ATTENUATORS, TEMPORARY (NON- REDIRECTIVE), TEST LEVEL 2	EACH	4	4	0	0	0	0	0					
Z0032700	KEYWAY REPAIR	FOOT	87	0	14	0	73	0	0					
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	0	0	0	0	1	0					

* SPECIALTY ITEM

[] CONSTRUCTION TYPE CODE
SFTY-3N

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
PALATINE ROAD UNDER WCR, UNDER W. FRONTAGE RD.,
UNDER E. FRONTAGE RD. & UNDER WOLF RD.

SUMMARY OF QUANTITIES

SCALE: NONE
DATE 02/05

DRAWN BY ACE/CAD
CHECKED BY TAE

