

URBAN  
1000

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2503	2004-116 RS	KANE	20	4

CONTRACT CONTRACT 62858

Pay Item	Description	Unit	Qty	Total
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON		2.00
40600300	AGGREGATE (PRIME COAT)	TON		9.00
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON		1.00
40600895	CONSTRUCTING TEST STRIP	EACH		1.00
40600980	BITUMINOUS SURFACE REMOVAL - BUTT JOINT	SQ YD		118.00
40601000	BITUMINOUS REPLACEMENT OVER PATCHES	TON		97.00
42001300	PROTECTIVE COAT	SQ YD		36.00
44000006	BITUMINOUS SURFACE REMOVAL 1 1/2"	SQ YD		4527.00
44000116	BITUMINOUS REMOVAL OVER PATCHES 4"	SQ YD		140.00
44000132	BITUMINOUS REMOVAL OVER PATCHES 8"	SQ YD		140.00
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT		200.00
44201753	CLASS D PATCHES, TYPE II, 9 INCH	SQ YD		158.00
44201757	CLASS D PATCHES, TYPE III, 9 INCH	SQ YD		23.00
44201759	CLASS D PATCHES, TYPE IV, 9 INCH	SQ YD		45.00
60250200	CATCH BASINS TO BE ADJUSTED	EACH		4.00
60255500	MANHOLES TO BE ADJUSTED	EACH		4.00
60260100	INLETS TO BE ADJUSTED	EACH		4.00
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO		2.00
67100100	MOBILIZATION	L SUM		1.00
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM		1.00
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM		1.00
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM		1.00
70300100	SHORT-TERM PAVEMENT MARKING	FOOT		430.00
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT		145.00
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT		182.00
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT		1668.00
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT		1020.00
* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT		250.00
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT		900.00
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT		152.00
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH		55.00
* 88600600	DETECTOR LOOP REPLACEMENT	FOOT		950.00
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT		96.00
X4066426	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "D", N70	TON		381.00
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT		2850.00
60266600	VALVE BOXES TO BE ADJUSTED	EACH		3.00

ILLINOIS DEPARTMENT OF TRANSPORTATION

## SUMMARY OF QUANTITIES