CONTRACT NO. 64A39

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
74	81-1TS-1	ROCK ISLAND	16	4
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

SCHEDULE OF QUANTITIES

20200500 EARTH EXCAVATION (WIDENING)

CU YD	LOCATION	REMARKS
	ROCK ISLAND COUNTY	
12	NORTHBOUND RAMP, NORTH RETURN	
38	NORTHBOUND RAMP, SOUTH RETURN	
TOTAL 50		

25200100 SODDING

SQ YD	LOCATION		REMARKS
	ROCK ISLAND COUNTY		
184.8	125+53.30 TO 126+32.10	LT	
176.3	226+11.70 TO 227+37.00	RT	
TOTAL 361.2			

31200100 STABILIZED SUBBASE 4"

SQ YD	LOCATION		REMARKS
	ROCK ISLAND COUNTY		
83.3	125+51.50 TO 126+27.30	LT	RETURN
100.2	125+68.50 TO 126+25.00	LT	ISLAND
121.9	225+82.20 TO 226+32.20	RT	ISLAND
120.4	226+09.30 TO 227+37.00	RT	RETURN
TOTAL 121.9			

35300500 PORTLAND CEMENT CONCRETE BASE COURSE 10"

SQ YD	LOCATION		REMARKS
	ROCK ISLAND COUNTY		
26.6	125+51.50 TO 126+27.30	LT	RETURN
67.7	125+68.50 TO 126+25.00	LT	ISLAND
59.1	225+82.20 TO 226+32.20	RT	ISLAND
81.5	226+09.30 TO 227+37.00	RT	RETURN
TOTAL 234.9			

42400200 PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH

SQ FT	LOCATION	REMARKS
	ROCK ISLAND COUNTY	
737	125+59.50 TO 126+30.10	
401.7	226+28.00 TO 226+99.00	
TOTAL 1138.7		

44000025 BITUMINOUS SURFACE REMOVAL (SPECIAL)

SQ YD	LOCATION	REMARKS
	ROCK ISLAND COUNTY	
705	125+56.00 TO 126+27.00	
590	225+70.00 TO 227+70.00	
TOTAL 1295		

44000500 COMBINATION CURB AND GUTTER REMOVAL

FOOT	LOCATION		REMARKS
	ROCK ISLAND COUNTY		
145.3	125+51.50 TO 126+27.30	LT	RETURN
170.0	226+09.30 TO 227+37.00	RT	RETURN
191	125+51.50 TO 126+27.30	LT	ISLAND
170.0	226+09.30 TO 227+37.00	RT	ISLAND
TOTAL 315.3			

44002800 ISLAND PAVEMENT REMOVAL

SQ YD	LOCATION	REMARKS
	ROCK ISLAND	
136	NORTHBOUND INTERSECTION	
17	SOUTHBOUND INTERSECTION	
TOTAL 153		

44300200 STRIP REFLECTIVE CRACK CONTROL TREATMENT

FOOT	LOCATION	REMARKS
	ROCK ISLAND COUNTY	
317	225+40.00 TO 228+20.00	
317	125+36.00 TO 126+87.00	
TOTAL 634		

60240355 INLETS, TYPE B, TYPE "V" FRAME AND GRATE

EACH	LOCATION		REMARKS
	ROCK ISLAND COUNTY		
1	125+68.46	99' LT	TYPE 3V GRATE
TOTAL 1			

60605000 COMBINATION CONCRETE CURB AND GUTTER, TYPE B - 6.24

FOOT	LOCATION		REMARKS
	ROCK ISLAND COUNTY		
146.1	125+51.50 TO 126+27.30	LT	
166.3	226+09.30 TO 227+37.00	RT	
TOTAL 312.4			

78000500 THERMOPLASTIC PAVEMENT MARKING - LINE 8"

FOOT	LOCATION	REMARKS
	ROCK ISLAND COUNTY	
240	NORTHBOUND RAMP, NORTH RETURN	ISLAND & CW'S
320	NORTHBOUND RAMP, SOUTH RETURN	ISLAND & CW'S
345	SOUTHBOUND RAMP, NORTH RETURN	ISLAND & CW'S
255	SOUTHBOUND RAMP, SOUTH RETURN	ISLAND & CW'S
TOTAL 1160		

78000600 THERMOPLASTIC PAVEMENT MARKING - LINE 12"

FOOT	LOCATION	REMARKS
	ROCK ISLAND COUNTY	
74	NORTHBOUND RAMP, NORTH RETURN	ISLAND CHEVRON
105	NORTHBOUND RAMP, SOUTH RETURN	ISLAND CHEVRON
97	SOUTHBOUND RAMP, NORTH RETURN	ISLAND CHEVRON
93	SOUTHBOUND RAMP, SOUTH RETURN	ISLAND CHEVRON
TOTAL 369		

78000650 THERMOPLASTIC PAVEMENT MARKING - LINE 24"

FOOT	LOCATION	REMARKS
	ROCK ISLAND COUNTY	
36	NORTHBOUND RAMP	STOP BARS
36	SOUTHBOUND RAMP	STOP BARS
TOTAL 72		

X0323230 ISLAND SPECIAL

SQ YD	LOCATION		REMARKS
	ROCK ISLAND COUNTY		
100.1	125+68.50 TO 126+25.00	LT	
122.0	225+82.20 TO 226+32.20	RT	
TOTAL 222.1			

X4066436 BITUMINOUS SURFACE COURSE, SUPERPAVE, MIX "E", N70

TON	LOCATION	REMARKS
	ROCK ISLAND COUNTY	
80	225+40.00 TO 228+20.00	
70	125+36.00 TO 126+87.00	
TOTAL 150		

X4066770 LEVELING BINDER (MACHINE METHOD), SUPERPAVE N70

TON	LOCATION	REMARKS
	ROCK ISLAND COUNTY	
53	225+40.00 TO 228+20.00	
47	125+36.00 TO 126+87.00	
TOTAL 100		

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCALE: VERT. HORIZ.

DATE

DRAWN BY

CHECKED BY

PLOT DATE = Wed Mar 09 12:56:01 2005
FILE NAME = S:\Pennsch\c81984.dgn
PLOT SCALE = 20.0000 ' / IN.
REFERENCE = REF