

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

ROUTE NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
S. B. I.	*	JoDaviess	7	2
F. A. I.				
FED. ROAD DIST. NO. 7	ILLINOIS	FED. AID PROJECT-		

* Section 102VBR-M CONTRACT NO. 64A87

TOTAL SUMMARY OF QUANTITIES – BRIDGE REPAIRS

GENERAL NOTES

CODE NUMBER	ITEM	SAFETY CODE		UNIT	TOTALS
		SFTY - 2A			
50300160	Neoprene Expansion Joint 4"	•		Foot	140
70102620	Traffic Control and Protection, Standard 701501	•		L. Sum	1
70102635	Traffic Control and Protection, Standard 701701	•		L. Sum	1
70102640	Traffic Control and Protection, Standard 701801	•		L. Sum	1
* X0301424	Silicone Joint Sealer	•		Foot	345
* X0321259	Polymer Modified Portland Cement Mortar	•		Cu. Ft.	55
* X0323648	Limestone Masonry Veneer	•		Sq. Ft.	60
* Z0022400	Fabric Reinforced Elastomeric Trough	•		Foot	137
Z0048665	Railroad Protective Liability Insurance	•		L. Sum	1
* X0324937	Stone Removal	•		Cu. Ft.	47
* X0324938	Limestone Replacement	•		Sq. Ft.	284
* X0324939	Anchor Rods	•		Each	160
67100100	MOBILIZATION	•		L SUM	1

* Specialty Items

See sheet 3 of 7 for additional general notes.

The contractor is responsible for all utility contacts prior to construction. Call J.U.L.I.E. at 1-800-892-0123.

The contractor is responsible for obtaining existing structure plans for all structures prior to construction or ordering materials. Plans are available by written request through the Illinois Department of Transportation, District 2, Bureau of Operations, 819 Depot Avenue, Dixon, Illinois 61021.

The structure will retain the same structure number.

After approval of initial submittal, the contractor shall submit one set of shop drawings to the Engineer of Materials, 126 Ash Street, Springfield, IL 62706, and eight (8) sets of shop drawings to be distributed to:

District 2 District Engineer (1)
Fabricator (1)
Contractor (2)
Resident Engineer (2)
District 2 Bureau of Materials (2)

SUMMARY OF QUANTITIES
F.A.P Route 301 (U.S. Route 20)
SECTION 102VBR-M
JoDAVIESS COUNTY
SN 043-0043