

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
681	118 N	IROQUOIS	30	4
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	90% FED 10% STATE		CONSTRUCTION CODE TYPE:		
			TOTAL QUANTITY	LIGHTING YO30-1E		SIGNALS YO31-1F	ROADWAY IO00-1A
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	238				238
* 72000100	SIGN PANEL - TYPE 1	SQ FT	122				122
72400200	REMOVE SIGN PANEL ASSEMBLY - TYPE B	EACH	8				8
72400600	RELOCATE SIGN PANEL ASSEMBLY - TYPE B	EACH	6				6
73000100	WOOD SIGN SUPPORT	FOOT	220				220
73200100	CONCRETE FOUNDATIONS FOR WOOD SIGN SUPPORT	EACH	6.6				6.6
78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	2920				2920
78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	696				696
78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	705				705
78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	120				120
* [REDACTED]	[REDACTED]	[REDACTED]	[REDACTED]				[REDACTED]
78200300	PRISMATIC CURB REFLECTOR	EACH	36				36
80500105	SERVICE INSTALLATION, TYPE A (MODIFIED)	EACH	1			1	
81012500	CONDUIT IN TRENCH, 1 1/2" DIA., PVC	FOOT	1609	50		1559	
81021350	CONDUIT PUSHED, 3" DIA., PVC	FOOT	421	210		211	
81102600	CONDUIT ATTACHED TO STRUCTURE, 2" DIA., PVC	FOOT	40			40	
81400400	CONCRETE HANDHOLE	EACH	8	4		4	
81500200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	1870	181		1689	
81702450	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 3-1/C NO. 10	FOOT	480	480			
82103900	LUMINAIRE, SODIUM VAPOR, MULTI-MOUNT, 250 WATT	EACH	4	4			
82500605	LIGHTING CONTROLLER PHOTOCCELL RELAY	EACH	1	1			
83800650	BREAKAWAY DEVICE, COUPLING, SS SCREEN	EACH	8	8			
85000500	MAINTENANCE OF EXISTING FLASHING BEACON INSTALLATION	EACH	1			1	
85800100	FLASHER CONTROLLER	EACH	1			1	
87200400	SPAN WIRE	FOOT	175			175	
87200500	TETHER WIRE	FOOT	175			175	
87301215	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 2C	FOOT	2254			2254	
87302245	ELECTRIC CABLE AERIAL SUSPENDED, SIGNAL, NO. 14 5C	FOOT	210	62		148	
87800415	CONCRETE FOUNDATION, TYPE E 36-INCH DIAMETER	FOOT	24	24			
89502300	REMOVE ELECTRIC CABLE FROM CONDUIT	FOOT	2036			2036	
89502380	REMOVE EXISTING HANDHOLE	EACH	1	1			
89502400	REMOVE EXISTING FLASHING BEACON INSTALLATION COMPLETE	EACH	4			4	
X0322189	REMOVE EXISTING LIGHTING SYSTEM NO SALVAGE	L SUM	1	1			
X0323148	REMOVE EXISTING SERVICE INSTALLATION TYPE A	EACH	1	0.5		0.5	
X3550705	BITUMINOUS BASE COURSE SUPERPAVE 10 1/4"	SQ YD	800				800
X4066416	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "C", N70	TON	398.5				398.5
X4066740	LEVELING BINDER (HAND METHOD), SUPERPAVE N70	TON	2.4				2.4
X4066770	LEVELING BINDER (MACHINE METHOD), SUPERPAVE N70	TON	229.9				229.9
X7015100	PORTABLE CHANGEABLE MESSAGE SIGN	EACH	2				2
X8801100	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 1-SECTION, POST MOUNTED	EACH	4			4	
X8801505	SIGNAL HEAD, POLYCARBONATE, LED, 4-FACE, 1-SECTION, SPAN WIRE MOUNTED	EACH	1			1	
Z0001050	AGGREGATE SUBGRADE 12"	SQ YD	780				780
Z0023600	FILLING EXISTING CULVERTS	EACH	1				1
X0324990	STEEL STRAIN POLE 45 FEET	EACH	2	2			

• SPECIALTY ITEMS

© SFTY-3C

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: VERT. _____ HORIZ. _____ DATE _____

DRAWN BY _____ CHECKED BY _____

2/11/2005 01:40:00 PM C:\PROJETS\66534\DRAWING\118N.DWG