


F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
74	(72-71R-3)	PEORIA	1360	16
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		



SUMMARY OF QUANTITIES				URBAN										90% FED 5% STATE 5% CITY		90% FED 10% CITY	
				CONSTRUCTION TYPE CODE													
CODE NO.	PAY ITEM	UNIT	TOTAL QUANTITY	ROADWAY 1000-2A	ROADWAY J000-2A	BRIDGE (1) X271-2A	BRIDGE (2) X281-2A	BRIDGE (3) X781-2A	BRIDGE (4) X028-2A	MINOR STRUCTURES (5) Y007	OVERHEAD SIGNS Y002-1C	LIGHTING Y030-1E	ITS Y035	TRAFFIC SIGNAL INTERCONNECT Y031-1F	TRAFFIC SIGNALS (6) Y031-1F	TRAFFIC SIGNALS (7) Y031-1F	TRAFFIC SIGNALS (8) Y031-1F
MX504002	FURNISHING AND ERECTING PRECAST PRESTRESSED CONCRETE BULB T-BEAMS 1829 MM	METER	1,445.1				598.6	846.5									
MX509025	ALUMINUM RAILING TYPE H (SPECIAL)	METER	666.0			68.0	183.5	257.0		157.5							
MX637105	CONCRETE BARRIER TRANSITION, SPECIAL	CU M	5.7		5.7												
MX637112	CONCRETE BARRIER TRANSITION (MODIFIED)	METER	19.0		19												
MX720100	TEMPORARY SIGN PANEL ASSEMBLY	SQ M	30.03	8.94	21.09												
MX721010	COMPOSITE TEMPORARY SIGN OVERLAY	SQ M	18.83	7.33	11.50												
MX733010	OVERHEAD SIGN STRUCTURE - CANTILEVER, TYPE II-C-S (0.90M x 1.68M)	METER	7.9							7.9							
MX817055	ELECTRIC CABLE IN CONDUIT, 600V 3-1/C NO. 6	METER	70													50	20
MX871055	FIBER OPTIC CABLE IN CONDUIT, NO62.5/125, MM12F SM12F	METER	2,165										2,165				
MX873027	ELECTRIC CABLE IN CONDUIT, GROUNDING, NO. 6 1C	METER	113.0									113.0					
MX877019	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 16.46 METER	EACH	1													1	
MX877020	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 16.76 METER	EACH	1													1	
MX878030	CONCRETE FOUNDATION, TYPE E 900MM DIAMETER	METER	23													13.2	10.2
#101655	BARRIER BASE	SQ M	104		104												
MZ017205	DOWEL BARS 38 MM	EACH	4,106	4,106													
MZ021500	EXPANSION JOINT 75MM	METER	47.5		47.5												
MZ022800	FENCE REMOVAL	METER	725.0		725.0												
MZ031105	MECHANICALLY STABILIZED EARTH RETAINING WALL	SQ M	2,141.2							2,141.2							
MZ031107	MECHANICALLY STABILIZED EARTH RETAINING WALL WITH CAST-IN-PLACE FACING	SQ M	2,304.4							2,304.4							
MZ047300	PROTECTIVE SHIELD	SQ M	1,444				978	466									
X0322906	WEEP HOLES CORED	EACH	84							84							
X0323336	LED SIGNAL FACE RETROFIT, RED BALL	EACH	14												14		
X0323337	LED SIGNAL FACE RETROFIT, GREEN BALL	EACH	14												14		
X0323339	LED SIGNAL FACE RETROFIT, WALK/DON'T WALK SPECIAL	EACH	2												2		
X0323481	VIDEO VEHICLE DETECTION, 4 CAMERAS	EACH	2													1	1
X0323418	LED SIGNAL FACE RETROFIT, YELLOW BALL	EACH	14												14		
X0323419	LED SIGNAL FACE RETROFIT, YELLOW ARROW	EACH	14												14		
X0323420	LED SIGNAL FACE RETROFIT, GREEN ARROW	EACH	14												14		
X0323483	LED SIGNAL FACE RETROFIT, RED ARROW	EACH	8												8		
Δ X0323677	STREET SWEEPING	hour	713		713												
X0323678	DUST CONTROL PADS	EACH	4		4												
X0323778	DRAINAGE SCUPPERS, TYPE 1	EACH	6			2	4										
X0323779	DRAINAGE SCUPPERS, TYPE 2	EACH	12				4	8									
X0323920	POLE MOUNTED EQUIPMENT CABINET, TYPE B	EACH	1										1				
X0323959	FORM LINER MOCKUP	EACH	1		1												

- SPECIALTY ITEMS
- + FUND CODE SFTY-3N
- ++ FUND CODE Y080
- +++ FUND CODE SFTY-3C
- Δ NON PARTICIPATING

- (1) RAMP A-3 OVER RAMP B-5, SN 072-0172
- (2) RAMPS B-3 & B-5 OVER US 150 & RAMP B-6, SN 072-0190 PROPOSED (EXISTING 072-0026)
- (3) RAMPS B-1 & B-4 OVER RAMPS A-3, B-3 & I-74, SN 072-0183 PROPOSED (EXISTING 072-0027)
- (4) NORTH AND SOUTH CULVERT EXTENSION, SN 072-2005 (072-2005), SN 072-2030, SN 072-2032
- (5) WALL 8, SN 072-8556, WALL 8A, SN 072-8557, WALL 9, SN 072-8558, WALL 10, SN 072-8559, WALL 11, SN 072-8560, WALL 12, SN 072-8561, SN 072-2504, WALL 12B, DIFFERENTIAL HEIGHT BARRIER, BOX CULVERT, WALL 18B, SN 072-8618 (072-2005); WALL 18C, SN 072-8619 (072-2005)
- (6) WAR MEMORIAL DRIVE / STERLING / GLEN
- (7) WAR MEMORIAL DRIVE / SCENIC DRIVE
- (8) SCENIC DRIVE / MALL ENTRANCE



REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

FAI ROUTE 74 (I-74)

DATE 11/23/04

DRAWN BY ROY
CHECKED BY LSA