F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
74	(72-7)R-3	PEORIA	1360	26
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

SET * - BILL OF MATERIALS FOR INFORMATION ONLY

				URBAN IM													
				90 % FED 10 % STATE											90 % FED 5 % STATE 5% CITY		90 % FED 10 % STATE
				ROADWAY T000-2A	ROADWAY J000-2A	BRIDGE (1) X271-2A	BRIDGE (2) X281-2A	BRIDGE (3) X781-2A	BRIDGE (4) X028-2A	MINOR STRUCTURES (5) Y007	OVERHEAD SIGNS Y002-1C	LIGHTING Y030-1E	ITS Y035	TRAFFIC SIGNAL INTER-CONNECT Y031-1F	TRAFFIC SIGNALS Y031-1F	TRAFFIC SIGNALS Y031-1F	TRAFFIC SIGNALS Y031-1F
CODE NO.	PAY ITEM	UNIT	TOTAL QUANTITY	(WMD)	(I-74)	A3	B3/B5	B1/B4	Culvert>20	Culvert<20, R Wall					War Memorial Dr/Sterling/Glen	War Memorial Dr/Scenic Dr	Scenic Dr/Mall Entrance
M5030125	NEOPRENE EXPANSION JOINT 100 MM	METER	51.9				25.5	26.4									
M5030350	CONCRETE STRUCTURES	CU M	2,971.4			77.2	962.4	1,215.0		716.8							
M5030360	CONCRETE SUPERSTRUCTURE	CU M	1,505.7			89.4	483.0	729.8		203.5							
M5030390	BRIDGE DECK GROOVING	SQ M	3,842			269	1,422	2,151									
M5030450	PROTECTIVE COAT	SQ M	4,916			338	1,856	2,722									
M5040914	FURNISHING AND ERECTING PRECAST PRESTRESSED CONCRETE I-BEAMS 914 MM	METER	123.4				123.4										
M5041067	FURNISHING AND ERECTING PRECAST PRESTRESSED CONCRETE I-BEAMS 1067 MM	METER	161.5					161.5									
M5050105	FURNISHING AND ERECTING STRUCTURAL STEEL	L SUM	1			1											
M5050405	FURNISHING AND ERECTING STRUCTURAL STEEL	KILOGRAM	4,190				1,370	2,820									
M5070209	UNTREATED TIMBER LAGGING	SQ M	170							170							
M5070211	FURNISHING SOLDIER PILES 6P SECTION0	METER	360							360							
M5080105	REINFORCEMENT BARS	KILOGRAM	174,010							174,010							
M5080205	REINFORCEMENT BARS, EPOXY COATED	KILOGRAM	418,380			15,580	116,920	178,860		107,020							
M5110100	SLOPE WALL 100 MM	SQ M	975			111	399	465									
M5120100	FURNISHING METAL PILE SHELLS 305 MM	METER	716.0				150.0	566.0									
M5120115	FURNISHING METAL PILE SHELLS 356 MM	METER	1,703.0			437.0		1,266.0									
M5120160	FURNISHING STEEL PILES HP 310 X 79	METER	1,491.0				828.0	663.0									
M5120315	DRIVING STEEL PILES	METER	1,491.0				828.0	663.0									
M5120340	DRIVING AND FILLING SHELLS	METER	2,419.0			437.0	150.0	1,832.0									
M5120460	TEST PILE STEEL HP 310 X 79	EACH	2				1	1									
M5401225	PRECAST CONCRETE BOX CULVERT 3.6 M X 3.0 M	METER	55.0							55.0							
M5403000	CONCRETE BOX CULVENTS	CU M	1,460.1							1,460.1							
M542E112	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 300MM	EACH	16	4	12												
M542E116	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 375MM	EACH	4	2	2												
M542E124	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 525MM	EACH	3	1	2												
M542E128	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 600MM	EACH	4	1	3												
M542E136	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 750MM	EACH	2	1	1												
M542E144	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 900MM	EACH	2		2												
M542E152	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 1200MM	EACH	2	2													
M5420035	GRATING FOR CONCRETE FLARED END SECTION 600MM	EACH	4	1	3												
M5420045	GRATING FOR CONCRETE FLARED END SECTION 750MM	EACH	2	1	1												
M5420055	GRATING FOR CONCRETE FLARED END SECTION 900MM	EACH	2		2												
M5420065	GRATING FOR CONCRETE FLARED END SECTION 1200MM	EACH	2	2													
M5500030	STORM SEWERS, CLASS A, TYPE 1 300MM	METER	706.5	334.0	372.5												

FOR INFORMATION ONLY

PARSONS TRANSPORTATION GROUP
Engineers and Planners

REVISIONS	
NAME	DATE
	01/31/05

ILLINOIS DEPARTMENT OF TRANSPORTATION

BILL OF MATERIALS
WAR MEMORIAL DRIVE
FAI ROUTE 74 (I-74) (WB)
PLAN SET #1

DRAWN BY CADD
DATE 11/12/04 CHECKED BY RSC

P:\643996\CIVIL\SHTWB\SQ0001-1AWB.DGN