

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
74	(72-TIR-3)	PEORIA	1360	68
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

BITUMINOUS PAVEMENT SCHEDULE																
LOCATION	STA.	TO	STA.	LENGTH M	WIDTH M	AREA (CADD CALCS) SQ M	AGGREGATE SUB-BASE M TON	BIT CONC BINDER COURSE SUPERPAVE, IL 19.0L, (LOW ESAL),150 MM M TON	BIT CONC BINDER COURSE SUPERPAVE, IL 19.0L, (LOW ESAL),100 MM M TON	POLYMERIZED BIT. CONC SURFACE COURSE, SUPERPAVE, MIX E, N70 M TON	POLYMERIZED BIT. CONC BINDER COURSE, SUPERPAVE, IL 19.0, N70 M TON	BITUMINOUS SHOULDERS 200 MM M TON	STRIP REFLECTIVE CRACK CONTROL TREATMENT METER	AGGREGATE (PRIME COAT) M TON 2kg/m2	BITUMINOUS MATERIAL PRIME COAT M TON 2l/m2	
STAGE 3																
SCENIC DRIVE	10+050.000	TO	10+109.196	59.20	16.77	992.72				90.16	135.24			1.47	1.89	
	10+109.196	TO	10+238.738	129.54	19.65	2,545.50				231.18	346.77		129.54	3.21	4.84	
	10+238.738	TO	10+288.277	49.54	14.40	713.36				64.79	97.18		99.078	1.23	1.36	
MALL ACCESS	9+936.557	TO	9+986.557	50.00	8.47	423.50				43.23	64.85		50.00	1.24	0.80	
BRANDYWINE DR	39+385.798	TO	39+458.410	80.00	Var	704.00				69.17	103.75		80.00	1.89	1.34	
GLEN AVENUE	101+038.000	TO	101+107.062	127.00	Var	3,322.32				109.81	164.71		254	3.00	6.31	
FRONTAGE RD	39+346.675	TO	39+391.760	45.08	Var	424.65				38.57	57.85		90.2	1.07	0.81	
STERLING AVE	100+910.908	TO	100+970.889	80.00	Var	1,892.00				171.83	257.75			1.72	3.59	
STAGE 3 SUBTOTAL:							68,812	14,196	12,707	3,717	5,575	1,471	2,168	42.4	260.4	
WB 1-74 SUBTOTAL:							29,841	14,196	-	-	-	-	-	-	-	78
RAMP SUBTOTAL:							38,971	-	12,707	-	-	-	-	-	101	
WAR MEM DR SUBTOTAL:							-	-	-	3,194	4,791	1,471	1,465	32	66.8	
SCENIC DR SUBTOTAL:							-	-	-	90	135	-	229	1	1.9	
MALL ACCESS SUBTOTAL:							-	-	-	43	65	-	50	1	0.8	
BRANDYWINE DR SUBTOTAL:							-	-	-	69	104	-	80	2	1.3	
GLEN AVE SUBTOTAL:							-	-	-	110	165	-	254	3	6.3	
FRONTAGE RD SUBTOTAL:							-	-	-	38.6	57.9	-	90.2	1.1	0.8	
STERLING AVE SUBTOTAL:							-	-	-	172	258	-	-	2	3.6	
TOTAL							68,812	14,196	12,707	3,717	5,575	1,471	2,168	42.4	260.4	
Total for 1000-2A							-	-	-	3,717	5,575	1,471	2,168	42.4	81.6	
Total for 1000-2A							-	26,904	-	-	-	-	-	-	-	178.8

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION BITUMINOUS PAVEMENT SCHEDULE FAI ROUTE 74 (I-74) (WB)
NAME	DATE	
		DRAWN BY CADD CHECKED BY RSC DATE 11/12/04

