


F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
74	(72-7)R-3	PEORIA	1360	84
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

TEMPORARY PAVEMENT MARKING SCHEDULE											
					TEMPORARY PAVEMENT MARKING TAPE, TYPE III					WET TEMPORARY PAVEMENT MARKING TAPE TYPE III	
					100 MM	100 MM	100 MM	100 MM	200 MM	100 MM	100 MM
FAI ROUTE 74					WHITE	YELLOW	WHITE	YELLOW	WHITE	WHITE	YELLOW
STAGE 3-1					SOLID	SOLID	SKIP-DASH	SKIP-DASH	SOLID	SOLID	SOLID
LOCATIONS	STATION	TO	STATION	LENGTH	M	M	M	M	M	M	M

I-74	141+250.000	TO	141+600.000								
	141+111		141+487	376.0	376.0						
	141+450		141+600	150.0	150.0	150.0	37.5				150.0
	141+487		141+600	113.0						113.0	
I-74	141+600.000	TO	141+950.000								
	141+600		141+650	50.0							50.0
	141+600		141+900	300.0					300.0		
	141+600		141+950	350.0	350.0	350.0	87.5				
	141+650		141+950	300.0	300.0						
	141+900		141+950	50.0	50.0						
I-74	141+950.000	TO	142+300.000								
	141+950		142+200	250.0			62.5				
	141+950		142+300	350.0	700.0	700.0					
	142+200		142+300	100.0	100.0						
I-74	142+300.000	TO	142+650.000								
	142+300		142+326	26.0			6.5				
	142+300		142+371	71.0	71.0						
	142+300		142+379	79.0	79.0						
	142+300		142+650	350.0		700.0					
	142+326		142+650	324.0	324.0						
	142+379		142+436	57.0					57.0		
	142+416		142+526	110.0	110.0						
	142+417		142+442	25.0	25.0						
	142+417		142+650	233.0	233.0						
	142+436		142+650	214.0	214.0						
	142+442		142+489	47.0					47.0		
	142+489		142+640	151.0	151.0						
	142+640		142+650	10.0		10.0					
I-74	142+650.000	TO	143+000.000								
	142+650		143+000	350.0	700.0	700.0					
	142+669		143+000	331.5			82.9				
RAMP A-4	10+029		10+190	161.0	161.0	161.0					
RAMP A-3	10+840		10+977	137.0	137.0	137.0					
I-74	143+000.000	TO	143+300.000								
	143+000		143+028	28.0	28.0						
	143+000		143+079	79.0		79.0					
	143+000		143+206	206.0	206.0						
	143+000		143+271	271.0	271.0						
	143+000		143+300	300.0		600.0	75.0				
	143+028		143+111	83.0					83.0		
	143+028		143+214	186.0	186.0						
	143+079		143+183	104.0	104.0						
	143+183		143+198	15.0					15.0		
	143+198		143+206	8.0	8.0						
	143+214		143+234	20.0					20.0		
	143+217		143+300	83.0			20.8				
	143+234		143+300	66.0	66.0						
RAMP A-2	10+287		10+411	124.0	124.0						
RAMP A-2	10+287		10+440	153.0	153.0						

STAGE 3-1 SUBTOTAL I-74	5,077.0	3,887.0	372.6	0.0	0.0	635.0	200.0
-------------------------	---------	---------	-------	-----	-----	-------	-------

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION TEMPORARY PAVEMENT MARKING FAI ROUTE 74 (I-74) (WB) SCHEDULES
NAME	DATE	



DATE 11/12/04  
DRAWN BY CADD  
CHECKED BY RSC