

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
74	(72-74R-3)	PEORIA	1360	103
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

TEMPORARY SIGN															
LOCATIONS	STA	TO	STA	OFFSET	RT/LT	TYPE	NO OF SIGN	SIZE SQ M	REINSTALL TEMPORARY SIGN PANEL ASSEMBLY	COMPOSITE TEMPORARY SIGN OVERLAY	SIGN PANEL OVERLAY, SPECIAL	TEMPORARY SIGN PANEL OVERLAY	TEMPORARY SIGN PANEL ASSEMBLY	REMOVE SIGN PANEL ASSEMBLY TYPE B	REMOVE SIGN PANEL ASSEMBLY TYPE A
									RSPA	CTSO	SPO(S)	TSP0	TSPA	RSPA	RSPA
									EA	SO M	SO M	SO M	SO M	EACH	EACH
STAGE 3-1, 3-2, 3-3 FAI ROUTE 74 WEST BOUND STAGE 3-1 WAR MEMORIAL DRIVE															
Sterling Avenue	100+950				RT	RSPA									1.00
North Mall	9+910				LT	RTSPA			1						
	9+970				LT	TSPA							0.68		
War Memorial	38+870				RT	RTSPA			1						
	38+990				RT	RTSPA			1						
	39+075				RT	TSPA							1.00		
					RT	RSPA								1.00	
	39+085				RT	RSPA								1.00	
	39+310				LT	TSPA							1.00		
					LT	RSPA								1.00	
	39+425				RT	RSPA								1.00	
	39+515				RT	CTSO			0.85					1.00	
	39+610				RT	TSP0							0.72		
	39+775				RT	CTSO			0.85						
	39+920				LT	TSPA							0.94		
	40+150				LT	RSPA								1.00	
					LT	CTSO			0.85						
	40+350				LT	SPO					0.18				
					LT	SPO					35.46				REMOVAL ONLY
					LT	CTSO			0.96						REMOVAL ONLY
	40+470				LT	SPO					0.90				REMOVAL ONLY
	40+620				LT	CTSO			2.50						REMOVAL ONLY
					LT	SPO						5.30			REMOVAL ONLY
					LT	CTSO			0.96				0.18		
					LT	SPO							7.84		REMOVAL ONLY
					LT	SPO									REMOVAL ONLY
SUBTOTAL BITUMINOUS									3	6.97	36.54	13.32	4.34	6.00	
STAGE 3-2.1, 3-2.2, 3-2.3 & 3-3 FAI ROUTE 74 WEST BOUND															
WB	142+240				LT	TSPA								1.40	
SUBTOTAL, CONCRETE									0	0.00	0.00	0.00	1.40	0.00	
STAGE 3-2 WAR MEMORIAL DRIVE															
War Memorial	39+555				RT	RTSPA			1						1.00
	39+620				RT	RSPA									1.00
SUBTOTAL BITUMINOUS									1	0.00	0.00	0.00	0.00	1.00	
STAGE 3-3 WAR MEMORIAL DRIVE															
Sterling Avenue	100+890				LT	SPO					0.68				
War Memorial	38+950				RT	TSPA							2.03		1.00
	39+075				LT	RSPA									
	39+075				LT	RTSPA			1						
	39+140				LT	TSPA							2.03		1.00
	39+590				RT	RSPA									1.00
					RT	RTSPA			1						1.00
North Mall	9+910				LT	RSPA									1.00
SUBTOTAL BITUMINOUS									2	0.00	0.68	0.00	4.06	3.00	
ROUNDED TOTAL															

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
TEMPORARY SIGN SCHEDULE
 FAI ROUTE 74 (I-74) (WB)
 DATE 11/12/04
 DRAWN BY CADD
 CHECKED BY RSC

