

**SUMMARY OF QUANTITIES**

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
811	(2250)I	CHAMPAIGN	22	5

CONTRACT NO. 70437

LOCATION OF WORK:

CHAMPAIGN COUNTY  
 URBAN  
 ROADWAY  
 FAP 811  
 STA: 5+55  
 STA: 48+71  
 10 80% STATE  
 90 10% FEDERAL  
 1000-2A

CONSTRUCTION TYPE CODE:

CODE NO	ITEM	UNIT	TOTAL QUANTITY	
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	664.0	664.0
40600300	AGGREGATE (PRIME COAT)	TON	14.0	14.0
40600990	TEMPORARY RAMP	SQ YD	329.0	329.0
44201789	CLASS D PATCHES, TYPE II, THICKNESS 12 INCH	SQ YD	88.0	88.0
60255500	MANHOLES TO BE ADJUSTED	EACH	4.0	4.0
67100100	MOBILIZATION	L SUM	1.0	1.0
70102632	TRAFFIC CONTROL AND PROTECTION, STANDARD 701602	L SUM	1.0	1.0
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1.0	1.0
70300100	SHORT-TERM PAVEMENT MARKING	FT	1,618.0	1,618.0
70301000	WORK-ZONE PAVEMENT MARKING REMOVAL	SQ FT	267.0	267.0
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	203.0	203.0
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	2,608.0	2,608.0
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	965.0	965.0
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	90.0	90.0
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	202.0	202.0
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	78.0	78.0
* 78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	78.0	78.0
78300500	PAINT PAVEMENT MARKING REMOVAL	SQ FT	473.0	473.0
* 88600100	DETECTOR LOOP, TYPE I	FOOT	1,002.0	1,002.0
X4066548	POLYMERIZED BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "F", N90	TON	651.0	651.0
X4401705	PARTIAL DEPTH REMOVAL	SQ YD	166.0	166.0
X4409400	BITUMINOUS SURFACE REMOVAL 1 3/4"	SQ YD	6,639.0	6,639.0
X7015005	CHANGEABLE MESSAGE SIGN	CAL DA	28.0	28.0
Z0004800	BITUMINOUS MIXTURE FOR PATCHING	TON	72.0	72.0

\* SPECIALITY ITEMS