

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
811	(2250)I	CHAMPAIGN	22	7

CONTRACT NO. 70437

## SCHEDULE OF QUANTITIES

### TABULATION OF PARTIAL DEPTH PAVEMENT PATCHING

STATION	DIRECTION	EXISTING OVERLAY THICKNESS  ( INCHES )	LANE	LENGTH  ( FT )	WIDTH  ( FT )	PARTIAL DEPTH REMOVAL  ( SQ. YDS. )	BITUMINOUS MIXTURE FOR PATCHING  ( TON )
5+25	NB	4.75	TURN	4	12	5.3	2.3
5+25	NB	4.75	PASSING	4	12	5.3	2.3
5+25	NB	4.75	DRIVING	4	12	5.3	2.3
5+25	SB	4.75	PASSING	4	12	5.3	2.3
5+25	SB	4.75	DRIVING	4	12	5.3	2.3
4+60	SB	4.75	PASSING	4	12	5.3	2.3
4+60	SB	4.75	DRIVING	4	12	5.3	2.3
51+27	NB	4.75	PASSING	6	12	8.0	3.5
51+27	NB	4.75	DRIVING	6	12	8.0	3.5
51+27	SB	4.75	PASSING	6	12	8.0	3.5
51+27	SB	4.75	DRIVING	6	12	8.0	3.5
50+86	NB	4.75	PASSING	4	12	5.3	2.3
50+86	SB	4.75	PASSING	4	12	5.3	2.3
50+86	SB	4.75	DRIVING	4	12	5.3	2.3
50+39	NB	4.75	PASSING	4	12	5.3	2.3
50+39	NB	4.75	DRIVING	4	12	5.3	2.3
50+39	SB	4.75	PASSING	4	12	5.3	2.3
50+39	SB	4.75	DRIVING	4	12	5.3	2.3
49+99	NB	4.75	PASSING	4	12	5.3	2.3
49+99	NB	4.75	DRIVING	4	12	5.3	2.3
49+60	NB	4.75	PASSING	6	12	8.0	3.5
49+60	NB	4.75	DRIVING	6	12	8.0	3.5
48+95	SB	4.75	PASSING	4	12	5.3	2.3
48+95	SB	4.75	DRIVING	4	12	5.3	2.3
48+71	NB	4.75	PASSING	4	12	5.3	2.3
48+71	NB	4.75	DRIVING	4	12	5.3	2.3
48+71	SB	4.75	PASSING	4	12	5.3	2.3
48+71	SB	4.75	DRIVING	4	12	5.3	2.3

SHEET TOTALS                      165.3                      71.7

USE                                      166                      72  
( SQ. YDS. )                      ( TON )