

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
116	*	**	14	4

CONTRACT NO. 70447
 * D-5 CONTRACT MAINTENANCE 2005-8
 ** COLES COUNTY

SUMMARY OF QUANTITIES

LOCATION OF WORK:

FAP 116 (IL. 130)
 COLES COUNTY
 STATION 254+35
 TO
 279+35
 RURAL TWO LANE
 100% STATE

CONSTRUCTION TYPE CODE:

1000

CODE NO	ITEM	UNIT	TOTAL QUANTITY
35101400	AGGREGATE BASE COURSE, TYPE B	TON	23.0
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	750.0
40600300	AGGREGATE PRIME COAT	TON	15.0
40600980	BITUMINOUS SURFACE REMOVAL - BUTT JOINT	SQ. YD.	174.0
40600990	TEMPORARY RAMP	SQ. YD.	30.0
40800010	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	46.0
40800030	AGGREGATE PRIME COAT	TON	2.0
40800040	INCIDENTAL BITUMINOUS SURFACING	TON	32.0
44000025	BITUMINOUS SURFACE REMOVAL (SPECIAL)	SQ. YD.	140.0
44000030	BITUMINOUS SURFACE REMOVAL (VARIABLE DEPTH)	SQ. YD.	7,222.0
44201785	CLASS D PATCHES, TYPE I, 12 INCH	SQ. YD.	4.0
44201789	CLASS D PATCHES, TYPE II, 12 INCH	SQ. YD.	57.0
44201794	CLASS D PATCHES, TYPE III, 12 INCH	SQ. YD.	135.0
44201796	CLASS D PATCHES, TYPE IV, 12 INCH	SQ. YD.	561.0
48101200	AGGREGATE SHOULDERS, TYPE B	TON	175.0
67100100	MOBILIZATION	L SUM	1.0
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1.0
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1.0
70300100	SHORT - TERM PAVEMENT MARKING	FOOT	1,000.0
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	167.0
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	5,625.0
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	32.0
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	32.0
X4066414	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX C, N 50	TON	610.0

* SPECIALITY ITEMS