

ITEM NO. 72000100 SIGN PANEL - TYPE 1

LOCATION	TYPE	SQ FT
END OF SCHNEIDER (RT. STA. 223+85)	R11-I100	7.5
TOTAL = 7.5		

ITEM NO. 72500100 OBJECT MARKER - TYPE 1 (RED)

LOCATION	EACH
END OF SCHNEIDER (RT. STA. 223+85)	2
TOTAL = 2	

ITEM NO. 73000100 WOOD SIGN SUPPORT

LOCATION	FOOT
END OF SCHNEIDER (RT. STA. 223+85)	3 POST @ 12' 36
TOTAL = 36	

- ITEM NO. 70300100 SHORT-TERM PAVEMENT MARKING
- ITEM NO. 70300230 TEMPORARY PAVEMENT MARKING - LINE 5"
- ITEM NO. 70300260 TEMPORARY PAVEMENT MARKING - LINE 12"
- ITEM NO. 70301000 WORK ZONE PAVEMENT MARKING REMOVAL
- ITEM NO. 78001120 PAINT PAVEMENT MARKING - LINE 5"
- ITEM NO. 78003120 PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 5"
- ITEM NO. 78003150 PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 12"
- ITEM NO. 78008220 POLYUREA PAVEMENT MARKING TYPE I - LINE 5"
- ITEM NO. 78008230 POLYUREA PAVEMENT MARKING TYPE I - LINE 6"
- ITEM NO. 78100100 RAISED REFLECTIVE PAVEMENT MARKER
- ITEM NO. 78300200 RAISED REFLECTIVE PAVEMENT MARKER REMOVAL

PAVEMENT MARKING SCHEDULE	2 LANE SECTION		4 LANE CENTER OF PAVEMENT		GORE-TRANS 4 LANE TO 2 LANE		4 LANE SECTION										
	SHORT-TERM PAVEMENT MARKING	TEMPORARY PAVEMENT MARKING-LINE 5"	TEMPORARY PAVEMENT MARKING-LINE 12"	WORK ZONE PAVEMENT MARKING REMOVAL	PAINT PAVEMENT MARKING-LINE 5" WHITE EDGELINES	PAINT PAVEMENT MARKING-LINE 5" YELLOW SKIP-DASH	PAINT PAVEMENT MARKING-LINE 5" YELLOW NO-PASSING	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 5" WHITE SKIP-DASH	POLYUREA PAVEMENT MARKING TYPE I LINE 5" YELLOW EDGELINES	POLYUREA PAVEMENT MARKING TYPE I LINE 6" WHITE EDGELINES LT-TURN	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 12" YELLOW DIAGONALS	POLYUREA PAVEMENT MARKING TYPE I LINE 5" WHITE EDGELINES	POLYUREA PAVEMENT MARKING TYPE I LINE 5" YELLOW EDGELINES	RAISED REFLECTIVE PAVEMENT MARKER ONE-WAY AMBER	RAISED REFLECTIVE PAVEMENT MARKER ONE-WAY CRYSTAL	RAISED REFLECTIVE PAVEMENT MARKER TWO-WAY AMBER	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL
	FOOT	FOOT	FOOT	SQ. FT.	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	EACH	EACH	EACH	EACH
STA. 64+69.41 TO STA. 76+00 (N.B.)	336	2640		1137				280				1280	1080		14		14
STA. 66+90.50 TO STA. 76+00 (S.B.)	276	1950		844				230				860	860		16*		16
STA. 76+00 TO STA. 105+85 (N.B.)	900	6720		2900				750				2985	2985		37		37
STA. 76+00 TO STA. 108+40 (S.B.)	972	7490		3229				810				3440	3240		46*		46
STA. 105+85 TO STA. 111+92 (N.B.)	180	1400		603					795			605		15			15
STA. 108+40 TO STA. 112+50 (S.B.)	120	1230	180	526					820	180		410		10			10
STA. 111+92 TO STA. 117+07.42 (N.B. ENDS)	156	1545		661					1030			515		10		3	13
STA. 112+50 TO STA. 117+68.70 (S.B.)	156	1545	75	661					950	40	75	555		10		3	13
STA. 117+68.70 TO STA. 118+28.70 (S.B.)	24	240		103					120			120				1	1
(EQUATION)																	
STA. 98+15.41 TO STA. 122+00	720	5370		2318	4770	600										30	30
STA. 122+00 TO STA. 142+85	624	7010		2990	4170	450	2390									26	26
STA. 142+85 TO STA. 179+97.59	1116	8355		3605	7425	930										46	46
(BRIDGE OMISSION)																	
STA. 189+09.27 TO STA. 215+80	804	6010		2593	5340	670										33	33
STA. 215+80 TO STA. 235+15	576	6580		2806	3870	390	2320									24	24
STA. 235+15 TO STA. 265+05.65	900	6730		2904	5980	750										37	37
(EQUATION)																	
STA. 40+88.70 TO STA. 48+35	228	1680		725	1490	190										9	9
STA. 48+35 TO STA. 53+45	156	1660		709	1020	130	510									6	6
STA. 53+45 TO STA. 55+00	48	350		151	310	40										2	2
+12" DIAGONALS				255													
TOTAL	8292	68505	255	29720	34375	4150	5220	2070	3715	40	255	10770	8165	45	113	220	378

\* INCLUDES LEFT TURN LANES FOR COMM./S.R. @ STA. 76+00

ITEM NO. 78003100 PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LETTERS AND SYMBOLS

LOCATION	TYPE	SQ. FT.
RT. STA. 113+00 (S.B.)	LT. TURN ARROW	15.6
TOTAL = 15.6		

REVISIONS	
NAME	DATE
GUARDRAIL/TMJ	02-08-05

ILLINOIS DEPARTMENT OF TRANSPORTATION

## SCHEDULE OF QUANTITIES

SCALE: VERT.      DRAWN BY TMJ  
 HORIZ.            CHECKED BY MCB  
 DATE 02-08-05

c:\projects\ed52901\jda\_fina1.12-20-04\_schedules.dgn  
 2/10/2005  
 \*REF01